# DELHI DEVELOPMENT AUTHORITY QUTAB GOLF COURSE PRESS ENCLAVE ROAD, NEW DELHI – 110017

F2 (33)/QGC/DDA/Civil/2009-10/ 1080

#### NOTICE INVITING QUOTATION NO. 125

Name of Work: - Up-gradation/Renovation of existing facilities i.e. Civil, Electricals, Horticulture and Sports

## SH: - Construction of Staff Toilet near tank at QGC.

S. No.	Description	Qty.
1.	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in	15.25 Cum
	foundation trenches or drains (not exceeding 1.5m in width or 10 Sqm. on plan)	
	including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out	
	the excavated soil and disposal of surplus excavated soil as directed, within a lead of	
	50m.	
2.	Providing & Laying in position cement concrete of specified grade excluding the cost of	
	centering and shuttering - All work upto plinth level.	2.71.0
	a) 1:5:10 (1cement:5 coarse sand 10: graded stone aggregate 40 mm nominal size).	3 71 Cum
. 3.	b) 1:2:4 (1cement 2: coarse sand 4: graded stone aggregate 20 mm nominal size).	2 89 Cum
, 3.	Brick work with F.P.S. brick of class designation 75 in foundation and plinth in	9.52 Cum
4.	a) Cement Mortar 1:6 (1 cement: 6 coarse sand)	
4.	Brick work with F.P.S. bricks of class designation 75 in super structure above plinth level	
	upto floor five level in all shapes and sizes in:	16 50 0
5.	a) Cement mortar 1:6 (1 cement:6 coarse sand)	16.58 Cum
3.	Providing & laying damp-proof course 50 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	6.1. Com
6.	Applying a coat of residual petroleum bitumen of penetration 80/100 of approved quality	6.14 Sqm.
0.	using 1.7 kg. per square meter on damp proof course after cleaning the surface with	6.14 Sqm.
	brushes and finally with a piece of cloth lightly soaked in kerosene oil.	0.1 · Sqm.
7.	Supplying and Stacking of good earth at site including royalty, carriage, loading,	
/.	unloading upto 20 Km lead (Earth measured in stakes will be reduced by 20% for	3.78 Cum
	payment).	3.75 Cum
8.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations	3.78 Cum.
О.	etc. in layers not exceeding 20cm in depth consolidating such deposited layer by	3.7 Cum.
	ramming and watering, lead upto 50m and lift upto 1.5m.	
9.	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto	
, .	15 <sup>0</sup> landing, balconies, shelves, chajjas, lintels, bands, plain windows sills, staircases and	
	spiral stair cases upto floor five level excluding the cost of centering, shuttering, finishing	0.43 Cum
	and reinforcement with 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate 20 mm	
	size).	
10.	Centering and shuttering including strutting, propping etc. and removal of form for:	
	a) Lintels, beams, plinth beams, girders, bressumers and cantilevers.	4.7 Sqm.
11.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in	
	position and binding all complete.	
	(a) Thermo-Mechanically Treated bars.	64.50 Kg.

Contd.....2/n

12.	15 mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement : 6 coarse sand).	96.∄5 Sqm.
. 13.	Washed stone grit plaster on exterior walls of height upto 10 m above level in two layers under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand) furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 kg. of cement per square meter, top layer 15 mm cement plaster 1: ½:2 (1 cement : ½ coarse sand : 2 stone chipping 10 mm nominal size) in panels with groove all around as per approved pattern including scrubbing and washing, the top layer with brushes and water to expose the stone chippings, complete as per specification and direction of Engineer-in-charge. (Payment for providing grooves shall be made separately).	42. 5 Sqm.
14.	Foaming groove of uniform size in the top payer of washed stone grit plaster as per approved pattern using wooden battens, nailed to the under layer including removal of wooden battens, repair to the edges of panels and finishing the groove complete as per specification and directions of Engineer-in-charge.  a) 15 mm wide and 15 mm deep grove	144.35 Metre
15.	Providing and fixing aluminium window with extruded built up standard tubular section/appropriate Z- section & other section 2.5" x 1.5" of approved make conforming to IS 733 & IS 1285 for fixed portion anodized aluminium with rawl plugs and screws with 5 mm one way glass all complete as per direction of In-charge.	12.0( Sqft.
. 16.	Structural steel work riveted, bolted of welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	454.74 Kg.
17.	Providing and fixing ISI marked flush door shutters conforming to IS 2202 (Part I) non-decorative type, core of block board construction with frame of 1 <sup>st</sup> class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:  a) 35 mm thick including ISI marked stainless steel butt hinges with necessary screws.	6.93 3qm.
18.	Providing and fixing aluminium sliding door bolt ISI marked anodized (Anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete.  a) 300 x 16 mm	4.00 Vos.
19.	Providing and fixing aluminium handles ISI marked anodized (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade with necessary screws etc. complete.  a) 125 mm	8.00 Vos.
- 20.	Providing and fixing aluminium tower bolts ISI marked anodized (anodic coating not less than AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete.  a) 250 x 10 mm	4.00 Nos.
21	Providing and fixing G. I. pipes complete with G. I. fittings and clamps, including cutting and making good the wall etc.  a) 15 mm dia nominal bore b) 20 mm dia nominal bore	24 Metre 84 Metre
22.	Providing and fixing brass stop cock of approved quality.  a) 20 mm dia nominal bore	02 Nos.
23.	Providing and fixing G. I. union in G. I. pipe line including cutting and threading the pipe and making long screws etc. complete (New work).  a) 15 mm nominal bore b) 20 mm nominal bore Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI:	8.00 Nos. 10 Nos. 1000
24.	12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and over flow pipes but without fittings and the base support for tank (Sintex, Electroplast, Star, Lotus or equivalent having valid ISI license).	1000

25.	Providing and fixing ball valve (brass) of approved quality, high or low pressure with	1.00 No.
	plastic floats complete.	
	a) 20 mm nominal bore	
26.	Painting with synthetic enamel paint of approved brand and manufacture to give an even	32.03 3gm.
	shade.	Î
	a) Two or more coats on new work	

#### **Conditions:-**

- 1. The work should be completed as per the direction of in-charge.
- 2. The work shall be completed within 15 days from the date of receipt of the order.
- 3. The contractor will have to make his own arrangement of T & P and cartage etc.
- 4. Payment will be made after entire satisfaction of Secretary, QGC.
- 5. Any conditional quotations shall be summarily rejected.
- 6. Necessary statutory deduction will be made as applicable.
- 7. The validity of the quotation is 60 days from the date of opening of the sealed quotations.
- 8. Debarred agency/or individual shall not be permitted to participate in the tendering process.
- 9. Any individual who has been debarred is not permitted to take part in any negotiations or represent an agency even if he holds a power of attorney on the agencies behalf. Any agency engaging debarred persons is also liable to debarring.
- 10. The quotationer should be registered with the sales Tax Deptt. (W.C Cell) Govt. of GNCTD and supposed to furnish a copy of Sales Tax Registration (W.C. Cell) & Sales Tax Clearance Cortificate and attach the same alongwith quotation otherwise the quotation may not be considered and liable to be rejected.
- 11. "Quoted Rates should be inclusive of all taxes/levies including service tax payable under respective statutes. DDA will not entertain any claim, whatsoever, in this respect".

(Brig. Virendra Kumar) Secretary, QGC

## Copy to:-

- 1. Director, (Sports) for information please.
- 2. Director (System), DDA through email ddatender@dda.org.in
- 3. Sr. A. O. (Sports), DDA
- 4. Secretaries of all Sports Complexes with request to place it on notice board.
- 5. Secretary/DDA Contractor's Welfare Association, E-18, Vikas Kutir, New Delhi 02.
- 6. Secretary/DDA Builders Association, Vikas Kutir, New Delhi 02.
- 7. AAO, QGC
- 8. J. E. (Civil), QGC
- 9. Asstt. Cashier, QGC
- 10. Notice Board, QGC

