

In Lieu of PWD-6
15/EE/WD8/2009-10
Form applicable-PWD-8

0 DELHI DEVELOPOMENT AUTHORITY
WESTERN DIVISION-8
CENTRAL NURSERY, SECTOR-5, DWARKA,
NEW DELHI-75

NOTICE INVITING TENDER

Sealed item rate tenders are invited for the following works from the approved and eligible contractors in DDA up to 3.00 P.M. on the date indicated against each work which shall be opened on the same day at 3.30 P.M. at Vikas Minar, DDA, New Delhi by the Ex. Engineer/WD-8/DDA in the presence of intending tenderers /their authorized representatives.

The enlistment of contractors should be valid on the last date of sale of tenders.

In case the last date of sale of tender is extended, the enlistment of contractor should be valid on the original date of sale of tenders.


In case both the last date of receipt of application and sale of tenders are extended, the enlistment of contractor should be valid on either of the two date i.e. original date of sale of tender or on the extended date of sale of tenders.

The tender documents can be obtained on any working day from the CAU/DWK., DDA & sale counter, Vikas Minar between 11.00 A.M. to 3.00 P.M. on payment of cost of tender (non-refundable) mentioned against each work on production of valid enlistment certificate. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The manner of submission of tender/opening of the same and entry of contractor's /their authorized representative to the place of opening shall be as provided in clause 3(a), (b) & (c) of PWD-6 forming part of the tender documents.

The earnest money should be deposited along with tender documents in Receipt Treasury Challan /C.D.R./F.D.R./D.D. of a scheduled bank issued in favour of Sr. A.O./CAU, Dwarka, DDA, New Delhi. It should, however, be ensured that FDR/pay Order is valid for a period of six months or more after last date of receipt of tender. The tender of the Agency who does not enclose the earnest money in the prescribed manner shall be summarily rejected.

S.No.	Name of work	Estimated cost Earnest Money	Cost _____ of Tender Time allowed	Last date of sale Date of opening
1	M/O Various colonies under DwarkaZone Nazul A/c-II.SH: Making connection of missing link of C.I. water line near M.C.D.office atT- Junction of A & B blockSec. 8, Dwarka. NIT No.31/EE/WD-8/DDA/09-10.	<u>Rs.1,84,461.00</u> Rs3,689.00-00	<u>Rs.520.00</u> 1 Months.	11.01.2010 ----- 14.01.2010


Executive Engineer
Western Division-8

No: F.81 (2)/A/Cs/WD-8/DDA/2009-10/ 1806
Copy to:-

Dated: 28/12/09

18. CE(Dwarka)/DDA.
19. CE(QC)/DDA, Vikas Sadan.
20. SE(CC-13)/DWK/DDA.
21. All EE's/DDA/Dwarka.
22. F.O. to C.E(Dwarka)/DDA.
23. A.O.(CAU)Dwarka/DDA.
24. AE-(P), WD-8/DDA.
25. Commissioner, Works Contract Cell, Sale Tax Deptt. Sale Tax Building, ITO, New Delhi.
26. Trans Yamuna Contractor association (Regd) 11-12, Vir Sawakar Market (Budh Bazar)Gandhi Nagar, New Delhi-110031(UPC).
27. Delhi Contractors Building association (Regd) .No.5503, Ch. Bhim Singh Road, Delhi(Ch. Prem Raj Bhawan, New Chandrawal Road (UPC).
28. Delhi Contractors Welfare association (Regd) 2618, Gali Dharamshala wali, kali Masjid, Turkman gate, New Delh I (UPC).
29. Indian Contractor Association (Regd) G-80/20, Main Bazar Laxmi Nagar, Delhi-110092 (UPC).
30. Delhi Contractor's Welfare Association, 306 Masjid Moth, South Extension Part-2 New Delhi-110049 (UPC).
31. Work File.
32. DDA website ddatender@dda.org.in.
33. Tender Clerk, Vikas Minar.
34. Tender Clerk, CAU (DWK).

Executive Engineer
Western Division-8

SCHEDULE OF QUANTITIES

Name of Work:
S.H.

M/O various colonies of Dwarka Zone under Nazul A/C-II
Making connection of missing link of C.I. Water line Near M.C.D. office at T-Junction of A & B Block Sec. -8, Dwarka

S.No.	Description of Item	Qty.	Unit	Rate	Amount
1.	Excavation trenches of required width of pipes cables. etc. including excavation for socked and dressing of sides, ramming of bottom depth upto 1.5m including getting out the excavated soil and then returning the soil as required in layers not exceeding each deposited layer by ramming, watering etc. and disposal of surplus excavated soil as directed within a lead of 50M all kinds of soil.				
	a) Pipes, cable etc. exceeding 80mm dia but not exceeding 300mm dia.	132.00 Mtr.	Mtr.		
2.	Providing and laying S & S centrifugally cast (spun)iron pipes (Class LA) conforming to IS : 1536				
	a) 100mm dia pipe	55.00 Mtr.	Mtr.		
	b) 150mm dia pipe	75.00 Mtr.	Mtr.		
	c) 200mm dia pipe	2.00 Mtr.	Mtr.		
3.	Supply pig lead at site of work.	1.00 Qtl.	Qtl.		
4.	Providing lead caulked joints to spun iron or C.I. pipes and specials including testing of joints but excluding the cost of pig lead.				
	a) 100mm dia pipe	12 Nos.	Each		
	b) 150mm dia pipe	8 Nos.	Each		

	c) 200mm dia pipe	4 Nos.	Each		
5.	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately)				
	a) 100mm diameter (Class-II)	1No.	Each		
	b) 150mm diameter (Class-II)	1 No.	Each		
6.	Providing & laying flanged C.I. standard specials such as tees, bends, collars, tapers, caps etc. suitable for flanged jointing as per IS: 1538.				
	a) Upto 300mm dia.	1.00 Qtl.	Qtl.		
7.	Constructing masonry chamber 90x90x100 cm inside with 75 class designation brick work in cement mortar 1:4 (1 Cement : 4 Coarse Sand) for sluice valve, with C.I. surface box 100mm diameter, 160mm bottom diameter and 180mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1Cement: 2 Coarse Sand : 4 Graded Stone aggregate 20mm nominal size) and inside plastering with cement mortar 1: 3 (1 Cement : 3 Coarse Sand) 12mm thick finished with floating coat of neat cement complete as per standard design. a) With F.P.S. bricks	2 Nos.	Each		
8.	Earth work in excavation by mechanical mean (Hydraulic excavator)/manual means over areas (exceeding 30cm depth, 1.5m in width as well as 10 sqm. On plan) including disposal of excavated earth lead upto 50m and lift upto 1.5m, disposed earth to be leveled and neatly dressed. a) All kinds of soil.	10.00 Cum	Cum		

9.	Providing and laying S & S C.I. standard specials such as tees, bends, collars, tapers, caps etc. (heavy class) a) Upto 300mm dia.	3.00 Qtl.	Qtl.		
10.	Labour for cutting C.I. Pipe with steel saw. a) 100mm diameter C.I. Pipe.	4 Nos.	Each Cut		
	b) 150mm diameter C.I. Pipe.	4 Nos.	Each Cut		
	c) 200mm diameter C.I. Pipe.	4 Nos.	Each Cut		
11.	Providing flanged joints to double flanged C.I./D.I. pipes and specials including testing of joints. a) 100mm diameter pipe.	2 Nos.	Each		
	b) 150mm diameter pipe.	2 Nos.	Each		
12.	Providing push-on-joints to centrifugally (spun) cast iron pipes or ductile iron pipes including testing of joints and including the cost of rubber gasket: a) 100mm dia pipe.	13.00	Joint		
	b) 150mm dia pipe	19.00	Joint		