

**OFFICE OF THE EXECUTIVE ENGINEER  
WESTERN DIVISION NO.13:DDA  
LAKKAR MANDI:KIRTI NAGAR:N.DELHI**

NIT No.48/EE/WD-13/DDA/2010-11.

**TENDER NOTICE**

Sealed item rate tender are re- invited for the following work by the Ex.Engineer:WD-13:DDA., Lakkar Mandi:Kirti Nagar:N.Delhi-15 up to 3.00P.M. on 6.01.2011 on behalf of the DDA from the specialized contractors which shall be opened on the same day at 3.30 P.M. by the EE/WD-13/DDA at Ground Floor, Vikas Minar, ITO., DDA. office New Delhi in the presence of intending purchaser or their authorized representatives.

The tender documents can be had any working day up to 3.00P.M. from the **Office of Executive Engineer/EE/WD-13/DDA Lakkar Mandi Kirti Nagar, New Delhi-15** between 11.00A.M. to 3.00P.M. on payment of the cost of the tender mentioned against each work(non-refundable). Sales of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender.

The manner of submission of tender opening of the same and entry of contractors/their authorized representative, the place of opening shall be as provided in clause 3 (a), (b) & (c) of PWD-6 forming part of the tender documents.

The tender shall be accompanied with earnest money in cash (upto Rs.10,000)/Receipt Treasury challan/CDR/FDR/DD of a scheduled bank in favour of Sr. A.O./CAU/DWK/DDA., New Delhi.

NIT No.	Name of work.	<u>Estt. Cost.</u>	<u>Last date of sale.</u>
		<u>Earnest Money.</u> Cost of Tender.	<u>Date of Opening.</u> Time allowed.
48/EE/ WD-13/ DDA/ 2010-11	M/o completed scheme under nazul A/c-II S.W.Z. SH:-Replacement of sign boards and direction boards in Jheel Wala Park at Hari Nagar G-8 area Rajouri Garden(under special repair).		
		<u>Rs.2,99,493/-</u>	<u>03.01.2011</u>
		<u>Rs.5,990/-</u>	<u>06.01.2011</u>
		<u>Rs.525/-</u>	<u>One Months.</u>

**CONDITION:-**

The tender documents shall be issued from the office of EE/WD-13/DDA to those agencies who fulfill the following condition


i)Three similar works, each of value not less than 40% of the estimated cost put to tender.

Or

ii)Two similar works, each of value not less than 60% of the estimated cost put to tender.

Or

iii)One similar work of value not less than 80% of the estimated cost put to tender,  
in the last 7 year ending on the last day of the previous month in which the tenders are invited.

  
**Executive Engineer  
WD-13:DDA**

### Schedule of Quantities

Name of work : M/o Completed Scheme under Nazual A/c-II SWZ  
SH Replacement of Sign boards and Direction Boards in Jheel Wala Park at Hari Nagar  
G-8 area Rajouri Garden (under special repairs)

S no	Description of Items	Qty	Unit	Rate	Amount
1	Excavation holes upto 0.5 m <sup>3</sup> i/c getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth including consolidating of surplus excavated soil as directed within a lead of 50m and lift upto 1.5m A) All kinds of soil	46.0 Nos	Each		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- all work up to plinth level. A) 1:3:6 (1cement : 3 c.sand : 6 grade stone agg. 20 mm nominal size)	2.50	m <sup>3</sup>		
3	Structural steel work riveted, bolted or welded in built up section trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	2105.0	Kg		
4	Manufacturing supplying and fixing retro reflective overhead signage boards made up of 2mm thick aluminium sheet face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type-III of ASTM-D-4956-01 as approved by Engineer-in-charge letters, borders etc, as per IRC:67-2001 in silver white with blue colour back ground and with high intensity grade pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II	47.90	m <sup>2</sup>		

Blank  
Ar

A - 2  
C -  
D -  
OW - } 412

JE G. / DN

OK  
A. E. C.

EE / 10.12.13

ii) Two similar works, each of value not less than 60% of the estimated cost put to tender.

Or


of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets, or bolts & nuts @ 300mm centre to center all along the periphery as well as in to vertical rows along with theft resistant measures including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer in charge. (Structural frame work including M.S plate to be provided separately. Rectangular area of the sheet only shall be measured for payment).

A) Over head informantor road signage.


Plate  
A2

Rs. 2,99,493/-

A - 2  
C - }  
D - } Nil  
OW - }

  
JE(T)/ D/Man

  
AE(P)/ WD-13/DDA

  
EE/WD-13/DDA