

DELHI DEVELOPMENT AUTHORITY  
OFFICE OF THE EXECUTIVE ENGINEER  
WD-5/N.Z./1<sup>ST</sup> FLOOR, V. MINAR/ND-2

No. : F.5(Misc.)WD-5/DDA/0-1/3-

DT: 20-12-10

To,

The Deputy Director (System),  
D.D.A., 1<sup>st</sup> Floor, Vikas Sadan,  
INA, New Delhi

Sub. : Uploading of the documents on DDA Website on behalf of WD-5.

Sir,

Please find enclosed herewith the following documents for uploading on DDA website

*Tender documents for MIT NO-53,52/WD5/*  
*DDA/2010-11 vide this office letter no*  
*F-5(38)WD5/DDA/2010-11/5277 dt 18<sup>12</sup>/<sub>10</sub> along with*  
*Schedule*  
*MIT NO. 54/EE/WD5/DDA/2010-11 along with*  
*Schedule vide this office letter no*  
*F-5(38)WD5/DDA/2010-11/5267 dt 16<sup>12</sup>/<sub>10</sub>*

Executive Engineer  
Western Division-5  
D.D.A.  
20/12/10

**DELHI DEVELOPMENT AUTHORITY  
OFFICE OF THE EXECUTIVE ENGINEER  
WESTERN DIVISION NO.-5 (NORTH ZONE)  
~~PRESS~~ TENDER NOTICE**

Sealed Item rate tenders for the following works are invited by the Executive Engineer/WD-5/DDA 1<sup>st</sup> Floor Vikas Minar, New Delhi for the following works from the approved and eligible contractors of DDA, CPWD, Civil Wing of P & T, M.E.S. & Railways upto 3.00 P.M. which shall be opened on the same day at 3.30 P.M. at Ground Floor, DDA Office Vikas Minar, New Delhi in the presence of intending tenderers or their authorised representatives on the dates indicating against the each work. For eligibility criteria, please see foot note-I.

The tender documents can be obtained on any working day from the Sr.A.O. (CAU) NZ, DDA, Ashok Vihar New Delhi and Tender Sale Counter, Vikas Minar, New Delhi between 11.00 A.M. to 3.00 P.M. on payment of cost of tender (non-refundable) in cash as mentioned against each work on production of valid certificate of registration with works contract Sales Tax deptt. of the GNCTD and the tax Clearance Certificate on Form-XI. Sale of tender forms will be stopped 4 days (including the date of opening before the date fixed for opening of tender documents.

The manner of submission of tenders, opening of the same entry of contractors/their authorized representative of the place of opening shall be as provided in clauses 3 (a), (b) & (c) of PWD-6 forming part of the tender documents.

S. No.	NIT No.	Name of work	Estt. Cost Earnest Money Cost of Tender	Last date of sale Date of opening Time allowed
1.	53/EE/WD-5/ DDA/2010-11	M/O Completed Scheme under Nazul A/C-II of North Zone. SH: Providing and laying G.I. Pipe Line in Rock Garden Patel Nagar.	Rs.8,10,046/- Rs.16,201/- Rs.500/- + 5% Vat	24.12.2010 29.12.2010 2 months
2.	52/EE/WD-5/ DDA/2010-11	M/O Completed Scheme under Nazul A/C-II of North Zone. SH: Repair of boundary wall with chain link fencing of R-Block, Rajender Nagar (Ridge area).	Rs.7,08,620/- Rs.14,172/- Rs.500/- + 5% Vat	24.12.2010 29.12.2010 1 month

**Foot Note-I**

- c) For works costing upto Rs. 25.00 lacs, tenders shall be issued to contractor(s) registered with DDA only.

**Foot Note-II**

**Special condition for work at serial no. \_\_\_\_\_**

- a) The tenders are open for Non - registered specialized contractors also in addition to registered contractors;
- b) The satisfactorily completion of atleast two works of similar nature/class, each costing not less than 50% of the estimated cost [gross] or one work of similar nature/class, costing not less than 100% of the estimated cost [gross] in Govt. Department of the proposed work during the last five years; Being specialized nature of work, tender in respect of works mentioned at serial no. \_\_\_\_\_ will be issued by Sr. A.O. (CAU)/NZ/DDA, Ashok Vihar, Phase - I, Delhi - 110052 or tender clerk, Central Tender Unit, Vikas Minar, New Delhi - 02 after verification of application by the concerned Executive Engineer.

Executive Engineer  
Western Division-5  
DDA

No. F5 (38) WD-5/DDA/2010-11

5277

Dated :- 18/14/10

**Copy to:-**

- 25 Chief Engineer (NZ), DDA.
- 26 SE/CC-7/DDA.
- 27 Director (System), DDA, 'B' Block Vikas Sadan, DDA, for displaying the NIT on DDA web site.
- 28 F.O. to CE (NZ), DDA.
- 29 Sr. A.O. (W)-II, DDA, Vikas Sadan, New Delhi.
- 30 A.O. (CAU) NZ, DDA.
- 31 Ex. Engineer/QC. IV. DDA, Vikas Sadan.
- 32 All Executive Engineers/DDA.
- 33 The Labour Commissioner, 15, Rajpur Road, Delhi.
- 34 The Commissioner (Sales Tax) IIIrd Floor, Delhi Govt. of NCT Delhi Bikrikar Bhawan, I.P. Estate, New Delhi-110002.
- 35 DDA, Contractor Association (Regd.), Vikas Kuteer, I.P. Estate, New Delhi.
- 36 Cont. Welfare Association (Regd.) 12-A Barrack No. 1, Block-A, Vikas Kuteer, I.P. Estate, New Delhi
- 37 The ITO Contractor circle central revenue office, 263 'A' 2nd Floor, I.P. Estate, New Delhi.
- 38 Cont. Association, CPWD, Y-Shape Building, I.P. Estate, New Delhi
- 39 Delhi Cont. Welfare Association, 306, Masjid Morh Rai Sahib Market, N.D.S.E. Part-II, New Delhi-110049.
- 40 The Chairman, Trans Yamuna DDA Cont. Association (Regd.) 11-12, Veer Sawarkar Mkt., Budh Bazar, Gandhi Nagar, Delhi.
- 41 The Delhi Cont. Building Association, (R) No. 5503, Choudhary Prem Bhwan, New Chanderwal Chowk, Bhim Singh Road, Delhi -1100073.
- 42 Security officer, DDA Vikas Minar, New Delhi
- 43 Tender Clerk, WD-5, Vikas Minar (Sale Counter).
- 44 Tender Clerk, CAU (NZ), DDA Ashok Vihar (Two copies).
- 45 All A.E./WD-5/DDA.
- 46 Head Clerk WD-5/DDA. To ensure for displaying the NIT on DDA website and confirm.
- 47 Notice Board of WD-5/DDA.
- 48 Secretary all Delhi DDA and MCD Contractors welfare Association (Regd.). 253, Pratap Khand, Vishakarma Nagar, Delhi.

Executive Engineer  
Western Division-5  
DDA

DELHI DEVELOPMENT AUTHORITY  
OFFICE OF THE EXECUTIVE ENGINEER  
WESTERN DIVISION NO.-5 (NORTH ZONE)  
TENDER NOTICE

Sealed Item rate tenders for the following works are invited by the Executive Engineer/WD-5/DDA 1<sup>st</sup> Floor Vikas Minar, New Delhi for the following works from the approved and eligible contractors of DDA, CPWD, Civil Wing of P & T, M.E.S. & Railways upto 3.00 P.M. which shall be opened on the same day at 3.30 P.M. at Ground Floor, DDA Office Vikas Minar, New Delhi in the presence of intending tenderers or their authorised representatives on the dates indicating against the each work. For eligibility criteria, please see foot note-I.

The tender documents can be obtained on any working day from the Sr.A.O. (CAU) NZ, DDA, Ashok Vihar New Delhi and Tender Sale Counter, Vikas Minar, New Delhi between 11.00 A.M. to 3.00 P.M. on payment of cost of tender (non-refundable) in cash as mentioned against each work on production of valid certificate of registration with works contract Sales Tax deptt. of the GNCTD and the tax Clearance Certificate on Form-XI. Sale of tender forms will be stopped 4 days (including the date of opening before the date fixed for opening of tender documents.

The manner of submission of tenders, opening of the same entry of contractors/their authorized representative of the place of opening shall be as provided in clauses 3 (a), (b) & (c) of PWD-6 forming part of the tender documents.

S. No.	NIT No.	Name of work	<u>Estt. Cost</u>	<u>Last date of sale</u>
			<u>Earnest Money</u> Cost of Tender	<u>Date of opening</u> Time allowed
1.	54/EE/WD-5/ DDA/10-11	M/O Completed Scheme under North Zone. SH: Raising of Existing Boundary Wall, Removal of Malba and maintaining of site No.7 at MOR Land New Ejender Nagar.	Rs. 4,90,795/- Rs. 2,816/- Rs. 500/- + 5% Vat	24-12-2010 29-12-2010 4 months

Foot Note-I

- c) For works costing upto Rs. 25.00 lacs, tenders shall be issued to contractor(s) registered with DDA only.

Foot Note-II

Special condition for work at serial no. \_\_\_\_\_

- a) The tenders are open for Non - registered specialized contractors also in addition to registered contractors;
- b) The satisfactorily completion of atleast two works of similar nature/class, each costing not less than 50% of the estimated cost [gross] or one work of similar nature/class, costing not less than 100% of the estimated cost [gross] in Govt. Department of the proposed work during the last five years; Being specialized nature of work, tender in respect of works mentioned at serial no. \_\_\_\_\_ will be issued by Sr. A.O. (CAU)/NZ/DDA, Ashok Vihar, Phase - I, Delhi - 110052 or tender clerk, Central Tender Unit, Vikas Minar, New Delhi - 02 after verification of application by the concerned Executive Engineer.

Executive Engineer  
Western Division-5  
DDA

No. F5 (38) WD-5/DDA/2010-11/5267

Dated :- 16-12-10

Copy to:-

- 25 Chief Engineer (NZ), DDA.
- 26 SE/CC-7/DDA.
- 27 Director (System), DDA, 'B' Block Vikas Sadan, DDA, for displaying the NIT on DDA web site.
- 28 F.O. to CE (NZ), DDA.
- 29 Sr. A.O. (W)-II, DDA, Vikas Sadan, New Delhi.
- 30 A.O. (CAU) NZ, DDA.
- 31 Ex. Engineer/QC. IV. DDA, Vikas Sadan.
- 32 All Executive Engineers/DDA.
- 33 The Labour Commissioner, 15, Rajpur Road, Delhi.
- 34 The Commissioner (Sales Tax) IIIrd Floor, Delhi Govt. of NCT Delhi Bikrikar Bhawan, I.P. Estate, New Delhi-110002.
- 35 DDA, Contractor Association (Regd.), Vikas Kuteer, I.P. Estate, New Delhi.
- 36 Cont. Welfare Association (Regd.) 12-A Barrack No. 1, Block-A, Vikas Kuteer, I.P. Estate, New Delhi
- 37 The ITO Contractor circle central revenue office, 263 'A' 2nd Floor, I.P. Estate, New Delhi.
- 38 Cont. Association, CPWD, Y-Shape Building, I.P. Estate, New Delhi
- 39 Delhi Cont. Welfare Association, 306, Masjid Morh Rai Sahib Market, N.D.S.E. Part-II, New Delhi-110049.
- 40 The Chairman, Trans Yamuna DDA Cont. Association (Regd.) 11-12, Veer Sawarkar Mkt., Budh Bazar, Gandhi Nagar, Delhi.
- 41 The Delhi Cont. Building Association, (R) No. 5503, Choudhary Prem Bhwan, New Chanderwal Chowk, Bhim Singh Road, Delhi -1100073.
- 42 Security officer, DDA Vikas Minar, New Delhi
- 43 Tender Clerk, WD-5, Vikas Minar (Sale Counter).
- 44 Tender Clerk, CAU (NZ), DDA Ashok Vihar (Two copies).
- 45 All A.E./WD-5/DDA.
- 46 Head Clerk WD-5/DDA. To ensure for displaying the NIT on DDA website and confirm.
- 47 Notice Board of WD-5/DDA.
- 48 Secretary all Delhi DDA and MCD Contractors welfare Association (Regd.). 253, Pratap Khanda, Vishakarma Nagar, Delhi.

Executive Engineer  
Western Division-5  
DDA

## SCHEDULE OF QUANTITY

Name of work:- M/o Completed scheme under Nazul A/c II of North Zone  
SH:- Providing and laying G.I. pipe line in Rock Garden Patel Nagar

S. No.	Description of items	Qty.	Unit	Rate	Amount
1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 m lead as per direction of Engineer-in-charge. a) 1:3:6 or richer mix b) 1:4:8 or leaner mix	2.20 4.00	Cum Cum		
2	Demolishing stone rubble masonry manually/mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge, in cement mortar.				
3.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	3.00	Cum		
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work upto plinth level. a) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone	27.50	Sqm.		

5.	aggregate 20 mm nominal size) b) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) 40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand including pointing with cement mortar 1:2 (1 cement : 2 stone dust) with an admixture of pigment to match the shade of stone. a) Red Sand stone	2.20 4.00	Cum Cum
6.	Providing and fixing G.I pipes complete with G.I. fittings including trenching and refilling etc. a) 20 mm dia nominal bore b) 40 mm dia nominal bore c) 50 mm dia nominal bore d) 65 mm dia nominal bore	28.00 23.00 280.00 720.00 602.00	Sqm Mtr. Mtr. Mtr. Mtr.
7.	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc complete. a) 50 to 80 mm	3 Nos.	Each
8.	Providing and fixing gun metal gate valve with C.I. wheel of approved quality. (Screwed end ) a) 40 mm nominal bore.	4 Nos.	Each

9.	b) 50 mm nominal bore. c) 65 mm nominal bore.. Providing and fixing brass stop cock of approved quality, 20 mm nominal bore.	6 Nos. 8 Nos.	Each Each
10.	Painting G.I. pipes and fittings with two coats of anti-corrosive bitumastic paint of approved quality. a) 20 mm dia pipe b) 40 mm dia pipe c) 50 mm dia pipe d) 65 mm dia pipe	50 Nos.  23.00 280.00 720.00 602.00	Each  Mtr. Mtr. Mtr. Mtr.
11.	Providing and filling sand of grading Zone-V or coarser grade all round the G.I. pipes in external work. a) 40 mm dia pipe b) 50 mm dia pipe c) 65 mm dia pipe	  280.00 720.00 602.00	  Mtr. Mtr. Mtr.
12.	Providing and fixing G.I. Union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New Work) a) 40 mm nominal bore b) 50 mm nominal bore c) 65 mm nominal bore	  3 Nos. 6 Nos. 10 Nos.	  Each Each Each



13.	Providing and laying 60 mm thick factory made cement concrete inter locking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc all complete as per the direction of Engineer in charge.	541.00	Sqm
14.	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement :6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at plinth level with, cement mortar 1:6 (1 cement: 6 coarse sand)	4.00	Cum
15.	Disposal of malba, building rubbish, moorum etc by mechanical transport including loading, unloading lead upto 10 km	12.00	Cum

16.	Chequered precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand), light shade using white cement.	12.00	Sqm.
17.	Demolishing brick work manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge, In Cement mortar.	1.38	Cum
18.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in cement mortar 1:4 (1 cement : 4 coarse sand)	2.00	Cum

19.	40 mm thick rubbed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand) with joints 3 mm thick, side buttered with cement mortar 1:2 (1 cement : 2 stone dust) admixed with pigment to match the shade of stone and pointing with same mortar, Red sand stone.	2.00	Sqm,	

Executive Engineer - up  
 Executive Engineer  
 Western Division-6  
 D.D.A.

### SCHEDULE OF QUANTITY

N.O.W.: M/o Completed Scheme under Nazul A/c-II of North Zone

SH: Repair of Boundary Wall with Chain link fencing at R-Block, Rajender Nagar (Ridge Area).

S.No.	Description of Items	Qty.	Unit
1.	Random Rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 Cement : 6 Coarse Sand : 12 Graded Stone agg. 20mm NS) at plinth level with (a) Cement Mortar 1:6 (1 Cement: 6 Coarse Sand)	132.00	Cum
2.	Pointing on stone work with cement mortar 1:3 (1 Cement : 3 Fine Sand) (i) Raised and cut pointing	735.00	Sqm.
3.	Centering and shuttering including strutting, propping etc. and removal of form work for:- (i) Retaining walls, return walls, wall (any thickness) including attached pilasters, buttresses, plinth and string courses, fillet etc.	70.00	Sqm.
4.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) i/c attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets coping, bed blocks, Anchor blocks, plain window sills fillet etc. up to floor five level excluding the cost of centring, shuttering and finishing. (a) 1:2:4 (1 Cement : 2 Coarse Sand : 4 Graded Stone agg. 20 mm N.S.)	22.00	Cum

5.	Providing and fixing link chain fencing made of angle iron frame welded with angle iron 40x40x6mm of Panel size 2.40x1.20 m vertical post 1.60m long, horizontal angle 40x40x6mm 2.40m long at top and bottom welded with 30x5mm M.S. flats over G.I. Chain link Jali 50x50x3mm thick to vertical and horizontal sides of Panel i/c stretching, tightening and hoisting of Jali Screwing with 2 Nos. galvanized steel nuts & bolts on each vertical post i/c applying a priming cost of steel primer of approved brand and manufacture, each panel to be fixed with two vertical posts and horizontal legs to be embedded in Cement Concrete 1:2:4 (1 Cement : 2 Coarse Sand : 4 Graded Stone agg. 20mm N.S.) The payment of cc block will be paid separately. The chain link Jali will be welded in high angle iron frame M.S. flat will be welded at every 10 cm c/c on both horizontal and vertical side complete as per direction of Engineer Incharge.			
6.	Painting with Synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	251.00	Sqm.	
7.	Painting with synthetic enamel paint of approved brand & manufacture of required colour to give an even shade. One or more coats on old work.	706.00	Sqm.	
8.	Excavation in dumped stones / malba i/c stacking of serviceable and unserviceable material separately and disposal of unserviceable material lead upto 50m and lift upto 1.5m disposed material to be neatly dressed.	264.00	Sqm.	
9.	Disposal of building rubbish, malba, earth, moorum etc. by mechanical transport i/c loading and unloading upto 10 km lead.	150.00	Cum	
		150.00	Cum	

10.	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material with in 50m lead as per direction of engineer incharge in cement Mortar.		
11.	Demolishing cement concrete manually / by mechanical means i/c disposal of material with in 50m lead as per direction of Engineer Incharge (a) 1:3:6 or richer mix	15.00	Cum
12.	Colour washing such as green, blue, or buff to give an even shade. New work (two or more coats) with a base coat of white washing with lime	5.00	Cum
		405.00	Sqm

Executive Engineer  
Western Division-5  
D.D.A.

Name work : M/o Completed Scheme under North Zone.  
 SH : Raising of Existing Boundary Wall, Removal of Malba and maintaining of site No. 7 at MOR land  
 New Rajender Nagar.

S. No.	Description of item	Qty.	Unit	Rate	Amount
1	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	99.36	Cum		
2.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. upto floor five level, excluding the cost of centring, shuttering and finishing : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
3.	Centering and shuttering including strutting, propping etc. and removal of form work for: a) Retaining walls, return walls (any thickness) including attached pilasters, buttresses plinth and string courses fillets etc.	5.52	Cum		
4.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	48.00	Sqm.		
		432.00	Sqm.		

5.	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement : 6 fine sand)	432.00	Sqm.
6	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	960.00	Sqm.
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) One or more coats on old work		
8.	Providing & fixing 1.25 mm thick M.S. sheet boards of size 1.80 x 1.20 m frame and legs 40 x 40x 5mm with over all length 10.20 m bracing 35x 35x 5mm angle iron 2 Nos. including cutting, welding fixing in position and applying a coat of approved steel primer all complete as per drawing and direction of Engineer-in-charge.	90.00	Sqm.
9.	Deploying of labour for daily cleaning of site i/c removal of garbage as per direction of Engineer in charge.	8 Nos.	Each
10.	Excavation in dumped stones or malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable material lead upto 50 m and lift up to 1.5 m disposed material to be neatly dressed.	400	Each
		498.00	Cum



11.	Carriage of material by mechanical transport including loading, unloading for all lead and lift.		
	a) Lime moorum, building rubbish etc.	498.00	Cum

Note :

1. The work will be executed under the supervision of R.W.A.
2. A satisfactory completion of work to be submitted from R.W.A.
3. Double the measurement to be covered if any labour found absent
4. ~~Fourteen~~ *Fourteen* men needed ~~assisted~~ *to be employed at site daily*
5. Duty hour 9.00 A.M. to 5.00 P.M.

Executive Engineer  
Western Division-5  
D.A.