

DELHI DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER
WD-5/N.Z./1ST FLOOR, V. MINAR/ND-2

No. : F.5(Misc.)WD-5/DDA/0-112

DE 30/11/10

To,
The Deputy Director (System),
D.D.A., 1st Floor, Vikas Sadan,
D.D.A., New Delhi

Sub. : Uploading of the documents on DDA Website on behalf of WD-5.

Sir,

Please find enclosed herewith the following documents for uploading on DDA website.

Tender Notice

vide M.I.T. No - 20/EE(WDS)/DDA/2010-11

27/EE(WDS)/DDA/2010-11

51/EE(WDS)/DDA/2010-11

along with schedule.

vide letter No 15 (38)WDS/DDA/2010/11/5147 dtd 29/10

Executive Engineer
Western Division-5
D.D.A.

**DELHI DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER
WESTERN DIVISION NO-5 (NORTH ZONE)**

TENDER NOTICE

re-invited /invited

Sealed Item rate tenders for the following works are ~~to be~~ by the Executive Engineer/WD-5/DDA 1st Floor Vikas Minar, New Delhi for the following works from the approved and eligible contractors of DDA, CPWD, Civil Wing of P & T. M.E.S. & Railways upto 3.00 P.M. which shall be opened on the same day at 3.30 P.M. at Ground Floor, DDA Office Vikas Minar, New Delhi in the presence of intending tenderers or their authorised representatives on the dates indicating against the each work. For eligibility criteria, please see foot note-I & II.

The tender documents can be obtained on any working day from the Sr.A.O. (CAU) NZ, DDA, Ashok Vihar New Delhi and Tender Sale Counter, Vikas Minar, New Delhi between 11.00 A.M. to 3.00 P.M. on payment of cost of tender (non-refundable) in cash as mentioned against each work on production of valid certificate of registration with works contract Sales Tax deptt. of the GNCTD and the tax Clearance Certificate on Form-XI. Sale of tender forms will be stopped 4 days (including the date of opening before the date fixed for opening of tender documents.

The manner of submission of tenders, opening of the same entry of contractors/their authorized representative of the place of opening shall be as provided in clauses 3 (a), (b) & (c) of PWD-6 forming part of the tender documents.

S. No.	NIT No.	Name of work	Estt. Cost Earnest Money Cost of Tender	Last date of sale Date of opening Time allowed
1.	20/EE/WD-5/ DDA/2010-11	A/R & M/O Staff Qtr. Jai Dev Park. SH: Providing and fixing collapsible sheet shutters, concertina coil fencing, interlocking, paver block, painting, distempering and white washing at DDA Community Hall at Jai Dev Park.	Rs.2,81,621/- Rs.56,321/- Rs.500/- + 5% Vat	10-12-10 15-12-10 One month
	<u>Re-invited</u>			
2.	27/EE/WD-5/ DDA/2010-11	A/R & M/O Staff Qtr. at Rajender Nagar, Dev Nagar and Bagh Raoji. SH: Cleaning & Sweeping of DDA Staff Qtr. at Rajender Nagar.	Rs.58,609/- Rs.1,172/- Rs.150/- + 5% Vat	10-12-10 15-12-10 Six Month
	<u>Re-invited</u>			
3.	51/EE/WD-5/ DDA/2010-11	M/O Completed Scheme under N/A-II. of N.Z. SH: Restoration of Trench cut by BSES for laying cable near Rachna Cinema at Rajendra Place.	Rs.1,44,456/- Rs.2,889/- Rs.500/- + 5% Vat	10.12.10 15-12.10 one month

Foot Note-I

- a) For works costing upto Rs. 25.00 lacs, tenders shall be issued to contractor(s) registered with DDA only.

Foot Note-II

Special condition for work at serial no. _____

- i. The tenders are open for Non - registered specialized contractors also in addition to registered contractors;
- ii. The satisfactory completion of atleast two works of similar nature/class, each costing not less than 50% of the estimated cost [gross] or one work of similar nature/class, costing not less than 100% of the estimated cost [gross] in Govt. Department of the proposed work during the last five years; Being specialized nature of work, tender in respect of works mentioned at serial no. _____ will be issued by Sr. A.O. (CAU)/NZ/DDA, Ashok Vihar, Phase - I, Delhi - 110052 or tender clerk, Central Tender Unit, Vikas Minar, New Delhi - 02 after verification of application by the concerned Executive Engineer.

No. F5 (38) WD-5/DDA/07-08/10-11/5147

Dated :

29/11/10

Executive Engineer
Western Division-5
DDA

Copy to:-

- 1 Chief Engineer (NZ), DDA.
- 2 SE/CC-7/DDA.
- 3 Director (System), DDA. 'B' Block Vikas Sadan, DDA, for displaying the NIT on DDA web site.
- 4 F.O. to CE (NZ), DDA.
- 5 Sr. A.O. (W)-II, DDA, Vikas Sadan, New Delhi.
- 6 A.O. (CAU) NZ, DDA.
- 7 Ex. Engineer/QC. IV. DDA, Vikas Sadan.
- 8 All Executive Engineers/DDA.
- 9 The Labour Commissioner, 15, Rajpur Road, Delhi.
- 10 The Commissioner (Sales Tax) IIIrd Floor, Delhi Govt. of NCT Delhi Bikrikar Bhawan, I.P. Estate, New Delhi-110002.
- 11 DDA Contractor Association (Regd.), Vikas Kuteer, I.P. Estate, New Delhi.
- 12 Cont. Welfare Association (Regd.) 12-A Barrack No. 1, Block-A, Vikas Kuteer, I.P. Estate, New Delhi.
- 13 The ITO Contractor circle central revenue office, 263 'A' 2nd Floor, I.P. Estate, New Delhi.
- 14 Cont. Association, CPWD, Y-Shape Building, I.P. Estate, New Delhi.
- 15 Delhi Cont. Welfare Association, 306, Masjid Morh Rai Sahib Market, N.D.S.E. Part-II, New Delhi-110049.
- 16 The Chairman, Trans Yamuna DDA Cont. Association (Regd.) 11-12, Veer-Sawarkar Mkt., Budh Bazar, Gandhi Nagar, Delhi.
- 17 The Delhi Cont. Building Association, (R) No. 5503, Choudhary Prem Bhawan, New Chanderwal Chowk, Bhini Singh Road, Delhi -1100073.
- 18 Security officer, DDA Vikas Minar, New Delhi.
- 19 Tender Clerk, WD-5, Vikas Minar (Sale Counter).
- 20 Tender Clerk, CAU (NZ), DDA Ashok Vihar (Two copies).
- 21 All A.E./WD-5/DDA.
- 22 Head Clerk WD-5/DDA. To ensure for displaying the NIT on DDA website.
- 23 Notice Board of WD-5/DDA.
- 24 Secretary all Delhi DDA and MCD Contractors welfare Association (Regd.). 253, Pratap Khand, Vishakarma Nagar, Delhi.

Executive Engineer
Western Division-5
DDA

Name of work :

A/R & M/o Staff Qtr. At Jai Dev Park.

SH :

Providing and fixing in Collapsible steel shutters, concerina coil fencing, interlocking Paver block Painting, Distempering, and White washing at DDA Community Hall Jai Dev Park.

S. No.	Description of Item	Qty.	Unit	Rate	Amount
1.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: a) Cement mortar 1:4 (1 cement : 4 coarse sand)	8.15	Cum		
2.	Providing and fixing ISI marked flush door shutters confirming to IS: 2202 (Part-1) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. a) 35mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	14.23	Sqm.		
3.	Extra for providing and fixing flush doors with decorative veneering: a) On one side in item No. 9.21	14.23	Sqm.		
4.	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rail of T-iron 40x40x6mm with 40mm dia, steel pulleys complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	18.00	Sqm.		
5.	Welding by gas or electric plant including transportation of plant at site etc complete.	1000.00	Cm.		

6.	12mm cement plaster of mix : a) 1:6 (1 cement : 6 fine sand)	157.96	Sqm.
7.	Renewing glass panes, with putty and Nails wherever necessary: a) Float glass panes of thickness 4 mm.	10.47	Sqm.
8.	White washing with lime to give an even shade: a) Old work (Two or more coats).	157.14	Sqm.
9.	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade: a) Old work (one or more coats)	306.87	Sqm.
10.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: a) One or more coats on old work.	47.78	Sqm.
11.	Finishing walls with water proofing cement paint of required shade: a) Old work (one or more coats applied @ 2.20 Kg/10 sqm) over priming coat of primer applied @ 0.80 lt./10 sqm complete i/c cost of priming coat.	1015.50	Sqm.
12.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	144.39	Sqm.
13.	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse	297.00	Sqm.

	sand, filling the joints with fine sand etc. all-complete as per the direction of Engineer -in-charge.		
14.	Providing and fixing concertina coil fencing with required dia 610 mm (having 50 Nos. rounds per 6 metre length) up to 3m height of wall with existing angle iron 'S' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron all complete as per direction of Engineer-in-charge with reinforced barbed tape (R.B.T.) /Spring core (2.5 mm thick) wire of high tensile strength of 165 Kg/sq. mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	100.80	Metre
15.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. a) In cement mortar	0.70	Cum
16.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level: a) 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	1.06	Cum
17.	Centering and shuttering including strutting, propping etc. and removal of form work for: a) Foundations, footings, bases for columns.	6.12	Sqm.

18.	Providing and fixing brass bib cock of approved quality: a) 15 mm nominal bore.	3.00	Each
19.	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI: 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	Per Ltr.
20.	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931 a) 15 mm nominal bore.	2.00	Each
21.	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. a) 15 mm nominal bore.	2.00	Each
22.	Providing and fixing wash basin with C.I. brackets, 15 mm, C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets cutting and making good the walls wherever require. a) White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps.	1.00	Each
23.	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work a) 20 mm dia. Nominal bore.	28.00	Metre

ABSTRACT OF COST

Name of work : A/R & Maintenance of Staff Qtrs. At Rajender Nagar, bagh Raoji & Dev Nagar
 SH : Cleaning and sweeping of DDA Staff Qtrs. At Rajender Nagar

S.No.	Item	Qty.	Unit	Rate	Amount
1.	Cleaning and sweeping of road path/ drains and sand stone flooring marble stone kota stone flooring complete including collection of garbage. Malba sludge and refuse of all type i/c dead animals at site daily and dumping the same in the dustbin complete as per direction of engineer in charge	6.	Month		
2.	Disposal of building rubbish moorum sludge by mechanical transport including loading unloading all lead & lift complete as per direction Engineering -in-charge	450	Cum		

Condition :-(1) Labour on duty will be in dress

(2) Duty hours 9AM to 5 PM

(3) Satisfactory completion of work to be submitted ^{from} ~~from~~ R. W.A

(4) Double the market rate to be recovered if any labour found absent from duty

(5) One Nos Environmental Assistant to be employed at site of daily

Schedule of Quantity

Name of work :- M/o Completed scheme under Nazual A/c -II of N.Z.
S.H. :- Restoration of trench cut by B.S.E.S. for laying cable near Rachna Cinema at Rajindra Place.

S. No.	Description of Items	Qty.	Unit	Rate	Amount
1.	Demolishing cement concrete manually/by mechanical means i/c disposal of material with in 50m lead as per direction of Engineer-in-charge. (i) 1:3:6 or richer mix (ii) 1:4:8 or leaner mix	8.00 15.00	Cum Cum		
2.	Dismantling stone slab flooring laid in cement mortar i/c stacking of serviceable material and disposal of unserviceable material with in 50 m lead.	117.00	Sqm.		
3.	Excavation work by mechanical means (hydraulic excavator)/manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm. on plan i/c dressing of sides and ramming of bottoms lift up to 1.5 m i/c getting out the excavated soil and disposal of surplus excavated soil as directed with in a lead of 50 m (a) Ordinary Work.	67.00	Cum		
4.	Supplying and filling in plinth with Jaruna sand under floors including watering, ramming consolidating and dressing complete.	47.00	Cum		

5.	P/L in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level. (i) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (ii) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	8.00 15.00	Cum Cum
6.	40 mm thick finished stone flooring over 20 mm (average) thick base of cement mortar 1 : 5 (1 cement : 5 coarse sand) including pointing with cement mortar 1:2 (1 cement : 2 Stone Dust) with an admixture of Pigment to match the shade of stone. (i) Red Sand Stone	117.00	Sqm.
7.	Disposal of malba, building rubbish moorum etc. by mechanical transport including loading , unloading lead upto 10 Km.	97.00	Cum