

**OFFICE OF THE EXECUTIVE ENGINEER
SOUTH-WESTERN DIVISION NO.8
DELHI DEVELOPMENT AUTHORITY
CENTRAL NURSERY, SECTOR-5, DWARKA**

No. F 54 (1727)/EE/SWD-8/A/12-13/DDA/209

Dated: 02-3-13

To

M/s. G.C. Enterprises,
C-3/153, Yamuna Vihar,
New Delhi-110053.

Name of work:- M/o pertaining complete scheme under Dwarka Zone.

SH:- Providing entry and exit to Dwarka Court Complex from M.P. Road No.224 including providing and laying bitumen mastic wearing course on the entire crossing.

Ref:- F. 54(1727)EE/SWD-8/A/2012-13/DDA/198 Dt: 27.02.13.

P.G. Received on:- 01.03.13. for Rs. 40,000/- in the shape of FDR issued by Punjab National Bank Yamuna Vihar, Delhi.

Dear Sir,

Your item rate tender for the above mentioned work is hereby accepted on behalf of the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost:- Rs. 7,42,043/- (Rs. Seven Lacs Forty Two Thousand Forty Three Only).

Quoted/tendered Amount:- Rs.7,56,422/- (Rs. Seven Lacs Fifty Six Thousand Four Hundred Twenty Two only).

Accepted Amount: Rs.7,53,124/- (Rs. Seven Lacs Fifty Three Thousand One Hundred Twenty Four only).


The percentage to be taken for the purpose of Clause-12 of the agreement shall **1.49 %** above on the rates based on DSR-2007.

You are requested to attend the office along with a non-judicial stamp paper worth Rs.50/- (Rupees fifty only) to complete the formal agreement within seven days from the date of issue of this letter, failing which, acceptance of tender is likely to be withdrawn and earnest money forfeited.

Please note that time allowed for completion of work as entered in the tender shall be reckoned from the 10th day after the date of issue of this letter to commence the work. The time allowed for execution of work is Forty Five Days.

You are requested to contact AE-I of this division and start the work immediately.


Executive Engineer
SWD-8/DDA



DELHI DEVELOPMENT AUTHORITY (REVISED SCHEDULE)

Name of work:- M/o various colonies under Nazul A/c-II in Dwarka.

SH:- Providing entry and exit to Dwarka Court Complex from M.P. Road No.224 including providing and laying bitumen mastic wearing course on the entire crossing.

SCHEDULE OF QUANTITIES

NIT No.:- 31/EE/SWD8

Estimated Cost: Rs. 7,42,043/-

NAME OF THE FIRM


G.C. Enterprises

S. No.	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. a. All kinds of soil	64.40	cum	90.00	Rupees Ninety only	5796.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a. 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) b) 1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size).	7.98	cum	1800.00	Rupees One Thousand Eight Hundred only	14364.00
		13.50	cum	2700.00	Rupees Two Thousand Seven Hundred only	36450.00
3	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm. depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth lead upto 50 metres.	30.00	sqm	50.00	Rupees Fifty only	1500.00

	Supplying and stacking at site.	7.56	cum	790.00	Rupees Seven Hundred Ninety only	5972.40
	a) 90 mm to 45 mm size stone aggregate.					
	b) 63 mm to 45 mm size stone aggregate.	2.81	cum	810.00	Rupees Eight Hundred Ten only	2276.10
4	c) 53 mm to 22.4 mm size stone aggregate.	2.81	cum	870.00	Rupees Eight Hundred Seventy only	2444.70
	d) Stone screening 13.2 mm nominal size (Type A).	1.68	cum	250.00	Rupees Two Hundred Fifty only	420.00
	e) Stone screening 11.2 mm nominal size (Type B).	0.93	cum	240.00	Rupees Two Hundred Forty only	223.20
	f) Red bajri	1.26	cum	240.00	Rupees Two Hundred Forty only	302.40
5	Laying spreading and compacting stone aggregate of specified sizes to WBM specifications including spreading in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate watering and compacting to the required density.	10.50	cum	110.00	Rupees One Hundred Ten only	1155.00
6	Providing and applying tack coat using hot straight run bitumen of grade 80/ 100 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications a) On W.B.M. @ 0.75 Kg / sqm. b) On bituminous surface @ 0.50 Kg / sqm.	30.00	sqm	11.99	Rupees Eleven and paise Ninety Nine only	359.70
		221.00	sqm	10.99	Rupees Ten and paise Ninety Nine only	2428.79
7	Providing and laying Bituminous Macadam on prepared surface with specified graded crushed stone aggregate for profile corrective	2.25	cum	3600.00	Rupees Three Thousand Six Hundred only	8100.00

8	Providing and laying Dense Bituminous concrete on prepared surface with specified graded stone aggregate for wearing course including loading of aggregate with F.E. loader , and hot mixing of bitumen with filler and stone aggregate in hot mix plant , transporting the mixed material by tippers to paver and laying the mixed material with mechanical paver finisher fitted with electronic sensing device to the required level and grade and rolling with road rollers, as per MORTH specification, to achieve the desired density and compaction but excluding cost of primer/ tack coat. a. 40 mm/50mm compacted thickness with bitumen of grade 60/ 70 @ 5.5% and lime @3% (percentage by weight of total mix).	8.84	cum	5400.00	Rupees Five Thousand Four Hundred only	47736.00
9	Providing and laying bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 conforming to IS : 702 prepared by using mastic cooker and laid to required level and slope including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm and at approximates spacing of 10cm centre to centre in both directions, pressed into surface protruding 1mm to 4mm over mastic surface, including cleaning the surface, removal of debris etc. all complete. (Considering bitumen using 10.2% as per MORTH specification). a. 25mm thick.	1,123.60	sqm	522.00	Rupees Five Hundred Twenty Two only	586519.20
10	Dismantling of cement concrete kerb stones of M-25 grade fixed in cement mortar, manually i/c stacking of servicable material and disposal of unservicable material with in 50m lead.	114.00	m	18.50	Rupees Eighteen and paise Fifty only	2109.00
11	Fixing at or near ground level factor made kerb stone issued by department free of cost of M-25 grade cement in position the required level and curvature jointed with cement mortar 1:3 (1 cement:3 coarse sand) i/c making joints with or without grooves (thickness of joints except of sharp curves shall not more than 5 MM) i/c making drainage opening where ever required complete as per the direction of engineer in- charge.	114.00	m	35.00	Rupees Thrity Five only	3990.00

12	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compactors and of approved size, design and shape laid in required colour and pattern over and including 50 mm thick compacted bed of Jamuna sand, filling the joints with jamuna sand etc all complete as per the direction of engineer in charge.	63.70	sqm	380.00	Rupees Three Hundred Eighty only	24206.00
13	Providing & laying 75mm thick compacted bed of dry brick aggregate of 40mm thick nominal size including spreading, well ramming consolidation and grouting with jamuna sand including finishing smooth etc complete as per direction of engineer in charge.	63.70	sqm	50.00	Rupees Fifty only	3185.00
14	Disposal of earth/building rubbish/ malba by mechanical transport i/c loading and unloading with all leads and lift as per the direction of engineer-in-charge.	64.40	cum	56.00	Rupees Fifty Six only	3606.40
						753143.89
						say Rs. 7,53,144.00


 Executive Engineer
 WWD-3, DDA