

DELHI DEVELOPMENT AUTHORITY
WESTERN DIVISION NO-8
Sector-5, Central Nursery, Dwarka
New Delhi-110075

R.A.D

No.F.81(21)Acs/WD-8/DDA/2012-13/ 338

Dt. 4/3/13

To

M/s A.K.Sharma Construction,
H.No.152A, Indraj Colony, Bawana,
Delhi-110039.

Name of work : M/O various colonies under Dwarka Zone, Nazul A/c-II.
SH Improvement of path & roads works along road berms of
12 m & 20 m road around crown CGHS and around Park No.1 & 2
behind Siddhartha Kunj society, Sector-7, Dwarka.
Ref: : Letter of intent vide No.F.81 (21)A/cs/WD-8/DDA/2012-13/174
dt.31.01.13
Ref of P.G.: : FDR No.087501 A/c No.117320100070422 dt. 14.02.2013 for
Rs.82,555/- only.

Dear Sir,

Your item rate tender dated 04.01.13 for the above mentioned work has been accepted on behalf of DDA at the rates, terms and conditions given below:

1. Estt.Cost. : Rs.13,89,974/- (Rupees thirteen lacs eighty nine thousand nine hundred seventy four only)
2. Quoted Amount. : Rs.16,51,076/- (Rupees sixteen lacs fifty one thousand seventy six only).
3. Accepted tender Amount : Rs.16,51,076/- (Rupees sixteen lacs fifty one thousand seventy six only).
(As per annexure 'A')
4. Percentage for the Purpose : 18.78% above the Estt Cost based on D:S.R. -2007.
5. Time allowed : Three months

You are requested to attend this office to sign the agreement along with one non-judicial stamp paper worth Rs.50/- (fifty) within 7 days from the date of issue of this letter. Please note that if you fail to sign the agreement within seven days from the date of issue of this letter, of acceptance of the tender is likely to be withdrawn and the earnest money as well as performance guarantee will be forfeited.

You are also requested to contact the A.E. V of this division and start the work at once. Please note that time allowed for carrying out the work as entered in the tender form shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

VAT, Cess, & other statutory taxes shall be deducted as applicable from time to time.

Encl: Schedule of awarded rates


Executive Engineer
Western Division-8



DELHI DEVELOPMENT AUTHORITY

M/S A.K. Sharma

Consent

Name of Work: M/O various colonies under Dwarka Zone, Nazul A/C-II

SH : Improvement of path and road works along road berms of 12.00m and 20.0m road around crown CGHS and around park no.1 & 2 behind Siddhartha kunj society, sector-7, Dwarka


SCHEDULE OF QUANTITIES
NIT No.29/EEWD-8/12-13
Estimated Cost: Rs. 13,89,974/-

Approved Rate

NAME OF THE FIRM

| S. No. | Description of Item | Qty | Unit | Rate | Rate in words | Amount |
|--------|---|---------|---------|---------|---|-----------|
| 1 | Earth work in surface excavation not exceeding 30cm in depth but exceeding 1.5m in width as well as 10sqm. On plan including disposal of excavated earth upto 50m and lift upto 1.5m disposed soil to be leveled and dressed. a) All kinds of soil. | 1610.00 | 100/sqm | 1100.00 | Rupees One Thousand One Hundred Only | 17710.00 |
| 2 | Providing and laying 75mm thick compacted bed of dry brick aggregate of 40mm thick nominal size including spreading, ramming well, consolidating and grouting with jammna sand including finishing smooth etc complete as per direction of engineer-in-charge. | 1610.00 | sqm | 70.00 | Rupees Seventy Only | 112700.00 |
| 3 | Providing and laying in position cement of specified grade excluding the cost of centering and shuttering: All work up to plinth level. a) 1:2:4 1 cement: 2 coarse sand: 4 graded stone aggregates 20mm nominal size) | 7.00 | cum | 3500.00 | Rupees Three Thousand Five Hundred Only | 24500.00 |
| 4 | Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge. | 1474.00 | sqm | 350.00 | Rupees Three Hundred Fifty Only | 515900.00 |
| 5 | Providing and applying tack coat using hot straight run bitumen of grade 80/100 including heating of bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specification: (a) On bituminous surface @ 0.50kg/sqm. | 5333.00 | sqm | 25.00 | Rupees Twenty Five Only | 133325.00 |
| 6 | 2.5cm premix carpet surfacing with 2.25 cum and 1.12 cum of stone chippings of 13.2mm and 11.2mm size respectively per 100 sqm. And 52kg of hot bitumen per cum of stone chippings of 13.2mm and 11.2mm size respectively including a tack coat with hot straight run bitumen with the aid of hot mix plant and sponser paver finisher including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately) with paving asphalt 60/70 with no solvent. | 5333.00 | sqm | 157.00 | Rupees One Hundred Fifty Seven Only | 837281.00 |

| | | | | | | |
|---|--|--------|-----|-------|--------------------|----------|
| 7 | Disposal of muck/earth/building rubbish by mechanical transport including loading, unloading within 5km lead | 322.00 | cum | 30.00 | Rupees Thirty Only | 9660.00 |
| | TOTAL | | | | | reservat |


 Executive Engineer
 Western Division-8
 BDA