

DELHI DEVELOPMENT AUTHORITY
WESTERN DIVISION NO-8
Sector-5, Central Nursery, Dwarka
New Delhi-110075

No.F.81(26)Acs/WD-8/DDA/2012-13 | 369

Dt. 13/3/13

To

M/s R.K. Construction Co.
H.No. U-1/53,
Budh Vihar, Phase-I,
New Delhi-110043.

Name of work : M/o Various colonies under Dwarka Zone, Nazul A/c-II.

SH : Improvement of works behind Rishikul Garden & along Command
 Tank No. 1 boundry 6.00 m wide road Sector-7, Dwarka.

Ref: : Letter of intent vide No.F.81(26)A/cs/WD-8/DDA/2012-13/322
 dt.28.02.2013

Ref of P.G.: : FDR No.H-465049 A/cs No. 0303101000052210 dt. 28.02.2013
 amounting to Rs.73,000.00 of The South Indian Bank Ltd.

Dear Sir,

Your item rate e-tender dated 11.02.13 for the above mentioned work has been accepted on behalf of DDA as per terms and conditions given below:

1. Estt.Cost. : Rs.12,38,556.00 (Rupees Twelve lacs thirty eight thousand five hundred fifty six)only
2. Quoted Amount. : Rs.14,56,445.00(Rupees Fourteen lacs fifty six thousand four hundred forty five) only
3. Accepted Tender Amount : Rs.14,56,445.00(Rupees Fourteen lacs fifty six thousand Four hundred forty five only
 (As per annexure 'A')
4. Percentage for the Purpose : 17.59% above the Estt Cost based on D.S.R. -2007.
5. Time allowed : Three Months.


You are requested to attend this office to sign the agreement along with one non-judicial stamp paper worth Rs.50/- (fifty) within 7 days from the date of issue of this letter. Please note that if you fail to sign the agreement within seven days from the date of issue of this letter, the acceptance of the tender is likely to be withdrawn and the earnest money as well as performance guarantee will be forfeited.

You are also requested to contact the A.E. V of this division and start the work at once. Please note that time allowed for carrying out the work as entered in the tender form shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

VAT, Cess ,& other statutory taxes shall be deducted as applicable from time to time.

Encl: Schedule of awarded rates

Yours faithfully


 Executive Engineer
 Western Division-8

DELHI DEVELOPMENT AUTHORITY

Name of Work: M/O various colonies under Dwarka Zone, Nazul A/c-II
SH : Improvement of works behind Rishikul Garden & along Command Tank No.1 boundary 6.00 m wide road Sec.-07, Dwarka.


SCHEDULE OF QUANTITIES
NIT No.- 31 /EEWD-8/DDA/12-13
Estimated Cost: Rs. 12,38,556/-
Awarded Rate
M/s R. K. Construction Co.

R.K.Const.Co.

NAME OF THE FIRM

S. No.	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	71.00	Cum	120.00	Rupees One Hundred Twenty Only	8520.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	20.00	Cum	2000.00	Rupees Two Thousand Only	40000.00
3	Providing and laying design mix cement concrete in roads, taxi tracks and runways having a minimum works test beam flexural strength of 30kg. per cm2. at 28 days using not less than 340 Kg. of cement per cum of finished concrete, coarse sand and graded stone aggregate of 40mm nominal size in appropriate proportions as per specified design criteria approved by Engineer-in-charge mechanically vibrated using needle and surface vibrators including steel form work with sturdy M. S. channel sections including curing and providing and filling construction joints and dummy joints with approved joint filler and primer including rounding of the edges and filling the grooves 10x25mm deep at top for construction joints and 10mmx50mm deep at top for dummy joints with joint sealing compound (conforming to grade B of IS : 1834) including making necessary arrangements for expansion joints etc. all complete.	256.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	1177600.00
4	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge	195.00	SQM	325.00	Rupees Three Hundred Twenty Five Only	63375.00
5	Providing, stacking and placing perforated or non-perforated SFRC covers of grade M.D.(M.D.-10) conforming to size complete over S.W. drain having engraving WD-8/DDA and year of manufacture as per direction of Engineer -in - charge. (a) 70mm thick(preferred grey colour)	140.00	Sqm	1100.00	Rupees One Thousand One Hundred Only	154000.00
6	Deslitting of S.W. Drains and chambers by removing of covers and placing in position after cleaning the drain of water and silt as per direction Engineer-in-charge.	42.00	Cum	120.00	Rupees One Hundred Twenty Only	5040.00

7	Disposal of maba/earth/building rubbish by mechanical transport including loading, unloading within 5km lead	113.00	Cum	70.00	Rupees Seventy Only	7910.00
	TOTAL					1456445.00


 Executive Engineer
 Western Division-3
 DDA