

DELHI DEVELOPMENT AUTHORITY
ELECTRICAL DIVISION NO-I

By speed post

NO. F-14 (120)/A/c/ED-I/DDA/2012-13/

375

Dated:

28 ²/₁₃

To,

M/s Sanjay sales Corporation,
18/16, Kammruddin Nagar,
Nangloi,
Delhi-110041.

Sub: - M/o Various parks under NA-I East Zone

(SH: - Providing flood light luminaries at play field-I Vasundhra Enclave under HD-VII DDA.)

Dear Sir,

Your negotiated item rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority as under:-

- | | | |
|---|---|--|
| 1. Estimate Cost | : | Rs. 4,75,919.00 (Rs. Four lacs seventy Five Thousand Nine Hundred Nineteen Only) |
| 2. Accepted Amount | : | Rs. 4,73,630.00 (Rs. Four Lacs Seventy Three Thousand Six Hundred Thirty Only). |
| 3. Percentage for the Purpose clause-12 | : | 0.48% (Zero Point Four Eight) below of the Estt. cost |
| 4. Timed allowed | : | 30 Days (Thirty Days) |

You are requested to attend this office along with a non-judicial stamp paper worth Rs. 50.00 (Rs. Fifty only) to sign the formal agreement within fifteen days from stipulated date of start. failing which the award is likely to be withdrawn and earnest money PG amount will be forfeited absolutely to DDA.

You are requested to contact AE-4/ED-I of this Division and start the work at once Please note that the time allowed for carrying out the work shall be reckoned after 10th day of issue of this letter. Your letter dated 22.01.2013 shall also part of the agreement.

Your faithfully

[Signature]
28/2/13
Executive Engineer (E)
Electrical Division No-I
DDA

Copy to:-

1. Chief Engineer (Elect.) DDA
2. Income Tax Officer (Const.) ITO Building, Delhi.
3. EE (QC) DDA (Elect.) DDA
4. Sr. AO (W)-III/DDA
5. Sales Tax Officer (work contract cell) sales tax building, New Delhi
6. The Labour Commissioner, 5 Sham Nath Marg, Delhi-54
7. SE(E) Circle-III, DDA
8. FO to CE (Elec.) DDA
9. EE/ED-2/DDA to ED-12/DDA (Elect.)
10. Sr. AO CAU/EZ/DDA
11. AE (P)/ED-I/DDA
12. AE-4 along with a copy of Schedule and conditions.
13. Copy for agreement.
14. A/Cashier/ED-I/DDA
15. DDA web site i.e. dda.tender@dda.org.in

[Signature]
28/2/13
EE/ED-I/DDA

DELHI DEVELOPMENT AUTHORITY

Name of work : M/o Various parks under NA-I East Zone
SH: Providing flood light luminaries at play field-I Vasundhara Enclave under HD-VII DDA

SCHEDULE OF QUANTITIES
NIT No.:101/EE/ELD-J/DDA/2012-2013
Estimated Cost: Rs. 4,75,919.00


NAME OF THE FIRM

SANJAY SALES CORPORATION

S. No.	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	Supplying and fabrication of 9 mtr. height swaged type steel tubular pole 410 SP-28 conforming to IS: 2713-1980 (Part-II) with base plate of size 300mm x 300mm x 6mm thick and having mounting & installation arrangement of the following accessories i/c S/F of 50mm dia GI pipe B Class for incoming and outgoing cables with locking arrangement connection testing painting and numbering etc. as required a) 32 Amp. DPMCB-1 No. b) Connector 4 way - 1 No. c) Neutral link 4 way - 1 No.	8.00	Each	11800.00	Rupees Eleven Thousand Eight Hundred Only	94400.00
2	S/F of 150 watt metal halide aluminium die cast integral IP65 Flood lighting luminaries with toughened glass complete with all accessories & ballast suitable for double ended 150 watt metal halide lamp i/c S/F of 150 W MH lamp connection testing etc., complete as required.	16.00	Each	5500.00	Rupees Five Thousand Five Hundred Only	88000.00
3	S/F and installation of MS bracket suitable for installation on 9 mtr. steel tubular pole 410 SP-28 having 2 Nos. arms of length 500 mm each of 50mm dia MS pipe i/c making holes for installation of flood light luminaries painting etc. complete as required	8.00	Each	1350.00	Rupees One Thousand Three Hundred Fifty Only	10800.00
4	Erection of metallic street light standard pole of length exceeding 8 mtr. but not exceeding 11 mtr. in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate, 40mm nominal size) foundation with cement concrete collar of size 0.4 mtr. dia x 0.5mtr. height to accommodate the looping type cable end box including excavation and refilling etc. as required.	8.00	Each	3200.00	Rupees Three Thousand Two Hundred Only	25600.00
5	Supplying and testing of following sizes XLPE insulated & PVC sheathed armoured aluminium LT cable to 1.1 KV grade conforming to IS: 7098 etc. complete as a) 2x25sqmm.	900.00	Mtr.	140.00	Rupees One Hundred Forty Only	126000.00
6	Laying of one No. PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of sizes not exceeding 25sqmm. Direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required.	500.00	Mtr.	120.00	Rupees One Hundred Twenty Only	60000.00
7	Laying of 1 No. additional PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size not exceeding 25sqmm. direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc. as required.	350.00	Mtr.	70.00	Rupees Seventy Only	24500.00

54,29,360 ~

8	Laying of one No. PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size not exceeding 25sqmm. in the existing RCC / HUME/ STONEWARE/ DWS pipe/ metal pipe as required.	48.00	Mtr.	20.00	Rupees Twenty Only	960.00
9	Supplying & drawing of 3x2.5sqmm. FR PVC insulated copper conductor, single core cable in the existing pole etc. complete as required.	112.00	Mtr.	70.00	Rupees Seventy Only	7840.00
10	Earthing with GI earth pipe 4.5mtr. long 40mm dia including accessories, and watering pipe etc. with charcoal / coke and salt as required.)	2.00	Set	2600.00	Rupees Two Thousand Six Hundred Only	5200.00
11	Supplying and laying 6 SWG GI wire at 0.50m below ground level for conductor earth electrode i/c connection / termination wire GI thimble etc. as required.	600.00	Mtr.	18.00	Rupees Eighteen Only	10800.00
12	Providing & fixing 25mm x 5mm GI strip on surface or in recess for loop earthing etc. as required.	5.00	Mtr.	90.00	Rupees Ninety Only	450.00
13	Supplying & fabrication and installation of timer box of size 400mm x 300mm x 250mm of 1.6mm thick CRCA MS sheet on the angle iron frame 25mm x 25mm x 3mm thick and suitable size having the four legs of 120mm long having the following accessories connection painting testing etc. complete as required. a) Reset synchronous time- 1 No. b) 32 Amps. Contactor block-1 No. c) Toggle switch 6 Amps. (for bye pass arrangement)-1	1.00	set	8000.00	Rupees Eight Thousand Only	8000.00
14	Supplying and fixing following way, single pole and neutral sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, MCB/RCCB/ Isolator) 2+6 way single door	1.00	Set	1000.00	Rupees One Thousand Only	1000.00
15	Supplying and fixing 5 Amps. To 32 Amps. Rating 240 volts 'C' series, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. a) 32 Amp. SP & N MCB	4.00	Each	450.00	Rupees Four Hundred Fifty Only	1800.00
16	Fabrication, supplying and installation of wire mesh guard made out of 10 SWG MS wire and suitable size of MS strip suitable for 150 watt metal halide luminaries i/c welding etc. complete required.	16.00	Each	450.00	Rupees Four Hundred Fifty Only	7200.00
17	Supplying & fixing of galvanized steel barbed wire ground the poles of all sizes upto required height as decided by Engineer-in-Charge i/c P/F of clamps, nut bolts etc. complete as required.	60.00	Mtr.	18.00	Rupees Eighteen Only	1080.00
TOTAL						473630.00


 अधिशासी अभियन्ता (विद्युत)
 विद्युत खण्ड-1
 दिल्ली विकास प्राधिकरण
 शावरमुस्य दिल्ली-110092