

**DELHI DEVELOPMENT AUTHORITY
EASTERN DIVISION NO.-14
SEED BED PARK SHAKARPUR
DELHI-110092**

E- TENDER PRESS NOTICE

The Executive Engineer/ Eastern Division No.-14 on behalf of Delhi Development Authority invites online Item rate tenders from approved and eligible contractors of DDA, CPWD and those of appropriate list of M.E.S., BSNL, Railway from the following works.

S.No.	NIT No.	Name of Work & Location	Estimate d Cost put to tender	Earnest Money	of Period Completion	Last Date & time of submissi on of tender	Period during which EMD, Cost of Tender Document, E- Tender processing Fee and other Documents shall be submitted	Time & date of Opening of tendering
1	2	3	4	5	6	7	8	9
1.	NIT No. 21 EE/ED-14/ DDA/ 2012-13	M/o Various scheme under NA-II East Zone SH: Providing and laying paver blocks in Park adjoining Pkt-'B' Mayur Vihar Phase-II	Rs. 3,92,291.00	Rs. 7,846.00	One Month	01.04.2013	Upto 03:30 PM on 02.04.2013 <u>Rs. 7846.00</u> <u>Rs. 525.00</u> <u>Rs. 562.00</u>	05.04.2013
2.	NIT No. 23 EE/ED-14/ DDA/ 2012-13	M/o various scheme under NA-II /East Zone SH: Providing Sweeping /scavenging etc. service at Distt. Centre Mayur Palace, Mayur Vihar Phase-I	Rs. 2,70,594.00	Rs. 5412.00	Six months	01.04.2013	Upto 03:30 PM on 02.04.2013 <u>Rs. 5412.00</u> <u>Rs. 525.00</u> <u>Rs. 562.00</u>	05.04.2013
3.	NIT No. 25 EE/ED-14/ DDA/ 2012-13	M/o Various scheme under NA-II (EZ) SH: Sweeping / Scavenging of CC Path, drain etc. at LSC Pocket-B & CSC Pkt. C, A & E at Mayur Vihar Phase-II	Rs. 73,330.00	Rs. 1467.00	Six months	01.04.2013	Upto 03:30 PM on 02.04.2013 <u>Rs. 1467.00</u> <u>Rs. 158.00</u> <u>Rs. 562.00</u>	05.04.2013
4.	NIT No. 28 EE/ED-14/ DDA/ 2012-13	M/o Various scheme under NA-II/East Zone SH: Providing and fixing concertina coil fencing and repair of Bajri path in Triangular Park behind Pkt.-III Mayur Vihar Phase-I	Rs. 2,16,554.00	Rs. 4330.00	One Months	01.04.2013	Upto 03:30 PM on 02.04.2013 <u>Rs. 4330.00</u> <u>Rs. 525.00</u> <u>Rs. 562.00</u>	05.04.2013

The tender document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents can be seen from website www.tenderwizard.com/DDA or www.dda.org.in free of cost.

The enlistment of the contractors should be valid on the last date of submission of tenders.

In case only the last date of submission of tender is extended, the enlistment of contractor should be valid on the original date of submission of tenders.

Those contractors not registered on the website mentioned above, are required to get registered beforehand. The intending bidder must have valid class-II digital signature to submit the bid.

Conditions for Non-DDA, Non-CPWD contractors only, if tenders are also open to Non-DDA, Non-CPWD contractors (For works estimated to cost up to Rs. 15 Crore)**

Earnest Money in the form of Treasury Challan or Demand Draft or Pay order or Banker's Cheque or Deposit at Call Receipt (drawn in favour of Accounts Officer of concerned Zone) or Bank Guarantee of any Scheduled Bank (in the name of Executive Engineer concerned) shall be scanned and uploaded to the e-tendering website within the period of tender submission and original should be deposited in office of Executive Engineer.

A part of earnest money is acceptable in the form of bank guarantee also. In such case, 50% of earnest money or Rs. 20 lakh, whichever is less, will have to be deposited in shape prescribed above and balance in shape of Bank Guarantee.

Interested contractor who wish to participate in the tender has also to make following payments in the form of Demand Draft or Pay order or Bankers Cheque of any Scheduled Bank and to be scanned and uploaded to the e-tendering website within the period of tender submission.

(i) Cost of Tender Document – Rs 525.00 and (Rs. 158/- on Sl. No. 3 only) drawn in favour of Sr. Accounts Officer CAU (EZ)/ DDA

(ii) e-Tender Processing Fee – Rs 562.00 drawn in favour of "ITI Limited" payable at Delhi.

Treasury Challan or Demand Draft or Pay order or Banker's Cheque or Deposit at Call Receipt or Bank Guarantee of any Scheduled Bank against EMD, Cost of Tender Document and Cost of Tender Processing Fee shall be placed in single sealed envelope superscripted as, "Earnest Money, Cost of Tender Document and Cost of Tender Processing Fee" with name of work and due date of opening of the bid also mentioned thereon.

Copy of Enlistment Order and certificate of work experience as required shall be scanned and uploaded to the e-tendering website within the period of tender submission and certified copy of each shall be deposited in a separate envelop marked as, "Other Documents".

Both the envelopes shall be placed in another envelope with due mention of Name of work, date & time of opening of tenders and to be submitted in the office of Executive Engineer during the period mentioned above.

Online tender documents submitted by intending bidders shall be opened only of those bidders, whose Earnest Money Deposit, Cost of Tender Document and e-Tender Processing Fee and other documents placed in the envelope are found in order.

Hanuk
15-3-13
o/c EE/ED-14/ DDA
2

No. F.1(1) EE/ED-14/ DDA/ 2012-2013/ 298.
Copy to :

Dated: 15.3.13.

1. CE (EZ) DDA
2. SE/CC-III/ DDA
3. Sr. AO/ CAU/ EZ/ DDA
4. Tender Clerk, CAU/ EZ/ DDA
5. FO to CE (EZ) DDA
6. Tender Clerk, Vikas Minar, Ground Floor, New Delhi.
7. CPWD Contractor Association 'Y' Shape Building ITO New Delhi.
8. DDA Builders Association 2/11 WHS Kirti nagar, Delhi.
9. Trans Yamuna DDA Contractor Association 11-12, Vir sawarkar Block market Budh Bazar, Gandhi nagar, Delhi.
10. DDA Contractor Association Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association near barrack No. 1, Vikas Kuteer, ITO New Delhi.
12. General Secy. Delhi Contractor Building Association, Ch. Prem Raj Building New New Chandrawal, Delhi.
13. East Delhi DDA Contractor Association (Regd.) 45/2C East Azad Nagar, Delhi.
14. Delhi Contractor Welfare Association (Regd.) 306 Masjid Moth South Extn. Part-II, Rai Sahab Market, New Delhi-110049.
15. Delhi Govt. Welfare Association (Regd.) 179, Treveni Apartment Near Police Station, Vivek Vihar Delhi.
16. AAO/ Cashier/ ED-14/ DDA
17. Notice Board/ ED-14/ DDA
18. DDA Website i.e. ddatender@dda.org.in
19. ITI i.e. dda.tender@gmail.com

14/3-13
15-3-13
o/c EE/ED-14/ DDA
2

NIT No-2/EO-14

Name of work : M/o Various scheme under NA-II East Zone
SH: Providing and laying paver blocks in Park adjoining Pkt-'B' Mayur Vihar Phase-II

S.No.	Description of item	Qty.	Unit	Rate	Amount
1.	Providing and laying 60mm thick factory made cement concrete interlocking paver blocks of M-30 Grade made by block making machine with strong vibratory compaction, of approved size, design and shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-Charge.	731.00 sqm.	Sqm.		

Harsh
15.3.13
Executive Engineer
Eastern Division-14
DDA 2

NTN-23/ED-14

Name of work: M/o various scheme under NA-II /East Zone

SH; Providing Sweeping /scavenging etc. service at Distt. Centre Mayur Palace, Mayur Vihar Phase-I

S.No.	Description of item	Qty.	Unit	Rate	Amount
1.	Daily cleaning of road, CC paths & desilting / cleaning of drain etc. i/c T & P complete and removing the chockage, if any, collection of garbage, silt, soil, sludge, malba, building rubbish and refuse of all kind & dead animals etc. if any collecting in nearby dustbin daily and then loading, unloading & carriage by mechanical transport in nearest low laying area or as per the direction of Engineer-in-Charge as complete.	180 days	Per Month		
Conditions:					
1.	All T & P shall be arranged by agency.				
2.	Men/ machine shall be worked as per direction of Engineer-in-Charge .				
3.	Agency shall engage 5.24 Nos. Safai Karamchari minimum per day.				
4.	The recovery of default of man power shall be Rs. 320/- per person per day.				

Executive Engineer
Eastern Division-14
D.D.A. 2

15-3-13

NIT No. 25/ ED-14

Name of work; M/o Various scheme under NA-II (EZ)

C, A & E at Mayur Vihar

SH: Sweeping / Scavenging of CC Path, drain etc. at LSC Pocket-B & CSC Pkt. C, A & E at Mayur Vihar
Phase-II

S.No.	Description of Item	Qty.	Unit	Rate	Amount
1.	Daily cleaning of Road CC Path and Desilting / cleaning of drain etc. complete and removing chowkage if any, collection of garbage, silt, soil, sludge, malba, building rubbish and refuse of all kind and dead animals etc. if any collecting in nearby dustbin daily and then loading unloading and carriage to nearest low lying area or as per direction of Engineer-in-Charge	180.00	Day		

Terms & Conditions:

1. The recovery of default man power shall be @ Rs. 320/- per day per person.
2. Whole area under this pocket shall be kept clean.
3. All T & P shall be arranged by agency.
4. Man power / machine shall be worked as per direction of Engineer-in-Charge
5. Agency shall be engaged 1.42 S.K. minimum per day

Y. Anand
15.3.13
Executive Engineer
Eastern Division-14
D.D.A. G

NIT No. 28/ED-14

SCHEDULE OF QUANTITIES

Name of work: M/o Various Schemes in Under NA-II/EZ
 SH: Providing and fixing Concertina coil fencing and repair of Bajri Path in Triangular Park behind
 Pkt -III Mayur Vihar Ph-I.

S.No.	Description of Item	Qty.	Unit	Rate	Amount
1	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	507.00	Meter		
2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge	4.50	Cum.		
3	In cement Mortar	18.00	Sqm.		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	12.00	Cum.		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	507.00	Meter		
6	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5mm) including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	3.20	Cum.		
7	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand) including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	25.00	Sqm.		
8	Making bajri path including preparation of subgrade, supplying and laying brick aggregate of 50mm nominal size 7.5 cm deep with blinding material consisting of 12 mm moorum and 12 mm red bajri consolidated with road roller.	898.00	Sqm.		
9	Supplying, stacking and Spreading 6 mm thick red bajri, watering and rolling complete including preparation of the surface and rolling. With road roller/ hand roller. Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand) : Raised and cut pointing	20.00	Sqm.		

10	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 meter openable length (total length 90 m) having 50 nos rounds per 6 meter length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron all complete as per direction of Engineer-in-charge with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	113.00	Meter.		
11	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	595.00	Kg.		
12	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	48.00	Sqm.		
13	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	48.00	Sqm.		
14	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	36.00	Sqm.		
15	White washing with lime to give an even shade : Old work (two or more coats)	314.00	Sqm.		
16	White washing with lime to give an even shade: New work (three or more coats)	30.00	Sqm.		
17	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	22.00	Sqm.		
18	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	90.00	Sqm.		
19	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	14.00	Cum.		
20	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns.	62.00	Sqm.		

Executive Engineer
Eastern Division-14
D.D.K. 2

15/3-13