# क्षा ५ ज ५ The Gazette of India

**EXTRAORDINARY** 

भाग II--खण्ड 3-उप-खण्ड (il)

PART II-Section 3-Sub-section (ii)

प्राधिकार से-प्रकाशित PUBLISHED BY AUTHORITY

सं. 1001] No. 10011

नई दिल्ली, बृहस्पतिवार, सितम्बर ७, २००६/भाद्र १६, १९२८

NEW DELHI, THURSDAY, SEPTEMBER 7, 2006/BHADRA 16, 1928

#### शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

#### अधिसूचना

नई दिल्ली, 7 सितम्बर, 2006

का.आ. 1456(अ).—यत: दिल्ली मास्टर प्लान-2001 में केन्द्र सरकार का जिन कुछ संशोधनों को करने का प्रस्ताव है उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) की धारा 44 के प्रावधानों के अनुसार दिनांक 21 जुलाई, 2006 के सं. का.आ. 1161(अ) के तहत सार्वजनिक सूचना के रूप में भारत के असाधारण राजपत्र में प्रकाशित किया गया था जिसमें उक्त अधिनियम की धारा 11-ए की उप-धारा (3) के तहत यथा अपेक्षित उक्त नोटिस की तारीख के तीस दिन के भीतर आपत्तिया/सुझाव आमंत्रित किए गए थे;

- 2. यतः प्रस्तावित संशोधनों के बारे में प्राप्त आपत्तियों/सुझावों पर दिल्ली विकास प्राधिकरण द्वारा संगत नियमों के तहत विधिवत गठित जांच बोर्ड द्वारा विचार किया गया था और प्राधिकरण ने उक्त बोर्ड की रिपोर्ट पर विचार करने के पश्चात्, दिल्ली मास्टर प्लान-2001 में, उक्त सार्वजनिक सूचना में यथा उल्लिखित संशोधन की, कुछ परिवर्तनों के साथ सिफारिश की है;
- 3. और यत: केन्द्र सरकार ने मामले क्रे सभी संगत पहलुओं पर ध्यानपूर्वक विचार करने के पश्चात् दिल्ली मास्टर प्लान-2001 को संशोधित करने का निर्णय लिया है;
- 4. अतः, अब, उक्त अधिनियम की धारा 11-ए की उप-धारा (2) द्वारा प्रवत्त शक्तियों का प्रयोग करते हुए केन्द्र सरकार, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से उक्त दिल्ली मास्टर प्लान-2001 में एतद्द्वारा निम्नलिखित संशोधन करती है :-

#### संशोधन :

भारत के राजपत्र, भाग II, खंड 3, उप-खंड (ii) दिनांक 1-8-1990 में निम्नलिखित शामिल किया जाएगा :--

(1) अंग्रेजी पाठ के पृष्ठ 165 पर (दायीं तरफ) अनुच्छेद 10.0 मिश्रित उपयोग विनियम, के अंतर्गत दिनांक 28-3-2006 की अधिसूचना सं. का.आ. 425(अ) द्वारा यथा-संशोधित विद्यमान प्रावधानों को निम्नलिखित द्वारा प्रतिस्थापित किया जाएगा:-

2783 GI/2006

(1)

#### 10.0 मिश्रित उपयोग विनियमः

इस अध्याय में कुछ अनुमेय प्रयोजनों हेतु भूमि की मिश्रित उपयोग नीति आती है। यह नीति, जिन प्रयोजनों हेतु इसे नियोजित किया गया था, उनसे मिन्न भूमि उपयोग की अनुमित देने की आवश्यकता को मानती है और उन शर्तों को निर्दिष्ट करती है, जिनके अंतर्गत इसे विभिन्न स्थितियों में लागू किया जा सकता है। उक्त नीति को लागू करने के लिए अपनाई जाने वाली सामान्य पद्धित और ऐसे क्षेत्रों में ऐसे अनिच्छित उपयोग के प्रभाव का सामना करने के लिए किए जाने वाले शमनीय उपाय भी बताए गए हैं।

#### 10.1 मिश्रित उपयोग के नियंन्रक सिद्धांत

- (i) इस अध्याय के प्रयोजनों हेतु मिश्रित उपयोग का आशय आवासीय परिसरों में गैर-आवासीय कार्यकलाप के प्रावधान से है ।
- (ii) नीति का लक्ष्य ऐसे कार्यकलाप हेतु सामाजिक-आर्थिक आवश्यकता और आवासीय क्षेत्रों में ज्वित कार्यकलाप के पर्यावरण प्रभाव के बीच संतुलन बनाए रखना है।
- (iii) मिश्रित उपयोग की नीति आवासों के निकटस्थ क्षेत्र में व्यावसायिक कार्यकलापों तक पहुंचने की अनुमति देती है और शहर में विभिन्न जोनों में आने-जाने की आवश्यकता को कम करती है। तथापि, साथ ही साथ, भीड़भाड़, बढ़ते हुए यातायात और नागरिक सुविधाओं पर बढ़ते हुए दबाव से संबंधित विपरीत प्रभाव को संभालने और कम करने के उद्देश्य से इसे विनियमित करने की आवश्यकता है।
- (iv) मिश्रित उपयोग की अनुमित देने वाले अध्यारोही सिद्धांतों का प्रयोजन सामुदायिक आवश्यकताओं को मानना तथा उन्हें पूरा करने के लिए पर्याप्त प्रावधान करना, पर्यावरणीय प्रभाव को कम करना तथा सुरक्षित एवं सुविधाजनक परिवहन और पार्किंग की उचित व्यवस्था करना है।
- (v) मिश्रित उपयोग की अनुमति लुटियंस बंगला क्षेत्र, सिविल लाइन्स, सरकारी आवास, सार्वजनिक और निजी एजेंसियों को सांस्थानिक व स्टाफ आवासों और विरासत संरक्षण समिति द्वारा सूचीबद्ध किए गए भवनों/अहातों में नहीं दी जाएगी।

#### 10.2 आवासीय क्षेत्रों में मिश्रित उपयोगः

#### 10.2.1 अलग-अलग दृष्टिकोण :

(i) मिश्रित उपयोग नीति में अलग-अलग दृष्टिकोण की आवश्यकता इस तथ्य से उत्पन्न हो गई है कि दिल्ली देश की राजधानी होने तथा आर्थिक कार्यकलाप का एक महत्वपूर्ण केन्द्र होने के कारण यहां आवासीय क्षेत्रों के प्रकार(टाइपोलॉजी) में काफी मिन्नता है। लुटियंस-दिल्ली के माग के रूप में और दिल्ली विकास प्राधिकरण द्वारा किए गए नियोजित विकास की प्रक्रिया के माध्यम से निर्मित नियोजित आवासीय कालोनियों के अतिरिक्त चार दोवारी शहर विशेष क्षेत्रों और शहरीकृत गांवों में प्राधिकृत आवासीय क्षेत्र है। अन्य नियोजित क्षेत्रों में पुनर्वास कालोनियां, दिल्ली विकास अधिनियम से पूर्व बर्सी कालोनियां, भारत पाकिस्तान के विभाजन के बाद पुनर्वास कालोनियां शामिल है। दिल्ली के विभिन्न भागों में नियमित

की गई अनधिकृत कालोनियां, अनधिकृत कालोनियां तथा स्लम एवं झुग्गी-झोपड़ी समूह भी

- (ii) इसके अतिरिक्त निवासियों द्वारा स्वयं आवश्यक या विछनीय समझे गए गैर आवासीय कार्यकलाप की सीमा निवासियों की सामाधिक-आर्थिक स्थिति और उस क्षेत्र में विकास की पुरानी पद्धित के आधार पर शिल्ल-भिल्ल हैं। कुछ कार्सोनियों को, अपनी आजीविका के अमिल्ल भाग के रूप में गैर अवासीक कार्यकलाप की जरूतत हो सकती है, जबकि कुछ अन्य कालोनियां अपनी कालोनियों और अध्यक्ष के बेट्टों के विशेष आवासीय स्वरूप को बनाए रखना चाहेगी।
- (iii) अतः दिल्ली में मिश्रित छन्छोम नीति को लागू करने के लिए अलग-अलग दृष्टिकोण अपनाने का प्रस्ताव है। अध्यक्षश्च जाने दाला अलग-अलग दृष्टिकोण संपत्ति कर निर्धारण के यूनिट एरिया सिद्धांत के रूप में दिल्ली नगर निगम द्वारा अपनाए गए क से छ तक कालोनियों के वर्गीकरण के आबार पर होगा।

#### 10.2.2 मिश्रित उपयोग की किस्प्रें

इस अधिसूचना के प्रावधानों के अध्यक्षीन आवासीय परिसरों में मिश्रित उपयोग की निम्नलिखित तीन व्यापक किस्में अनुभेय होंगी:-

- (i) अधिसूचित मिश्रित उपयोग मार्गों से लगे प्लाटों में, पैरा 10.6 में दी गई शर्तों के अनुसार फूटकर दुकानों के रूप में वाणिज्यिक कार्यकलाप ।
- (ii) पैरा 10.3.2 में निर्धारित न्यूनतम मार्गाधिकार वाली सड़कों से लगे प्लाटों में पैरा 10.7 में निर्दिष्ट शर्तों के अनुसार, पैरा 10.7.1 में सूचीबद्ध सामान्यतः सार्वजनिक और अर्ध सार्वजनिक सुविधाओं के रूप में अन्य कार्यकलाप
- (iii) पैरा 10.8 में निर्दिष्ट शर्तों के अनुसार व्यावसायिक कार्यकलाप

उपर्युक्त किस्म के मिश्रित उपयोग, परवर्ती पैराग्राफों में निर्दिष्ट सामान्य शर्तों और निबंधनों के अध्यधीन होंगे ।

10.3 वर्तमान शहरी क्षेत्रों और शहरीकरण योग्य क्षेत्रों में मिश्रित भूमि उपयोग का निर्धारणः

दिल्ली के शहरीकृत/शहरी क्षेत्रों तथा शहरीकरण योग्य क्षेत्रों, दोनों में, मिश्रित उपयोग क्षेत्रों/मार्गों का निर्धारण निम्नानुसार होगाः 10.3.1 पहले से शहरीकृत / शहरी क्षेत्रों में से निम्नलिखित क्षेत्रों में मिश्रित उपयोग अनुमेय होगा :-

- i. दिल्ली मास्टर प्लान-2001 के अंतर्गत सक्षम प्राधिकरण द्वारा पहले अधिसूचित और अनुबंध-। में निर्दिष्ट (निर्दिष्ट भूभागों / मार्गों की सूची) सभी मार्गों /भूभागों पर ।
- ii पूर्व में घोषित व्यावसायिक क्षेत्रो/ मार्गो अथवा जहां दिल्ली मास्ट्र प्लान 1962 में व्यावसायिक उपयोग की अनुभित दी गई थी, उन आवासीय क्षेत्रों और मार्गों / भूभागों में, दिल्ली मास्ट्र प्लान-1962 में अनुभेय सीमा तक, ऐसा उपयोग जारी रहेगा।
  - वस्तावेजी प्रमाण की शर्त पर 1962 से पूर्व आवासीय क्षेत्रों में मौजूद वाणिज्यिक कार्यकलाप ।
  - iv भविष्य में मिश्रित भूमि उपयोग की पहचान / अधिसूचना पैरा 10.3.2 में दिए गए मानदण्ड के आधार पर तथा पैरा 10.3.3 में निर्धारित प्रक्रिया के अनुसार होगी तथा संबंधित स्थानीय निकायों द्वारा इसका व्यापक प्रचार किया जायेगा !
- 10.3.2 विभिन्न श्रेणियों की कालोनियों में अनुमेय मिश्रित उपयोग की सीमा को नीचे लिखे अनुसार और अधिक स्पष्ट किया जाता है :-

#### 1. श्रेणी क और ख में आने वाली कालोनियों में

क और ख श्रेणियों के अधीन आने वाली कालोनियों में निम्नलिखित के सिवाय कोई व्यवसायिक कार्यकलाप अनुमेय नहीं होगा :-

- पैरा 10.8 में दी गई शर्तों के अध्यधीन व्यवसायिक कार्यकलाप ।
- मास्टर प्लान सडकों जिन्हे क्रमशः मिश्रित उपयोग मार्गो और व्यवसायिक मार्गो के रूप में अधिसूचित किया गया है, से सटे भूखण्डों में एक भूखण्ड की गहराई तक मिश्रित उपयोग और व्यवसायिक कार्यकलाप क्योंकि ऐसी सडकें कालोनियों की आन्तरिक सडकें नहीं हैं (बशर्ते कि मिश्रित उपयोग मार्गो अथवा व्यवसायिक मार्गों के रूप में कालोनियों से सटी मास्टर प्लान सड़कों को अधिसूचित करने के लिए संबंधित रेजीडेंट वेलफेंग्टर एसोसिएशन का अनुरोध आवश्यक नहीं होगा ) ।
- "अन्य कार्यकलाप" नियमित भूखण्ड विकास में न्यूनतम 18 मीटर मार्गाधिकार की सड़कों से सटे भूखण्डों में पैरा 10.7 में दी गई, शर्तों के अध्यधीन पैरा 10.7.1 में यथा परिभाषित गेस्ट हाउसों, निर्सिंग होमों और पूर्व-प्राथमिक विद्यालयों तक सीमित है क्योंकि ये कार्यकलाप" सार्वजिनक और अर्द्ध- सार्वजिनक सुविधाओं के प्रकार हैं । नए बैंक और फिटनेस केन्द्र इस अधिसूचना की तारीख से अनुमेय नहीं होंगे । तथापि दिल्ली मास्टर प्लान 2001 के अधीन इस संबंध में समय-समय पर जारी अधिसूचनाओं के अनुसार बैंक और फिटनेस केन्द्र जो इस अधिसूचना की तारीख को पहले से ही मौजद हैं, और न्यूनतम 18 मीटर मार्गाधिकार की सड़कों से सटे भूखण्डों में हैं , अनुमेय रहेंगे ।
- नियमित रिहायशी भूखण्ड विकास में कालोनी के भीतर न्यूनतम 18 मी0 मार्गाधिकार वाले ऐसे मिश्रित उपयोग मार्गो पर पैरा 10.6 के अनुसार फुटकर दुकाने जिन्हें पैरा 10.3.3 के अनुसार अधिसूचित किया गया है यदि पैरा 10.10 के अनुसार संबंधित रेजीडेन्ट वेल्फेयर एसोसिएशन की ओर से विशेष अनुरोध किया जाता है।

#### नोट :

दिल्ली मास्टर प्लान -2001 के अन्तर्गत पूर्व में अधिसूचित क और ख श्रेणी की कालोनियों के भीतर मिश्रित उपयोग मार्गों पर व्यवसायिक कार्यकलाप तत्काल प्रभाव से बन्द हो जाएंगे (मास्टर प्लान सड़कों से सटे भूखण्डों के सिवाय)।

#### 2. ग और घ श्रेणियों में आने वाली कालोनियों में :

- अनुलग्नक-। में सूचीबद्ध अधिसूचित मिश्रित उपयोग मार्गों से सटे भूखण्डों में पैरा 10.6 में दी गई शर्तों के अनुसार फुटकर दुकानों के रूप में मिश्रित उपयोग अनुमेय रहेगा।
- पैरा 10.7 की शर्तों के अध्यधीन नियमित भूखण्ड विकास में न्यूनतम 18 मी0 आर ओ डब्ल्यू पुनर्वास कालोनियों में 13.5 मी0 आर ओ डब्ल्यू तथा , नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, विशेष क्षेत्रों और शहरी गांवों में 9 मी0 मार्गाधिकार की सडकों से सटे भूखण्डों में पैरा 10.7 के अनुसार अन्य कार्यकलाप अनुमेय होंगे ।
- भिवष्य में नियमित रिहायशी भूखण्ड विकास में न्यूनतम 18 मी० मार्गाधिकार, पुनर्वास कालोनियों में 13.5 मी० मार्गाधिकार तथा पैरा 10.3.3 के अनुसार नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, पुरानी दिल्ली, विशेष क्षेत्र और शहरी गांवों में 9 मी० मार्गाधिकार के मिश्रित उपयोग मार्गों की अधिसूचना पैरा 10.10 के अनुसार संबंधित रेजीडेन्ट वेल्फेयर एसोसिएशनों के परामर्श के अध्यधीन होगी।
- पैरा 10.3.3 के अनुसार पैदल शापिंग मार्गी में मिश्रित उपयोग अनुभेय होगा ।
- पैरा 10.8 में नियत शर्तों के अनुसार व्यवसायिक गतिविधियां अनुमेय होंगी ।

#### .3. इ.च और छ श्रेणियों में आने वाली कालोनियों में :

- अनुलग्नक-। में सूचीबद्ध अधिसूचित मिश्रित उपयोग मार्गों से सटे भूखण्डों में पैरा
   10.6 में दी गई शर्तों के अनुसार फुटकर दुकानें अनुमेय रहेंगी ।
- पैरा 10.7 की शर्तों के अध्यधीन नियमित भूखण्ड विकास में न्यूनतम 13.5 मी0 मार्गाधिकार पुनर्वास कालोनियों में 9 मी0 मार्गाधिकार तथा नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, पुरानी दिल्ली, विशेष क्षेत्र और शहरी गांवों में 6 मी0 मार्गाधिकार की सड़कों से सटे भूखण्डों में पैरा 10.7 के अनुसार अन्य कार्यकलाप अनुमेय होंगे।
- · पैरा 10.8 में दी गई शर्तों के अध्यधीन व्यवसायिक कार्यकलाप अनुभेय होंगें 1
- भविष्य में नियमित रिहायशी भूखण्ड विकास में न्यूनतम 13.5 मी० मार्गाधिकार, पुनर्वास कालोनियों में 9 मी० मार्गाधिकार तथा नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, पुरानी दिल्ली विशेष क्षेत्र और शहरी गांवों में 6 मी० मार्गाधिकार के मिश्रित उपयोग मार्गों की अधिसूचना पैरा 10.3.3 के अनुसार होगी ।
- 📩 पैरा 10.3.3 के अनुसार पैदल शापिंग मार्गी में मिश्रित उपयोग अनुमेय होगा ।

## सभी श्रेणियां की कालोनियां में ग्रुप हाऊसिंग

- केवल व्यवसायिक कार्यकलाप अनुगेय होगा । ग्रुप हाऊसिंग की ले-हाउट प्लान में विशेष रूप से उल्लिखित फुटकर दुकाने अनुभेय होंगी ।
- 5. नई दिल्ली नगरपालिका परिषद क्षेत्र (लुटियन बंगला जोन, सरकारी आवास, संस्थागत सार्वजिनक और निजी एजेन्सी के स्टाफ आवास तथा हेरीटेज संरक्षण समिति द्वारा सूचीबद्ध भवनों/क्षेत्रों के सिवाए) में आने वाली कालोनियों के संबंध में नई दिल्ली नगरपालिका परिषद द्वारा मौजूदा मिश्रित उपयोग मार्गों/ भूभागों को अधिसूचित किया जायेगा । मिश्रित उपयोग मार्गों/ भूभागों की भावी अधिसूचना फील्ड स्तरीय सर्वेक्षण करने के बाद तथा संबंधित रेजिडेन्ट वेलफेयर एसोशिएसनों के परामर्श से जारी की जायेगी तािक सामुदायिक आवश्यकताओं, पर्यावरणीय प्रभाव और यातायात परिचालन/पर्याप्त पार्किंग का आकलन किया जा सके।

## 10.3.3 भविष्य में शहरी क्षेत्रों में मिश्रित उपयोग मार्गों की अधिसूचना

i) मिश्रित उपयोग मार्ग के रूप में किसी मार्ग अथवा भूभाग का निर्धारण करने के लिए न्यूनतम मार्गाधिकार निम्नवत होगा

क और ख कालोनियों में:

नियमित भूखण्ड विकास में 18 मीटर मार्गाधिकार यदि संबंधित रेजिडेन्ट वेलफेयर एसोशिएसन का विशेष अनुरोध है।

ंग और घं कालोनियों में:

रेजिडेन्ट वेलफेयर एसोशिएसन के परामर्श से नियमित रिहायशी भूखण्ड विकास में 18 मीटर मार्गाधिकार, पुनर्वास कालोनियों में 13.5 मीटर मार्गाधिकार तथ नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, पुरानी दिल्ली, विशेष क्षेत्र तथा शहरी गाँवों में 9 मीटर मार्गाधिकार।

ंड , च और छ कालोनियों में:

नियमित भूखण्ड विकास में 13.5 मीटर मार्गाधिकार, पुनर्वास कालोनियों में 9 मीटर मार्गाधिकार तथा पुरानी दिल्ली, नियमित-अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, विशेष क्षेत्रों और शहरी गाँवों में 6 मीटर मार्गाधिकार।

ii) निग्रमित-अनिधकृत कालोनियों, पुनर्खापन कालोनियों, शहरी गाँवों, विशेष क्षेत्र तथा पुरानी दिल्ली में 9 मीटर (अथवा ड. व और छ श्रेणी की कालोनियों में 6 मीटर) से कम के मार्गों को यदि मिश्रित उपयोग के लिए अधिसूचित किया जाता है, तो पैदल शॉपिंग मार्ग (पी एस एस) के रूप में घोषित किया जायेगा तथा मोटरयुक्त वाहनों को उस पर चलने नहीं दिया जायेगा।

#### टिप्पणी:

- (क) कालोनियों से सटी मास्टर प्लान सड़कों को मिश्रित उपयोग सड़के अधिसूचित करने कें. लिए संबंधित आरडब्लयूए का अनुरोध अथवा संबंधित आरडब्ल्यूए के साथ परामर्श आवश्यक नहीं है क्योंकि ये सड़कें कालोनियों की आंतरिक सड़कें नहीं हैं।
- (ख) संबंधित आरडब्ल्यूए का विशेष अनुरोध अथवा परामर्श पैरा 10.10 द्वारा शासित होगा ।
- (iii) मिश्रित उपयोग सड़कों को अधिसूचित करने के लिए स्थानीय निकाय अधिसूचना जारी होने के समुचित समय के अंदर शीघ्र ही उपर्युक्त चौड़ाई वाली सभी सड़कों का सर्वेक्षण कराएंगें यदि यह पहले न किया गया हो, तािक मिश्रित उपयोग सड़कों के रूप में इस प्रकार की सड़कों की पहचान हो सके।
- (iv) फील्ड सर्वेक्षण से सड़क पर मौजूदा गैर रिहायशी उपयोग के विस्तार, सड़क के जिस भाग को अधिसूचित किया जाना है , नागरिक सुविधाओं की अतिरिक्त आवश्यकता और यातायात व पार्किंग के लिए प्रावधान का मूल्यांकन किया जाएगा ।
- (v) फील्ड सर्वेक्षण पूरा होने के तत्काल बाद संबंद्ध अधिनियम के तहत सक्षम प्राधिकारी के अनुमोदन से स्थानीय निकाय/ प्राधिकारी द्वारा अधिसूचना जारी की जाएगी।

## 10.3.4 भविष्य में शहरीकरण योग्य क्षेत्रों में मिश्रित उपयोग सड़कों की अधिसूचना :

नए शहरीकरण योग्य क्षेत्रों में, निम्नलिखित क्षेत्रों में मिश्रित उपयोग की अनुमति होगी :-

- (i) नए विकसित आवासीय क्षेत्रों में उपर्युक्त निर्दिष्ट मिश्रित उपयोग केवल 18 मी. मार्गाधिकारों वाले मार्गों पर स्थित आवासीय प्लाटों पर ही अनुमेय होगा।
- (ii) ऐसे गांवों में जो शहरी घोषित किए जाते हैं और विकास प्रक्रिया में शामिल किए गए हैं जनमें इस प्रकार के समाकलन हेतु तैयार की गई स्थानीय क्षेत्रीय योजना/लेआउट प्लान में निर्दिष्ट क्षेत्रों/सीमाओं में मिश्रित उपयोग अनुमेय होगा।
- (iii) ऐसे नए क्षेत्रों में ले-आउट प्लान में ऐसे विस्तार क्षेत्रों / प्लाटों को निर्दिष्ट किया जाएगा और निजी विकास के मामले में ले-आउट प्लान के लिए अनुमित प्रदान करने के समय उन्हें मिश्रित उपयोग नीति के अंतर्गत दिल्ली विकास प्राधिकरण द्वारा विकसित क्षेत्रों के मामले में आवंटन अथवा नीलामी द्वारा निपटान के समय अधिसूचित किया जाएगा।

## मिश्रित उपयोग को गियंत्रित करने वाले सामान्य निबंधन एवं शर्ते :

उपर्युक्त पैरा 10.3.2 में उल्लिखित विभिन्न श्रेणियों की कालोनियों के लिए निर्धारित 10.4 शर्तों के संदर्भ में और वशर्तें कि प्लाट अधिसूचित मिश्रित उपयोग सड़क ( फुटकर दुकानों के मामले में) अथवा न्यूनतम मार्गाधिकार (अन्य मिश्रित उपयोग कार्यकलापों के मामले में ) वाली सड़क से सटा हो , तो निम्नलिखित शर्तों व निबंधनों के अध्यधीन मिश्रित उपयोग अनुमेय होगा: -

## आवासीय भूखण्ड विकास में:

- यदि किसी आवासीय प्लाट में केवल एक रिहायशी इकाई है तो इस इकाई में केवल एक ही प्रकार के मिश्रित उपयोग (अर्थात पैरा 10.6 के अनुसार फुटकर दुकान अथवा व्यावसायिक कार्यकलाप अथवा पैरा 10.7 में सूचीबद्ध अन्य कार्यकलापों में से कोई एक ) **(i)** की अनुमति दी जाएगी।
- यदि किसी आवासीय प्लाट में एक से अधिक रिहायशी इकाइया हैं तो प्रत्येक रिहायशी इकाई में केवल एक ही प्रकार के मिश्रित उपयोग ( पैरा 10.6 के अनुसार फुटकर दुकान अथवा व्यावसायिक कार्यकलाप अथवा पैरा 10.7 में सूचीबद्ध अन्य कार्यकलापों में से कोई (ii) एक ) की अनुमति होगी ।

## ग्रुप हाऊसिंग में :

ग्रुप हाउन्सिंग में, केवल व्यावसायिक कार्यकलाप अनुमेय है । ग्रुप हाउन्सिंग के ले-आउट नक्शे में फुटकर दुकान का प्रावधान यदि विशेषरूप से किया जाता है तो उनकी अनुमति दी जाएगी ।

## अन्य शर्ते एवं निबंधन :

- मार्गौ या सार्वजनिक भूमि पर अतिक्रमण की अनुमति नहीं होगी ।
- प्लाट/आवासीय इकाई को मिश्रित उपयोग में रखने के बाद भी विशेष आवासीय उपयोग (iv) के लिए यथा लागू विकास नियंत्रण मानदण्ड लागू रहेंगें । (v)
- यदि अधिसूचित मार्ग, मुख्य योजना सड़क है, और यदि सेवा सड़क उपलब्ध है अथवा स्थानीय निकाय द्वारा उपलब्ध कराई जाएगी तो उस मामले में मिश्रित उपयोग परिसर तक ऐसी सेवा सड़क से पहुंचा जा सके और मुख्य कैरिजवे से सीघे नहीं। (vi)
- (vii) भूखंडीय विंकास में, आगे के सैटबैक पर चारदीवारी नहीं होगी, ताकि उसका अतिरिक्त पार्किंग के लिए उपयोग किया जा सके।

- (viii) परिसरों के अंदर 2.0 ई.सी.एस. प्रति 100 वर्ग मीटर की दर से उपलब्ध कराई जाएगी। जहां तक उपलब्ध नहीं है, पार्किंग के विकास की लागत प्लाट के आबंदिती/ खागी द्वारा देय होगी। यह शर्त उन मामलों में भी लागू होगी जहां आवासीय परिसरों का उपयोग केवल व्यावसायिक कार्यों के लिए हो रहा है।
- (ix) मिश्रित उपयोग नीति के अंतर्गत मार्ग की अधिसूचना के परिणाम स्वरूप यातायात और पार्किंग पर अतिरिक्त भार को ध्यान में रखते हुए अधिसूचित मिश्रित उपयोग के चिन्हित मार्गों पर सामूहिक पार्किंग क्षेत्र निर्धारित किए जाएंगें । यदि कोई पार्किंग स्थल उपलब्ध नहीं है तो उक्त मार्ग पर भूमि/ प्लाट ट्रेडर्स एसोसिएशन द्वारा उपलब्ध कराया जाएगा या तो पार्किंग सुविधाओं के निर्माण के लिए वरीयतः बहुतलीय पार्किंग के लिए अधिग्रहीत किया जाएगा । इस प्रकार की पार्किंग सुविधाओं का विकास या तो ट्रेडर्स एसोसिएशन्स द्वारा अथवा स्थानीय निकायों द्वारा किया जाएगा और कार्यान्वयन के लिए एक मॉडल के रूप में सार्वजनिक निजी साझेदारी को भी शामिल किया जा सकता है।

#### 10.5 अनुमेय और गैर अनुमेय उपयोग

किसी भी व्यापार अथवा कार्यकलाप जिसमें किसी प्रकार का हानिकर , जोखिम भरा, ज्वलशील, असंगत और प्रदूषणकारी पदार्थ या प्रणाली हो, को अनुमित नहीं दी जाएगी ।

#### 10.6 फुटकर दुकानें

- (i) मिश्रित उपयोग के लिए अधिसूचित प्लाटों और मार्गों पर फुटकर दुकानें केवल भूतल पर अधिकतम अनुमेय भूतल कवरेज तक अनुमत होगी।
- (ii) निम्नलिखित कार्यकलापों को मिश्रित उपयोग के अंतर्गत अनुमित नहीं दी जाएगी :
- क. भवन निर्माण सामग्री (लकड़ी, लकड़ी के उत्पाद (फर्नीचर को छोड़कर) मार्बल, लौह एवं इस्पात, (बजरी सीमेंट व रेत) जलाने वाली लकड़ी (फायरवुड़), कोयला और अग्नि के जोखिम वाले और अन्य भारी सामग्री वाली फुटकर दुकानें।
- ख. ऑटोमोबाइल की मरम्मत की दुकानें और वर्कशॉप, टायर रिसोलिंग और रीट्रीडिंग, बैटरी चार्जिंग वाली दुकानें ।
- ग. भण्डारण, गोदाम और भाण्डागार ।
- घ. कबाड़ी की दुकान
- ड. शराब की दुकान

278262/06-24

- घ. मुद्रण, रंगाई एवं वार्निशिंग
- छ. कोई अन्य कार्यकलाप जो सरकार द्वारा रागय रागय पर अधिसूचित किया जाए ।

#### नोटः

- पूर्णतः तैयार मार्बल उत्पाद के व्यवसायी जो किटंग और पॉलिशिंग का कार्यकलाप नहीं करती हों, शामिल नहीं है ।
- 2. ड., च तथा छ श्रेणी कालोनियों में अधिसूचित मिश्रित उपयोग सड़कों में कम से कम 50 वर्ग मीटर के आवासीय प्लाटों में बजरी , रेत और सीमेंट की फुटकर दुकानों की अनुमित होगी बशर्त कि सामग्री पूरी तरह प्लाट परिसर में ही रखी जाए ।
- 3. ऑटोमोबाइल के मामले में मरम्मत की दुकाने और वर्कशॉप ऐसे प्लाटों पर अनुमेय होगी जो 30 मीटर या अधिक मार्गाधिकार वाले मिश्रित उपयोग मार्गों से लगे हुए हैं।

#### 10.7 अन्य कार्यकलाप

10.7.1 पैरा 10.4 में उल्लिखित सामान्य शर्तों तथा पैरा 10.7.3 में उल्लिखित अतिरिक्त शर्तों के अध्यधीन, 10.7.2 में यथा-निर्धारित न्यूनतम मार्गाधिकार वाली सङ्कों के साथ लगे रिहायशी भूखंडों में, चाहे वह सङ्क मिश्रित उपयोग मार्ग के रूप में अधिसूचित है या नहीं , निम्नलिखित सार्वजनिक और अर्ध-सार्वजनिक क्रियाकलापों की भी अनुमित दी जाएगी:-

- (क) प्री-प्राइमरी स्कूल (नर्सरी/मांटेसरी स्कूल, क्रेच सहित )
- (ख) नरिंग होम (क्लिनिक, डिस्पेंसरी, पैथोलोजी लैब तथा डायग्नोस्टिक सेंटर सहित)
- (ग) गेस्ट हाउस (लॉर्जिंग हाउस सहित), चाहे कमरों की संख्या कितनी भी हो
- (घ) बैंक
- (ड.) फिटनेस सेंटर (जिमनेजियम, योग्।/मेडिटेशन सेंटर सहित)

10.7.2 किसी मार्ग का न्यूनतम मार्गाधिकार अथवा सड़क का हिस्सा, जिस पर उपर्युक्त अन्य क्रियाकलाप अनुमत्य हैं, इस प्रकार हैं :-

ंक और खं कालोनियों में : नियमित भूखंडीय विकास में 18 मी0 मार्गाधिकार

#### टिप्पणी

\* तथापि, इस अधिसूचना के जारी होने की तारीख से पहले से चल रहे बैंक और फिटनेस सेंटरों के अलावा अन्य बैंक और फिटनेस सेंटरों की अनुमित नहीं होगी।

ंग और घ कालोनियों में : नियमित रिहायशी भूखंडीय विकास में 18 मी0 मार्गाधिकार, पुनर्वास कालोनियों में 13.5 मी0 मार्गाधिकार, नियमित - अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों, वाल्ड सिटी, विशेष क्षेत्रों तथा शहरी गांवों, और पैदल शॉपिंग मार्गों में 9 मी0 मार्गाधिकार

ड. , च और छ कालोनियों में : नियमित भूखंडीय विकास में 13.5 मी० मार्गाधिकार,
पुनर्वास कालोनियों में 9 मी० मार्गाधिकार तथा वाल्ड
सिटी, नियमित -अनिधकृत कालोनियों, पुनर्स्थापन कालोनियों,
विशेष क्षेत्रों तथा शहरी गांवों और पैदल शॉपिंग मार्गों में 6 मी०
मार्गाधिकार

10.7.3 उपर्युक्त सार्वजनिक और अर्ध-सार्वजनिक कार्यकलाए पूर्ववर्ती पैराग्राफों में निर्धारित सामान्य शर्तों के अलावा निम्नलिखित अतिरिक्त शर्तों के अधीन होंगे:-

(i) परवर्ती पैराग्राफों में उल्लिखित विशेष शतों के अध्यधीन निर्धारित न्यूनतम मार्गाधिकार सिंही मार्गों पर जिन भूखंडों पर ये कार्यकलाप अनुमेय होंगे, उनका न्यूनतम आकार' से कार्यकलाप अनुमत्य होगे, नियमित भूलकीय विकास में 200 वर्ग मी० तथा पुनर्यास कालोनियों, नियमित-अनिवृद्ध कालोनियों, पुनरर्थापन कालोनियों (रिहेबिलीटेशन कालोनी), याल्ड सिटी, विशेष क्षेत्रों व शहरी गावो में 75 वर्ग मी० होगा । तथापि, इन कालोनियों के साथ साथ उ. च और छ श्रेणी की कालोनियों में चल रहे क्लिनिक, डिस्पेंसरियो तथा पैथोलोजी लैब के लिए भूलक का न्यूनतम आकार 50 वर्ग मी० होगा ।

- (ii) बैंक एफएआर के 2/3 भाग पर 600 वर्ग मीठ की शर्त पर अनुमेय होंगे, जबकि गेस्ट हाउस और नर्सिंग होग तल क्षेत्र के 3/4 भाग तक अनुमेय होंगे !
- (iii) तथापि, मास्टर प्लान सड़कों और जोनल प्लान सड़कों के साथ लगते भूखंडों में चल रहे नर्सिंग होम निर्मित क्षेत्र के 100% तक अनुमेय होंगे और भूखंड के आकार की सीमा उन पर लागू नहीं होगी।
- (iv) विशेष क्षेत्र में निर्धारित न्यूनतम मार्गाधिकार की सड़कों के साथ लगते भूखंडों तथा मास्टर प्लान सड़कों व जोनल प्लान सड़कों के साथ लगते भूखंडों पर, जो मिश्रित उपयोग के लिए अधिसूचित हैं, निर्मित क्षेत्र के 100% तक अनुमेय होंगे और भूखंड के आकार की सीमा उन पर लागू नहीं होगी ।
- (v) प्री-प्राइमरी स्कूल तथा फिटनेस सेंटर(वाणिज्यिक मार्गों के साथ लगते भूखडों को छोड़कर) केवल भूतल पर अनुमत्य तल कवरेज तक सीमित होंगे।
- (vi) उपर्युक्त कार्यकलाप किन्हीं अन्य निवंधनों व शर्तों के अध्यधीन होंगे, जो उन पर लागू संबंधित विधानों/अधिनियमों में यथा निर्धारित हो ।
- (vii) भूखंडों के आबंटी/स्वामी की यह जिम्मेदारी होगी कि वे पार्किंग की व्यवस्था करें ताकि पार्किंग से सार्वजनिक भूमि पर कोई अतिक्रमण/फैलाव न हो ।

नोटः " भूखंड के आकार में ± 5% का अन्तर हो सकता है ।

10.7.4 बैंकट हॉल की अनुमित केवल औद्योगिक और वाणिज्यिक क्षेत्रों में होगी न कि रिहायशी उपयोग जोन में । तल कवरेज, तल क्षेत्र अनुपात (एफएआर), ऊंचाई और वेसमेंट के संबंध में विकास नियंत्रण मानक उस परिसर के लिए विशिष्ट उपयोग हेतु मास्टर प्लान मानकों के अनुसार लागू होंगे ।

#### 10.8 व्यावसायिक कार्यकलाप

पैरा 10.4 में विनिर्दिष्ट सामान्य निबंधनों व शर्तों के अध्यधीन भूखंडीय विकास और ग्रुप हाउसिंग में व्यावसायिक कार्यकलापों की अनुमति निम्नलिखित विशिष्ट शर्तों के अंतर्गत होंगी:-

- व्यावसायिक कार्यकलाप की अनुमति होगी, यदि निवासी ये कार्यकलाप स्वयं करे ।
- ii. व्यावसायिक कार्यकलापों का तात्पर्य उन कार्यकलापों से हैं, जिनमें डोंक्टर, वकील, वास्तुकार और वार्टर्ड अकाउंटेंट जैसे व्यावसायिक कौशल पर आधारित सेवाएं शामिल हैं।
- iii. ग्रुप हाउसिंग, तथा बहु आवासीय यूनिटों वाले भूखंडीय विकास में किसी भी तल पर व्यावसायिक कार्यकलाप की अनुमित होगी, वशर्ते कि यह कार्यकलाप प्रत्येक आवासीय यूनिट के अनुमत्य अथवा स्वीकृत तल क्षेत्र अनुपात, जो भी कम हो, का अधिक से अधिक 50% हो।
- iV. एकल रिहायशी यूनिट ताले भूखंडीय विकास के मामले में व्यावसायिक कार्यकलाप की अनुमति केवल एक ही तल पर होगी, लेकिन उस भूखंड पर अनुमत्य अथवा स्वीकृत तल क्षेत्र अनुपात, जो भी कम हो, के 50% से कम पर अनुमति होगी।

## 10.9 मिश्रित उपयोगं परिसरों का पंजीकरण तथा प्रभारों का भुगतान

- मिश्रित उपयोग के अन्तर्गत पहले से आने वाले अथवा मिश्रित उपयोग के अन्तर्गत लाए जाने वाले रिहायशी परिसरों के मागले में यदि भूखंडीय विकास है तो भूखंड/रिहायशी यूनिट के स्वामी/आवंटो/निवासी तथा यदि ग्रुप हासिंग है तो रिहायशी यूनिट को इस संबंध में एक फार्म भरकर ऐसे मिश्रित उपयोग की घोषणा करनी होगी और उस फार्म को संबंधित स्थानीय निकाय के पास जमा कराना होगा तथा केन्द्र सरकार के अनुमोदन से अधिसूचित दरों पर एकमुश्त पंजीकरण प्रभार जमा कराना होगा।
- ii. मिश्रित उपयोग वाले परिसरों को संबंधित स्थानीय निकाय को, केनीय सरकार के अनुमोदन से अधिसूचित दरों पर, जिस अविध के लिए सम्पत्ति को मिश्रित उपयोग में लाया गया है, उसके लिए हर साल मिश्रित-उपयोग प्रभारों का भुगतान भी करना होगा। पूर्व मूल्यांकन वर्ष (अप्रैल-मार्च) के संबंध में यह भुगतान सम्पत्ति के स्वामी/आवंटी द्वारा हर साल 30 जून से पूर्व स्वैच्छिक रूप से किया जाएगा।
- iii. मिश्रित उपयोग नीति के अन्तर्गत गैर-रिहायशी कार्यकलापों के लिए रिहायशी परिसर का उपयोग करने के लिए भवन में कोई परिवर्तन करने की अनुमितं तब तक नहीं होगी, जब तक कि आवंटी/स्वामी ने संशोधित भवन योजना की स्वीकृति न ले ली हो और आवश्यक शुक्क अथवा प्रभार का भुगतान न कर दिया हो।
- iv. संबंधित स्थानीय निकाय मिश्रित उपयोग वाली परिसम्पत्तियों, चाहे उसके पास पंजीकृत हो या न हो, की परीक्षण जांच करने के लिए उत्तरदायी होगा ।
- V. संगत अधिनिमय के अन्तर्गत उपलब्ध अन्य दण्डात्मक कार्रवाई के अलावा, पंजीकरण न की गई अथवा इस अधिसूचना के निबंधनों का उल्लंघन करने वाली सम्पत्तियों को मिश्रित उपयोग के लिए वार्षिक परिवर्तन प्रभार का 10 गुना जुर्माना स्थानीय निकाय को अदा करना होगा।

## 10.10 रेजीडेंट वेलफेयर एसोसिएशनों के साथ परामर्शः

- (i) रेजीडेंट वेलफेयर एसोसिएशन (आरडब्ल्यूए) किसी कानून यथा सोसायटी पंजीकरण अधिनियम के तहत दिनांक 21.7.2008 के पहले पंजीकृत निकाय होगा । .
- (ii) मिश्रित उपयोग वाले मार्गों को घोषित करने के उद्देश्यों के लिए संबंधित रेजिडेंट वेलफेयर एसोसिएशनों के साथ संबंधित स्थानीय निकायों द्वारा परामर्श किया जायेगा ।
- (iii) रेजीडेंट वेलफेयर एसोसिएशनों के साथ अर्थपूर्ण परामर्श के लिए स्थानीय निकायों द्वारा वास्तविक प्रयास किये जायेंगें । इस तरह के प्रयासों में शामिल हो सकते हैं : प्रस्तावित परामर्शों का व्यापक प्रचार, परामर्श के रिकार्ड का रखरखाव और रेजीडेंट वेलफेयर एसोसिएशनों और जनता तक उन रिकार्डों की पहुंच उपलब्ध कराना.।
- (iv) संबंधित रेजीडेंट वेलफेयर एसोसिएशन के साथ परामर्श व्यापक हो सकता है परन्तु यह मिश्रित उपयोग मार्गों की पहचान तक सीमित होगा और व्यक्तिगत मामलों में अनुमित प्रदान करने के लिए नहीं । तथापि, राबंधित रेजीडेंट वेलफेयर एसोसिएशनों को सार्वजनिक परेशानियों और गैर अनुभेयर उपयोगों की शिकायतों के मामलों में अपनी सुनवाई कराने का अधिकार होगा ।
- 10.11 किन मामलों में भिश्रित उपयोग मना किया जा सकता है/ वापस लिया जा सकता है/ प्रतिबंधित किया जा सकता है ।

10.11.1 किसी भी ऐसी शर्त , जिसके अंतर्गत ऐसा मिश्रित उपयोग अनुमेय/अनुमत है, के उल्लंघन के मामले में संबंधित स्थानीय निकाय मिश्रित उपयोग की अनुमति अथवा पंजीकरण को रह अथवा निलंबित कर सकती है ।

10.11.2 निम्नलिखित गेर-रिहायशी कार्यकलाप, जिन्हें मिश्रित उपयोग नीति के अंतर्गत शामिल नहीं किया गया है, निम्निलिखित शर्तों के अधीन रिहायशी क्षेत्रों में अनुमेय होंगें :-

- (i) रिहायशी उपयोग जोनों में रिहायशी परिसरों में चल रहे विद्यालय दिनांक 18 मई, 2007 तक चलते रहेंगें । संबंधित स्थानीय निकाय तत्पश्चात विद्यालयों को चलते रहने की अनुमति दे सकता है बशर्तें दिल्ली मास्टर प्लान 2001 के उप खण्ड 8(2) क (दिनांक 1.8.1990 को भारत के असाधारण राजपत्र में अधिसूचित सां.आ. 606 (अ) के तहत पृष्ठ 152-153) के संबंध में स्थानीय निकाय द्वारा अपनी क्षमता के भीतर उपयोग परिसरों/ भू-विन्यास योजना में आवश्यक परिवर्तन किए जायें तथा इस उद्देश्य के लिए विद्यालयों द्वारा संबंधित स्थानीय निकाय के पास आवेदन करना अपेक्षित होगा ।
- (ii) इसके अलावा रिहायशी परिसरों में चल रहे कोचिंग सेंटर तथा ऐसे ही शिक्षण संस्थान वर्तमान शैक्षणिक वर्ष के अंत तक या 18 मई, 2007 तक, इनमें से जो भी पहले हो, चलते रहेंगें।

#### 10.12 व्यावसायिक सबकें एवं क्षेत्र :-

10.12.1 निम्नलिखित अधिसूचित मिश्रित उपयोग वाले मार्गी/ मिश्रित उपयोग वाले मार्गी के विस्तार को स्थानीय प्राधिकरण द्वारा व्यावसायिक मार्गी था व्यावसायिक क्षेत्रों के रूप में अधिसूचित किया जा सकता है :-

- (क) जहां नियमित भूखण्ड विकास वाले क्षेत्र में 24 मीटर से अधिक मार्गाधिकार वाली सड़कों पर कम से कम 300 मीटर लंबी सड़क से लगे प्लाटों में से 70% से अधिक प्लाटों का व्यावसायिक उपयोग हो रहा हो (बशर्तें क और ख श्रेणी की कॉलोनियों में किसी मार्ग को व्यावसायिक मार्ग के रूप में अधिसूचित नहीं किया जायेगा),
- (ख) जहां पैरा 10.3.1 के अनुसार दिल्ली मास्टर प्लान 1962 के तहत घोषित पुनर्वास कालोनियों, अनिधकृत -नियमित कालोनियों, पुनर्वास कालोनियों (रीसेटलमेंट कालोनी), प्राचीरबद्ध शहर, विशेष क्षेत्र एवं ग्राम तथा स्थानीय व्यावसायिक मार्गों में 24 मीटर मार्गाधिकार से कम चौड़ी सड़कों पर कम से कम 100 मीटर लम्बी सड़क से लगी हुई संपत्तियों में से 70 % से अधिक संपत्तियों का व्यावसायिक उपयोग हो रहा हो, तथा
- (ग) (ड.), (च) तथा (छ) श्रेणी की कालोनियों में जहां एक हेक्टेयर के संसक्त क्षेत्र के भीतर 80% रिहायशी प्लॉटों का मिश्रित उपयोग हो रहा हो या 300 दुकानें हो ।
- 10.12.2 ऐसे मार्गी/ विस्तारों ( स्ट्रेचेज) की पहचान इस अधिसूचना के लागू होने की तिथि के बाद यथोचित समयाविध के भीतर तथा यथोचित शीघ्रता से स्थानीय निकाय द्वारा कराए गए फील्ड सर्वेक्षण के आधार पर की जायेगी।
- 10.12.3 पहचान किये जाने के बाद सक्षम प्राधिकारी के अनुमोदन से स्थानीय निकाय/ प्राधिकरण द्वारा व्यावसायिक क्षेत्रों/ मार्गों की अधिसूचना द्वारा निम्लिखित निबंधनों एवं शर्तों का अनुपालन अनिवार्य होगा :-
- (i) ऐसे क्षेत्रों/ मार्गों के लिए स्थानीय निकाय/ प्राधिकरण के अनुमोदन से संशोधित ले-आउट प्लान तैयार करना ।
- (ii) ऐसे क्षेत्रों/ मार्गों के ले-आउट प्लान में परिचालन, पार्किंग, खुले स्थानों की पर्याप्त व्यवस्था का प्रावधान और अन्य योजना मानदण्डों का उल्लेख किया जाना चाहिए ।
- (iii) किसी मार्ग को व्यावसायिक क्षेत्र/ मार्ग के रूप में अधिसूचित किए जाने के परिणामस्वरूप यातायात और पार्किंग पर पड़ने वाले अतिरिक्त भार को घ्यान में रखते हुए सामान्य पार्किंग क्षेत्र निर्धारित किए जायेंगें । यदि पार्किंग के लिए कोई स्थान उपलब्ध नहीं है तो जहां संभव हो उपर्युक्त मार्ग/क्षेत्र में भूमि/प्लाट ट्रेडर्स एसोसिएशन द्वारा उपलब्ध कराया जाये या पार्किंग सुविधाओं, अधिमानतः बहुस्तरीय पार्किंग के निर्माण के लिए भूमि/प्लॉट

का अधिग्रहण किया जाये । ऐसे पार्किंग सुविधाओं का विकास या तो ट्रेडर्स एसोसिएशन या स्थानीय निकायों द्वारा किया जायेगा तथा कार्यान्वयन के भॉडल के तौर पर इसमें सरकारी- निजी साझेदारी भी हो सकती है ।

- (iv) इस खण्ड के तहत किसी व्यावसासिक मार्ग/ क्षेत्र को अधिसूचित किए जाने के बाद व्यावसायिक मार्गों पर स्थित प्लाटों के मालिकों/ आवंटियों को व्यावसायिक उपयोग के लिए लागू विकास नियंत्रण मानकों के तहत अनुमेय क्षेत्र से अधिक कवरेज के लिए सरकार द्वारा अनुमोदित दरों पर अतिरिक्त परिवर्तन प्रभार का भुगतान करना अपेक्षित होगा । ऐसे व्यावसायिक क्षेत्रों/ मार्गों में प्लॉटों के आवंटियों/ मालिकों के लिए यह केवल एक बार की सुविधा है तथा इसे भविष्य में व्यावसायिक मार्गों/ क्षेत्रों में विकास नियंत्रण मानकों में छूट के रूप में नहीं समझा जाये ।
- (v) अन्य कोई शर्त जो समय-समय पर सरकार द्वारा निर्धारित की जाये ।

् [सं. के-13011/2/2006-डीडीआईबी] एस. मुखर्जी, अवर सचिव

..... I

अनुलग्नक-।

## दिल्ली के विभिन्न क्षेत्रों में गलियों का मिला जुला उपयोग

## . क्षेत्र "क " भाग "ग" (चार दीवारी शहर)

ह.सं.  1. चाँदनी चौंक रोड (100 फुट मार्गाधिकार) 2. नेताजी सुभाष मार्ग (80 फुट मार्गाधिकार) 3. अन्सारी रोड (60 फुट मार्गाधिकार) 4. खारी बावली (80 फुट मार्गाधिकार) 5. नया बाजार रोड (30 फुट मार्गाधिकार) 6. अद्धानन्द मार्ग (80 फुट मार्गाधिकार) 7. अजमेरी गेट बाजार (80 फुट मार्गाधिकार) 8. चर्च मिशन रोड (80 फुट मार्गाधिकार) 9. एस.भी.एम: मार्ग (120 फुट मार्गाधिकार) 10. एच.सी.सेन. रोड (100 फुट मार्गाधिकार) 11. अजमेरी.गेट रोड, बाजार सीताराम, गली कृचा पाती राम, गली आर्य समाज, गली काली मिरुजद, गली कटरा अनिखान 12. बाजार दिल्ली दरवाजा 13. नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कृचा चालान, गली पटौदी हाउस, गली कला महल 14. गली चूडीवालान चावड़ी बाजार, बाजार मंटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण 15. अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कृचा चंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार 16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दरिया रोड, गली बताशावाली, गली कूचा नवाब 17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड 18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, महं सड़क, चाँदनी चौंक। 19. नई सड़क, चाँदनी चौंक, एसप्लेनेड रोड, दरिबा कला बाजार गुलियान, चावरी बाजार, मालीवाड़ा रोड।	1. 8	त्र के भाग ग (वार वावाय राष्ट्र प
<ol> <li>चाँदनी चौंक रोड (100 फुट मार्गाधिकार)</li> <li>नेताजी सुभाष मार्ग (80 फुट मार्गाधिकार)</li> <li>खारी बावली (80 फुट मार्गाधिकार)</li> <li>खारी बावली (80 फुट मार्गाधिकार)</li> <li>मया बाजार रोड (30 फुट मार्गाधिकार)</li> <li>अद्धानन्द मार्ग (80 फुट मार्गाधिकार)</li> <li>अजमेरी गेट बाजार (80 फुट मार्गाधिकार)</li> <li>चर्च मिशन रोड (80 फुट मार्गाधिकार)</li> <li>एस.सी.एम: मार्ग (120 फुट मार्गाधिकार)</li> <li>एस.सी.एम: मार्ग (120 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>अजमेरी.गेट रोड, बाजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिस्जद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूडीवालान चावड़ी बाजार, बाजार मीटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौंक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चावरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ol>	क सं	
<ol> <li>नेताजी सुभाष मार्ग (80 फुट मार्गाधिकार)</li> <li>अन्सारी रोड (60 फुट मार्गाधिकार)</li> <li>खारी बावली (80 फुट मार्गाधिकार)</li> <li>नया बाजार रोड (30 फुट मार्गाधिकार)</li> <li>अद्धानन्द मार्ग (80 फुट मार्गाधिकार)</li> <li>अजमेरी गेट बाजार (60 फुट मार्गाधिकार)</li> <li>एस.प्री.एम: मार्ग (120 फुट मार्गाधिकार)</li> <li>अजमेरी गेट रोड, ब्राजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिस्जद, गली कटरा अनिखान</li> <li>अजमेरी गेट रोड, ब्राजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली कला महल</li> <li>वाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूड़ीवालान चावड़ी बाजार, बाजार मटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गांली कासिम जान, चावरी बाजार, महं सइक, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बांजार गुलियान, चावरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ol>		चाँदनी चौक रोड (100 फुट मार्गाधिकार)
<ol> <li>अन्सारी रोड (६० फुट मार्गाधिकार)</li> <li>खारी बावली (८० फुट मार्गाधिकार)</li> <li>नया बाज़ार रोड (३० फुट मार्गाधिकार)</li> <li>अद्धानन्द मार्ग (८० फुट मार्गाधिकार)</li> <li>अजमेरी गेट बाजार (६० फुट मार्गाधिकार)</li> <li>चर्च मिशन रोड (६० फुट मार्गाधिकार)</li> <li>एस.प्री.एम: मार्ग (१२० फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (१०० फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (१०० फुट मार्गाधिकार)</li> <li>अजमेरी गेट रोड, बाजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिराजद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूडोवालान चावड़ी बाजार, बाजार मिटया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिखा रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्राली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिबा कलां बाजार गुलियान, चावरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ol>	2	नेताजी सभाष मार्ग (80 फुट मार्गीधिकार)
<ol> <li>खारी बावली (80 फुट मार्गाधिकार)</li> <li>नया बाज़ार रोड (30 फुट मार्गाधिकार)</li> <li>श्रद्धानन्द मार्ग (80 फुट मार्गाधिकार)</li> <li>अजमेरी गेट बाजार (80 फुट मार्गाधिकार)</li> <li>एस.प्री.एम. मार्ग (120 फुट मार्गाधिकार)</li> <li>एस.प्री.एम. मार्ग (120 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>अजमेरी गेट रोड, ब्राजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिरिजद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूडीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्राली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिबा कलां बाजार गुलियान, चाबरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ol>		अन्सारी रोड (६० फूट मार्गाधिकार)
<ul> <li>नया बाजार रोड (30 फुट मार्गीधिकार)</li> <li>श्रद्धानन्द मार्ग (80 फुट मार्गिधिकार)</li> <li>अजमेरी गेट बाजार (60 फुट मार्गिधिकार)</li> <li>एस.प्री.एम. मार्ग (120 फुट मार्गिधिकार)</li> <li>एस.प्री.एम. मार्ग (120 फुट मार्गिधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गिधिकार)</li> <li>अजमेरी गेट रोड, बाजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिस्जद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूड़ीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिखा रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बलीमारान, गाली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>		ज्वारी बावली (80 फूट मागोधिकार)
<ul> <li>श्रद्धानन्द मार्ग (८० फुट मार्गाधिकार)</li> <li>श्रद्धाने रोट बाजार (६० फुट मार्गाधिकार)</li> <li>एस.प्री.एम. मार्ग (१२० फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (१०० फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (१०० फुट मार्गाधिकार)</li> <li>श्रद्धाने रोट रोड, ब्राजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिरिजद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चांलान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूड़ीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दरिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गाली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिबा कला बाजार गुलियान, चावरी बाजार, मालीवाइ। शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाइ।</li> </ul>		नया बाजार रोड (३० फूट मागीधकार)
<ul> <li>त. अजमेरी गेट बाजार (60 फुट मागाधिकार)</li> <li>श. वर्च मिशन रोड (60 फुट मागाधिकार)</li> <li>श. एस.प्री.एम. मार्ग (120 फुट मार्गाधिकार)</li> <li>10. एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>11. अजमेरी.गेट रोड, बाजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिस्जिद, गली कटरा अनिखान</li> <li>12. बाजार दिल्ली दरवाजा</li> <li>13. नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>14. गली चूड़ीवालान चावड़ी बाजार, बाजार मिटया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>15. अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दरिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिबा कलां बाजार गुलियान, चावरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>		श्रदानन्द्र मार्ग (८० फट मार्गाधिकार)
<ul> <li>एस.प्री.एम: मार्ग (120 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>एच.सी.सेन. रोड (100 फुट मार्गाधिकार)</li> <li>अजमेरी गेट रोड, बाजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिरिजद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटीदी हाउस, गली कला महल</li> <li>गली चूडीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्राली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>		अजमेरी गेट बाजार (60 फुट मागाधकार)
<ul> <li>एच.सी.सेन. रोड (100 फुट मागाधकार)</li> <li>अजमेरी.गेट रोड, ब्राजार सीताराम, गली कूचा पाती राम, गली आर्य समाज, गली काली मिस्जद, गली कटरा अनिखान</li> <li>बाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटीदी हाउस, गली कला महल</li> <li>गली चूडीवालान चावड़ी बाजार, बाजार मिट्या महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिखा रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिवा कला बाजार गुलियान, चावरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>	8.	चर्च मिशन रोड (60 फुट मागाधिकार)
<ul> <li>11. अजमेरी गेट रोड, बाजार सीताराम, गला कूचा पाता राम, गला जाम संस्ता, मिस्जद, गली कटरा अनिखान</li> <li>12. बाजार दिल्ली दरवाजा</li> <li>13. नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>14. गली चूड़ीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>15. अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिखा रोड, गली बताशावाली, गली कूचा नवाब</li> <li>17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>	9.	एस:प्री.एम: मार्ग (120 फुट मागाधिकार)
<ul> <li>मिस्जिद, गली कटरा आनखान</li> <li>वाजार दिल्ली दरवाजा</li> <li>नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>गली चूड़ीवालान चावड़ी बाजार, बाजार मिटिया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गाली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>	10.	एच.सी.सेन. रोड (100 फुट मागाधकार)
<ul> <li>12. बाजार दिल्ली दरवाजा</li> <li>13. नेताजी सुभाष मार्ग, सर सइयद अहमद मार्ग, गली कूचा चालान, गली पटौदी हाउस, गली कला महल</li> <li>14. गली चूडीवालान चावडी बाजार, बाजार मिटया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>15. अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गाली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।</li> <li>19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कला बाजार गुलियान, चावरी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>	11.	अजमेरी गेट राइ, बाजार साताराम, गला पूर्या नाता राज
13. नेताजी सुभाष मार्ग, सर सहयद अहमद मार्ग, गली कूचा चालान, गला पटादा हाउरा, नता महल  14. गली चूड़ीवालान चावड़ी बाजार, बाजार मिटया महल, सीताराम बाजार, गली पंडित प्रेम नारायण  15. अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार  16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब  17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड  18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।  19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा		
<ul> <li>महल</li> <li>गली चूड़ीवालान चावड़ी बाजार, बाजार मिटया महल, सीताराम बाजार, गली पंडित प्रेम नारायण</li> <li>अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार</li> <li>फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गाली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा</li> </ul>	12.	बाजार दिल्ली दरवाजा
नारायण   अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार   फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिरया रोड, गली बताशावाली, गली कूचा नवाब   नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड   कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई   सड़क, चाँदनी चौक ।   नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	13.	
नारायण   अजमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गंज, फराश खाना रोड लाल कुआं बाजार   फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिरया रोड, गली बताशावाली, गली कूचा नवाब   नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड   कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई   सड़क, चाँदनी चौक ।   नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा		महल
रोड लाल कुआं बाजार  16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब  17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड  18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।  19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	14.	गला चूडावालान चावडा बाजार, पाठार गठ
रोड लाल कुआं बाजार  16. फराश खाना रोड, समोसा वाली गली, फाजिल रोड, नया बांस रोड, बाजार खारी बावली, कटरा दिया रोड, गली बताशावाली, गली कूचा नवाब  17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड  18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक।  19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	1=	अनुमेरी गेट रोड, फाजिल रोड, गली शाह तारा, गली कूचा पंडित, गली शाह गर्ज, फराश खाना
<ul> <li>16. फराश खाना रोड, समोसा वाली गली, फाजिल राड, नया बास राड, बाजार कर दिया रोड, गली बताशावाली, गली कूचा नवाब</li> <li>17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड</li> <li>18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, ग्रांली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक ।</li> <li>19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाझ</li> </ul>	15.	रोड लाल कुआं बाजार
कटरा दिरया रोड, गली बताशविली, गली कूचा नवाब 17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी रोड 18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक । 19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	16	क्रिया खाना रोड समोसा वाली गली, फाजिल राड, नथा बाल राड, पाजार जा
17. नेताजी सुभाष मार्ग, दयानंद रोड अन्सारी राड 18. कटरा बारीयान रोड, लाल कुआं रोड, गली बल्लीमारान, गली कासिम जान, चावरी बाजार, नई सड़क, चाँदनी चौक। 19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिवा कला बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	1,0.	कट्य दरिया रोड् गली बताशावाली, गला क्या नवाब
18. कटरा बारीयान रोड, लाल कुआ रोड, गली बल्लामारान, ताल कारान जार सहक, चाँदनी चौक ।  19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कलां बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	17	
सड़क, चाँदनी चौक ।  19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दिखा कला बाजार गुलियान, चाबरी बाजार, छाता शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	<u> </u>	कटरा बारीयान रोड, लाल कुआ रोड, गली बल्लामारान, तला कारान कर
19. नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दारबा केला बाजार गुरावा , वर्ग मालीवाड़ा शाहजी, गली खजूर, गली कटरा कुशल राय, गली अनार वाली, किनारी बाजार, मालीवाड़ा	10.	सड़क, चाँदनी चौक ।
शाहजी, यली खजूर, गली कंटरा कुशल राय, गला अनार नारा,	19.	नई सड़क, चाँदनी चौक, एसप्लेनेड रोड, दरिबा कला बाजार गुणियान, पावरा मालीवाड़ा
1 \		शाहजी, गली खजूर, गली केंद्ररा कुशल राथ, गला उत्पार बराग
		\
20. चांदनी चौक, कटरा नील, चेच मिशन राड, कटरा १०५ र	20.	चांदनी चौक, कटरा नील, चर्च मिशन रोड, कटरा नटवर एरिया
21. एच.सी. सेन रोड, चांदनी चींक	21.	
22. बड़ा बाजार रोड	22.	बड़ा बाजार राड

## 2. क्षेत्र "क" (चार दीवारी शहर के अतिरिवत)

क्र.सं.		
1	रानी झांसी रोड (आजाद मार्किट से	गोशाला रोड के पास वाले क्रोसिंग से
	फिल्मिस्तान तक)	फिल्मिस्तान तक (पूर्व की ओर)
2	कुतुब रोड (सिंगाड़ा चौक से पुल मिठाई	सीनियर सेकेण्डरी स्कूल सदर बाजार के
-	(तक)	जंक्यान से पुल मिठाई और रोड के पश्चिम की
		ओर
3	सदर थाना रोड	सदर थाना से फूटा रोड
4	ईदगाह रोड	सिंगाड़ा चौक से सदर थाना रोड के क्रोसिंग
7	Artic 10	(रोड के उत्तरी साइड पर)
5	आजाद मार्किट रोड	आजाद मार्किट रोड से पुल मिठाई तक
6	चमेलियन रोड	रानी झांसी रोड क्रोसिंग से महाराजा अग्रसेन
	difference of	मार्ग जंक्शन तक
7	महाराजा अग्रसेन मार्ग	रानी झांसी रोड जंक्शन से कुतुब रोड क्रोसिंग
1	ACTION OF A LINE	तक (सदर बाजार)
8	मेन पहाड़गंज रोड	चेम्स फोर्ड रोड जंक्शन से रामकृष्ण आश्रम तक
9	देश बंधु गुप्ता रोड	पहाड़ गंज पुलिस स्टेशन क्रोसिंग से शीला
9	प्राचित्र पुरा राज	सिनेमा के सामने
10	राजगुरु रोड (गुरुवाला रोड)	देश बंधु गप्ता रोड जंक्शन से मेन बाजार
10	doily do (Braigh go)	पहाडगंज रोड जंक्शन तक
	नेहरु बाजार रोड	पंचकुइयां रोड जंक्शन से मेन पहाड़ गंज बाजार
11	नहरा वाजार राज	रोड जंक्शन तक

#### 3. क्षेत्र "ख

क्र.सं.		ं के मिर्ट के
1	देश बंधु गुप्ता रोड	फैज रोड क्रोसिंग से प्रस्तावित 30 मी0 रोड के जंक्शन तक (नक्शे में रोड नं0 -4)
2	बैंक स्ट्रीट	फैज रोड क्रोसिंग से रामकृष्ण मार्ग क्रोसिंग तक
3	हरध्यान सिंह रोड	कही फेज रोड क्रोसिंग से प्रस्तावित 30 मी0 चौड़ी रोड
4	आर्य समाज रोड	कासिंग तक (नक्शे में रोड नं0-4)
5	पदम सिंह रोड	सत्त्वावन गर्ल्स स्कूल रोड क्रासिंग से गुरुद्वारा रोड क्रासिंग तक
6	न्यू रोहतक रोड (दक्षिण साइड)	फैज रोड क्रांसिंग से जोशी रोड जंक्शन तक
7	रोड नं0 4 (प्रस्तावित 30 मी0 चौड़ी रोड	डी.बी.गुप्ता रीड क्रासिंग से पदमसिंह रोड जंक्शन
	पूर्व साइड)	तक

, .	A STATE OF THE STA	
8	न्यू पूसा रोड	ही.वी. गुप्ता शेंड अंक्शन से टेंक रोड अंकशन तक
9	रामकृष्णदास मार्ग	डी.वी. गुप्ता रोंड जंक्शन से नक्शे में रोड़ नं0 31
4		के जंकशन तक
10	विष्णु मंदिर मार्ग	नक्शे में डी.बी. गुप्ता रोड नं0 31 के जंक्शन से
11	सरस्वती मार्ग	ी.बी. गुप्ता रोड जंक्शन से आर्य समाज रोड
		अवशन तक
12	अजमल खां रोड	टेक रोड जंक्शन से पूसा लेन जंक्शन तक
13	गुरुद्वारा रोड	डी बी. गुप्ता रोड जंक्शन से पदम सिंह मार्ग
		जंदशन तक
14	लक्ष्मी द्वार मार्ग	आर्य समाज रोड जंक्शन से पूसा तेन जंक्शन तक
15	अब्दुल अजीज रोड	बैंक गली जंक्शन से आर्य समाज रोड जंक्शन तक
16	कृष्ण दास रोड	ही.बी. गुप्ता रोड जंक्शन से आर्य समाज रोड
	· · · · · · · · · · · · · · · · · · ·	जंब्शन तक
17	सत्बरावन आर्य गर्ल्स स्कूल मार्ग (पश्चिम	अर्थ संगाज रोड जंक्शन से पूसा लेन जंक्शन तक
	साइड)	
18	)जोशी रोड	न्यू रोहतक रोड ज्ंक्शन से डी.बी. गुप्ता रोड
		उक्ष्यन तक
19	अब्दुल रहमान रोड	हीं.बी. गुप्ता रोड जंक्शन से आर्य समाज रोड
		जंक्शन तक
20	इलाही वक्श मार्ग	वही
21	फैज रोड (पश्चिम साइड)	वही
		1

## 4. क्षेत्र "ग ".

	•
रोशननारा रोड	1.00
जी.टी. रोड	2:18
शक्ति मार्ग (नागिया पार्क के निकट)	0.32
सत्यवती रोड	0.15
मंडेला रोड	0.06
कोलाहपुर रोड	0.06
मल्कागंज रोड	0.88
	जी.टी. रोड शक्ति मार्ग (नागिया पार्क के निकट) सत्यवती रोड मंडेला रोड कोलाहपुर रोड

#### 5. क्षेत्र "घ"

		1.1
1.	टेंग्पल रोड, भोगल	
2.	शाही होस्पिटल रोड, भोगल	
3.	सेंट्रल रोड, भोगल	
4.	मस्जिद रोड, भोगल	•
5.	गुरुद्वारा रोड, लाजपत नगर-४	
6.	रिंग रोड़ के साथ नई दिल्ली साउथ एक्सटेंशन पार्ट-। सर्विस रोड	
7.	ब्लॉक "ओ " व के लाजपत नगर-2 के मध्य मेन रोड (24 मी0 चौड़ी)	• .
8.	सेंट्रल मार्किट और लाजपत नगर-2	
9.	अलंकार सीनेमा रोड/पुष्पा मार्किट रोड (लाजपत नगर)	
10.	भीष्म पितामह रोड (डिफेंस कालोनी)	
11.	दुकान प्लाटों के साथ सक्षम प्राधिकारी द्वारा अनुमोदित नक्शे का निर्मित भाग	

## 6. क्षेत्र "इ."

1.	शापिंग सेंटर, कृष्णा नगर		
2.	छोटा बाजार, शाहदरा		
3.	मेन गांधी नगर बाजार	·	-
4.	बड़ा बाजार, शाहदरा		
5.	अनाज मंडी, शाहदरा		
6.	विश्वास नगर, शापिंग एरिया		
7.	सीलमपुर का शापिंग एरिया/सलीमपुर		
8.	फर्श बाजार, शाहदरा	The Second	
9.	रेलवे रोड, शाहदरा		
10.	मेन रोड गांधी नगर		मार्जीनल बांध से झील बस टर्मिनल तक
11.	मेन विकास मार्ग		मार्जीनल बांध से पटपड़गंज रोड तक
12	विजय चौक रोड (लक्ष्मी नगर मेन रोड)		विकास मार्ग से पटपड़गंज रोड
13	पट्पइगंज रोड		जी.एच.बी.एस. और पुनर्वास कालोनियों
	•		के अतिरिक्त झील बस टर्मिनल से मधुबन
i			रेलवे क्रासिंग तक
14	रोड नं0 57		सी.जी.एच.एस. और सुविधा केन्द्रों के
	·		अतिरिक्त जी.टी. रेलवे लाइन से परवाना
			रोड तक
15	भोलानाथ नगर रोड		रोड नं0 57 से बाबूराम स्कूल तक
16	मंदिर मार्ग रोड		रघुनाथ मंदिर से रोड नं0 57 तक
17	रोड नं0 35 ए		पुल क्षेत्र और मदर डेरी प्लॉट के
		•	अतिरिक्त विकास मार्ग से मदर डेरी तक
18	60 फुटा चौड़ा रोड		तेलीवाड़ा से बाबूराम स्कूल तक

**** ** ******************************	<u>ार्क्सपुर</u> — प्राप्त का प्रमुख । प्राप्त का प्रमुख ।	अंदाह्मारण्
19 20 21 22	जी.टी रोड	रोड नं0 66 से घोंडा चीक जी.टी. रोड रो रोड नं0 68 तक राधू सिनेमा से लोनी रोड तक
23 24 25	रोड नं0 66  ब्रह्मपुरी मेन रोड  यमुना विहार रोड	जी.टी. रोड से केवल पश्चिम साइड पर रोड नं0 68 तक घोंडा चौक से न्यू सीलमपुर मार्किट रोड घोंडा चौक से डी.टी.सी. डिपो तक
26	60 फुटा चौड़ा रोड बलबीर नगर (बाबर पुर रोड) 100 फुटा रोड नं0 68 वजीरा बाद रोड	पूर्वी यमुना नहर से जी.टी. रोड तक पूर्वी यमुना नहर रेलवे लेवल क्रासिंग तक मार्जिनल बांध यमुना विहार योजना तक (केवल दक्षिण साइड)

## 7. क्षेत्र "च "

(क)	नई दिल्ली साउथ एक्सटेंशन पार्ट-२ (रिंग रोड पर सामने का भाग)
1 1	कालकाजी मेन रोड (ब्लॉक जी और एच तथा ई और एफ के मध्य)
	गरावाय नवर (मन माकिट राह)
(घ)	गोविंदपुरी और गोविंदपुरी विस्तार के एएम कर रे
(ਵ.)	दुकान प्लॉट, सक्षम अधिकारी द्वारा अनुमोदित नक्शे के अनुसार
	का अनुसार

#### 

क	लक्ष्मण सल्वानिया, न्यू मोती नगर चौक मेन नजफगढ़ रोड से बाहरी रिंग रोड क्रांसिंग तक
	गणेश नगर्।
ख	कीर्ति नगर मायापरी चौक से कीर्नि नगर को
ग	1 in the interest of the state of the s
घ	सुभाष नगर से दीन दयाल खाड्याय मार्गी
ਤ.	ातलक नगर चोक से नगल राय क्लार्ट को पर
ਧ	एच ब्लॉक, बाली नगर नजफगढ़ रोड से बी. ब्लॉक बाली नगर तक ।
	क्यां के तर्वा व्याक बाला नगर तक

## 

1.	रोड नं0 43 रानी बाग	<del></del>	
2.	मेन बाजार, ऋषि नगर	200 फुट	
3.	मेन बाजार (रोड रानी बाग)	50 फुट	
4.	मेन रोड राजा पार्क	50 फुट	
5.	मेन रोड, शास्त्री नगर	100 फੁਟ	$\dashv$
6.	क्रिक्ट के स्थापन	200 फੁਟ	$\dashv$
7	मेन रोड त्रिनगर ,	. 50 फ्ट	$\dashv$
1.	रोड नं0 41 रोहिणी	45 मी0	_

# MINISTRY OF URBAN DEVELOPMENT (Delhi Division)

## NOTIFICATION

New Delhi, the 7th September, 2006

**s.o. 1456(E).—** Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi 2001, were published in the Gazette of India, Extraordinary as public notice vide S.O. No. 1161 (E) dated 21<sup>st</sup> July 2006, by the Delhi Development Authority in accordance with the provisions of section 44 of the Delhi Development Act 1957 (61 of 1957) inviting objections and suggestions as required under sub-section (3) of Section 11 A of the said Act, within thirty days from the date of the said notice;

2. Whereas the objections and suggestions received with regard to the proposed modifications were considered by a Board of Inquiry duly constituted by Delhi Development Authority under the relevant rules, and the Authority, after considering the report of the said Board, has recommended the modification of the Master Plan of Delhi 2001 as envisaged in the said public notice, with certain changes;

- 3. And Whereas the Central Government has, after carefully considering all relevant aspects of the matter, decided to modify the Master Plan for Delhi 2001;
- 4. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11 A of the said Act, the Central Government hereby makes the following modifications in the said Master Plan for Delhi 2001 with effect from the date of Publication of this Notification in the Gazette of India.

#### **Modification:**

In Gazette of India, Part II, section 3, sub-section (ii) dated 1.8.1990 the following shall be incorporated:-

(i) †On page 165(RHS) under CLAUSE 10.0 MIXED USE REGULATIONS the existing provisions, as modified vide notification S.O. No. 425(E) dated 28.3.2006 shall be substituted by the following:-

#### 10.0 MIXED USE REGULATIONS

This chapter covers the policy for mixed use of land for certain permissible purposes. The policy acknowledges the need for permitting use of land for purposes other than that for which it was originally envisaged and lays down the conditions under which this may be applied in different situations. The general procedure to be followed for implementation of the said policy, and mitigating measures to be taken to counter the effect of such non-intended use in such areas are also described.

## 10.1 GOVERNING PRINCIPLES FOR MIXED USE

- Mixed use for the purposes of this Chapter means the provision for non-residential activity in residential premises.
- ii. The policy aims to balance the socio-economic need for such activity and the environmental impact of the said activity in residential areas.
- iii. Mixed use allows access to commercial activities in the proximity of the residences and reduces the need for commuting across zones in the city. However at the same time, it needs to be regulated in order to manage and mitigate the associated adverse impact related to congestion, increased traffic and increased pressure on civic amenities.
- iv. The over-riding principles for permitting mixed use are the need to acknowledge and make adequate provision for meeting community needs, mitigating environmental impact and providing for safe and convenient circulation and parking.
- v. Mixed-use shall not be permitted in the Lutyens Bungalow Zone, Civil Lines, Government housing, institutional and staff housing of public and private agencies and buildings/precincts listed by the Heritage Conservation Committee.

27835206-1

## 10.2. MIXED USE IN RESIDENTIAL AREAS:

## 10.2.1. DIFFERENTIATED APPROACH:

- policy arises from the fact that Delhi, being the country's capital and an important centre of economic activity has a large diversity in the typology of residential areas. Apart from the planned residential colonies built as part of Lutyens' Delhi as well as through the process of planned development undertaken by the Delhi Development Authority, there are authorized residential areas in the Walled City, Special areas and urban villages. Other planned areas include resettlement colonies and pre-Delhi Development Act colonies, including post-partition rehabilitation colonies. There are also regularized-unauthorized colonies; unauthorized colonies as well as slums and jhuggi jhonpri clusters in various parts of Delhi.
- being necessary or desirable by the residents themselves varies from area to area based on the socio-economic status of the residents as well as the past pattern of development in that area. While certain colonies may need non-residential activity as an integral part of their livelihood, some others may wish to preserve the residential character of their colonies and neighborhood.
- lii) Hence it is proposed to follow a differentiated approach in the application of the mixed use policy in Delhi. The

٠,

भारत वर्ग राजपुत्र : असुष्या

differentiated approach would be based on categorization of colonies from A to G as adopted by MCD for Unit Area method of property tax assessment.

## 10.2.2. TYPES OF MIXED USE

Subject to the provisions of this notification, the following three broad types of mixed use shall be permissible, in residential premises:

- Commercial activity in the form of retail shops as per conditions given in para 10.6 in plots abutting notified mixed use streets.
- ii) "Other activity" broadly in the nature of 'Public and Semi-Public' facilities listed in para 10.7.1 and as per conditions specified in para 10.7, in plots abutting roads of minimum ROW prescribed in para 10.3.2.
- iii) Professional activity as per conditions specified in para 10.8,

The above mentioned types of mixed use shall be subject to the general terms and conditions specified in the succeeding paragraphs.

# 10.3 IDENTIFICATION OF MIXED USE AREAS IN EXISTING URBAN AREAS AND URBANIZABLE AREAS:

The identification of mixed use areas / streets in both the urbanized/urban as well as urbanizable areas of Delhi would be as follows:

10.3.1. In already urbanized /urban areas, mixed use shall be permissible in the following areas:

278341/06-2

- On all streets/ stretches already notified by the i. competent authority under MPD 2001 and indicated in Annexure-I (List of identified stretches / Streets).
- Residential areas and Streets/ stretches earlier declared ii. as commercial areas/ streets or where commercial use was allowed in MPD 1962 shall continue such use at least to the extent as permissible in MPD 1962.
- Commercial activity existing from prior to 1962 in iii. residential areas, subject to documentary proof thereof.
- Identification and Notification of mixed use streets in iv. future, shall be based on the criteria given in para 10.3.2 and as per procedure prescribed in para 10.3.3, and given wide publicity by the local bodies concerned.
  - 10.3.2. The extent of mixed use permissible in various categories of colonies is further clarified as follows:
  - In colonies falling in categories A and B:

No commercial activities will be permissible in the colonies of A & B categories except the following:

- Professional activity, subject to conditions given in para 10.8.
- Mixed use and Commercial activity up to one plot depth, in plots abutting Master Plan roads that are notified as mixed use streets, and Commercial streets respectively, since such groads are not internal to the colonies  $\boldsymbol{\xi}$ (provided that the request of the RWA concerned shall \) not be necessary for notifying the Master Plan Roads: abutting the colonies, as mixed use streets or Commercial Streets).

- "Other activity" restricted to Guest Houses, Nursing Homes and Pre-primary Schools, as defined in para 10.7.1, subject to conditions contained in para 10.7, in plots abutting roads of minimum 18m ROW in regular plotted development, since these activities are in the nature of 'Public and Semi-Public' facilities. New Banks and Fitness Centres will not be permissible with effect from the date of this notification. Banks and Fitness Centres, which already exist, in accordance with notifications issued in this regard under Master Plan for Delhi 2001, from time to time, and are on plots abutting roads of minimum 18m ROW, on the date of notification, shall, however, remain permissible.
- Retail shops in terms of para 10.6. on such mixed use streets with a minimum 18 m ROW, within the colony, in regular residential plotted development, as are notified in terms of para 10.3.3, if there is a specific request of the RWA concerned, in terms of para 10.10.

#### Note:

Commercial activity on mixed use streets, within A & B category colonies, earlier notified under MPD 2001 shall cease with immediate effect (other than in plots abutting Master Plan roads).

## 2. <u>In colonies falling in categories C and D:</u>

 Mixed use in the form of Retail shops shall continue to be permissible as per conditions in para 10.6, in plots abutting notified mixed use streets listed in Annexure I.

- "Other activity" in terms of para 10.7 shall be permissible in plots abutting roads of minimum 18 m ROW in regular plotted development, 13.5 m ROW in rehabilitation colonies and 9m ROW in Walled City, Regularized-Unauthorized colonies, resettlement colonies, Special areas, and Urban Villages, subject to conditions in para 10.7.
- Notification of mixed use streets in future, of minimum
  18 m ROW in regular residential plotted development,
  13.5 m ROW in rehabilitation colonies and 9 m ROW in
  Regularized-unauthorized colonies, resettlement
  colonies, Walled city, Special Area and urban villages in
  terms of para 10.3.3 shall be subject to consultation
  with RWAs concerned in terms of para 10.10.
- Mixed use shall be permissible in Pedestrianised
   Shopping streets as per para 10.3.3.
- Professional activities shall be permissible as per conditions laid down in para 10.8.

## 3. In colonles falling in categories E, F and G:

- Retail shops shall continue to be permissible as per conditions in para 10.6., in plots abutting notified mixed use streets listed in Annexure I.
- "Other activity" in terms of para 10.7 shall continue to be permissible in plots abutting roads of minimum 13.5 m ROW in regular plotted development, 9 m ROW in rehabilitation colonies and 6m ROW in Walled City, Regularized-Unauthorized colonies, resettlement

colonies, Special areas, and urban Villages subject to conditions in para 10.7.

- Professional activities shall be permissible subject to conditions in para 10.8.
- Notification of mixed use streets in future, of minimum 13.5 m ROW in regular residential plotted development, 9 m ROW in rehabilitation colonies and 6 m ROW in Regularized-Unauthorized colonies, resettlement colonies, walled City, Special Area and urban villages shall be in terms of para 10.3.3.
- Mixed use shall be permissible in Pedestrianised
   Shopping streets as per para 10.3.3.

## 4. Group housing in all categories of colonies:

- Only professional activity shall be permissible. Retail shops specifically provided for in the lay out plan of group housing would be permissible.
- (excluding Lutyens Bungalow Zone, Government housing, institutional and staff housing of public and private agencies and buildings/precincts listed by the Heritage Conservation Committee), existing mixed use streets / stretches will be notified by NDMC. Future notification of mixed use streets/ stretches will be done on a field level survey to assess the community needs, environmental impact and traffic circulation/ adequate parking and in consultation with Residents Welfare Associations concerned.

278361/06-3

### 10.3.3. Notification of mixed use streets in urban areas in future;

The minimum ROW for identification of a street or i). stretch of road as mixed use street would be as follows:

In A&B Colonies: 18m ROW in regular plotted dévelopment, if there is a specific

request of the RWA concerned.

In C&D colonies:

18 m ROW in regular residential plotted development, 13.5 m ROW in rehabilitation colonies and in Regularised-9 m ROW colonies, Unauthorised resettlement colonies, City, Special area and urban villages; in consultation with RWA concerned.

In E,F&G Colonies: 13.5 m ROW in regular plotted development, 9 m ROW in rehabilitation colonies and 6m ROW in Walled City, Regularizedcolonies, Unauthorized resettlement colonies, Special areas, and Urban Villages.

Streets of less than 9 m (or 6 m in E, F & G category ii) ROW in Regularised-Unauthorised colonies, resettlement colonies, urban villages, Special Area and Walled City, if notified for mixed use, shall be declared as Pedestrian Shopping Streets (PSS) and will not be open to motorized transport.

#### Note:

- Request of the RWA concerned or consultation with RWAs concerned, shall not be necessary for notifying the Master Plan Roads abutting the colonies as mixed use streets, since such roads are not internal to the colonies.
- (b) Specific request of or consultation with RWA concerned shall be governed by para 10.10
- shall be required to carry out within a reasonable time of the Notification coming into force, and with due expedition, a survey of all streets of the above-mentioned width, if not already done, with a view to identifying stretches of such streets as mixed use streets.
- iv) The field survey shall assess the extent of existing nonresidential use on the street, the stretch of the street to be notified, the additional requirement of civic amenities and the provision for traffic circulation and parking.
- v) The notification shall be issued by the local body/ Authority, with the approval of the Competent Authority under the relevant Act, immediately after the field survey is completed.

# 10.3.4. Notification of mixed use streets in urbanizable areas in future:

In new urbanizable areas, mixed use shall be permissible in the following areas:

- i) In newly developed residential areas, mixed use as specified above shall be permitted only on residential plots abutting 18 m. ROW roads.
- ii) In villages that are declared as urban and get integrated into the process of development, mixed use shall be permissible in areas/ stretches identified in the local area plan/ lay out plan prepared for such integration.
- iii) The layout plan in such new areas shall earmark such stretches/ plots and notify them under the Mixed Use Policy at the time of grant of permission for layout plan in the case of private development and at the time of disposal by allotment or auction in the case of areas developed by DDA.

## . 10.4 GENERAL TERMS AND CONDITIONS GOVERNING MIXED USE:

In terms of the conditions prescribed for different categories of colonies, in para 10.3.2, and provided that the plot abuts a notified mixed use street (in the case of retail shops) or a road of prescribed minimum ROW (in the case of other mixed use activities), mixed use shall be permitted, subject to the following general terms and conditions:

### In residential plotted development:

(i) Where there is only one dwelling unit in a residential plot, only one type of mixed use (i.e., retail shop as per para 10.6 OR professional activity OR one of the other activities listed in para 10.7) shall be permissible in that unit.

4

where there are more than one dwelling units in a residential plot, each of the dwelling units will be permitted to have only type of mixed use activity (either retail shop as per para 10.6, OR professional activity OR any one of the other activities listed in para 10.7)

#### In group housing:

(iii) In group housing, only professional activity is permissible. Retail shops shall be permissible if specifically provided for in the lay out plan of group housing.

## Other terms and conditions:

- (iv) No encroachment shall be permitted on the streets or public land.
- (v) Development control norms as applicable for the particular residential use will continue to be applicable, even if the plot/ dwelling unit is put to mixed use.
- (vi) If the notified street is a Master Plan Road, and if a service road is available or provided for by local bodies, then, the mixed use premises should be approached from such service road and not directly from the main carriageway,
- (vii) In plotted development, front setback should not have boundary wall, so that it can be used for additional parking.
- (viii) Parking @ 2.0 ECS per 100 sqm shall be provided within the premises. Where this is not available, cost of development of parking, shall be payable by the plot

278302/06-4

11

- allottee/ owner to the local body concerned. This condition shall apply even if residential premises are used only for professional activity.
- (ix) Common parking areas would be earmarked on notified mixed use streets taking into account the additional load on traffic and parking consequent upon notification of the street under Mixed Use Policy. If no parking space is available, land/ plot on the said street may be made available by Traders association, wherever possible, or acquired for construction of parking facilities, preferably, multi-level parking. Development of such parking facilities shall be done by either the traders Association or by local bodies and may include public-private partnership as a model for implementation.

#### 10.5 PERMISSIBLE AND NON-PERMISSIBLE USES:

Any trade or activity involving any kind of obnoxious, hazardous, inflammable, non-compatible and polluting substance or process shall not be permitted.

#### 10.6 RETAIL SHOPS

- i. Retail shops shall be permitted on plots abutting streets notified for mixed use only on the ground floor and up to the maximum permissible ground floor coverage.
- ii. The following activities shall not be allowed under Mixed Use:
  - a) Retail shops of building materials (timber, timber products (excluding furniture), marble1, iron and

steel, (gravel, cement and sand)2), firewood, coal and any fire hazardous and other bulky materials.

- b) Repair shops of automobiles repair and workshop, tyre resoling and re-treading, and battery chargings.
- c) Storage, go-down and warehousing.
- d) Junk shop
- e) Liquor shop
- f) Printing, dyeing and varnishing
- g) Any other activity that may be notified from time to time by Government.

#### Note:

- Will not include business of finished marble products where cutting and polishing activity of marble is not undertaken.
- Retail shops of gravel, sand and cement shall be permissible in residential plots of at least 50 sqm, in notified mixed use streets in E , F, and G category colonies , provided that the material is kept entirely within the plot premises.

The repair shops and workshops in case of automobiles shall not be prohibited on plots abutting mixed use streets or commercial streets of right of way (ROW) of 30 m or more

#### 10.7 OTHER ACTIVITY

10.7.1 Subject to the general conditions given in para 10.4 and additional conditions given in para 10.7.3, the following public and semi-public activities shall also be permitted in the residential plots abutting roads of minimum ROW prescribed in 10.7.2, whether or not the road is notified as mixed use street:

- (a) Pre-primary school (including Nursery/Montessori School, Crèche.)
- (b) Nursing home (including clinic, dispensary, pathology lab and diagnostic centre)
- (c) Guest house (including lodging houses) irrespective of number of rooms.
- (d) Bank
- (e) Fitness Centre (including Gymnasium, yoga/ meditation centre)

10.7.2. The minimum ROW of a street or stretch of road on which the above-mentioned other activities are permissible is as follows:

In A&B Colonies\*:

18m ROW in regular plotted development;

## Note

\*Banks and fitness centres shall however, not be permissible, except those already operating on the date of this notification.

In C&D colonies:

18 m ROW in regular residential plotted development, 13.5 m ROW in rehabilitation colonies and 9 m ROW in Regularized-Unauthourised colonies, resettlement colonies, Walled City, special area and urban villages; and in Pedestrianised Shopping Streets.

In E,F &G Colonies:

development, 9 m ROW In rehabilitation colonies and 6m ROW in Walled City, Regularised-Unauthourised colonies, resettlement colonies, Special areas, and urban Villages and in Pedestrianised Shopping Streets.

- 10.7.3. The above mentioned public and semi-public activities shall be subject to the following additional conditions in addition to general conditions prescribed in preceding paras:
  - succeeding paras, the minimum size\*\* of the plot on which these activities shall be permissible, on streets of prescribed minimum ROW, shall be 200 sqm in regular plotted development, 75 sqm in rehabilitation colonies, regularized-unauthorized colonies, resettlement colonies, Walled City, special area & urban villages. However, the minimum plot size shall be 50 sqm for clinic, dispensaries and pathology labs running in these colonies and also in E, F and G Category colonies.
  - (ii) Banks shall be permissible on 2/3<sup>rd</sup> of FAR subject to 600 sqm, while Guest House and Nursing Homes will be permissible up to 3/4<sup>th</sup> of the floor area.
  - (iii) However, Nursing Homes operating in plots abutting Master Plan roads and Zonal Plan roads shall be

278362/06-5

- permissible up to 100% of built up area and the limits on the size of the plot would not apply.
- (iv) Guest Houses operating in plots abutting streets of prescribed minimum ROW in Special Area and in plots abutting Master Plan roads and Zonal Plan roads shall be permissible up to 100% of built up area and the limits on the size of the plot shall not apply.
- (v) Pre-primary school and fitness centre (other than those on plots abutting Commercial streets) shall be restricted only to the ground floor up to the permissible ground coverage.
- (vi) The above mentioned activities shall also be subject to any other specific terms and conditions, as may be prescribed in the relevant Statutes/ Acts applicable to them.
- (vii) It shall be the responsibility of the plot allottee/ owner to make arrangements for parking so that the parking does not encroach/ spill over on public land.

## Note:

\*\*Variation of  $\pm$  5% in plot size may be disregarded.

10.7.4. **Banquet hall** shall be permissible only in industrial areas and commercial areas and not in the residential use zone. Development control norms in respect of Ground coverage, FAR, height and basement shall be applicable as per Master Plan Norms for the specific land use for that premises.

# 10.8. PROFESSIONAL ACTIVITY

Subject to the general terms and conditions specified in para 10.4, professional activity is permissible in plotted development and group housing under the following specific conditions:

- Professional activity shall be permitted if carried out by the resident him/her self.
- ii. Professional activities shall mean those activities involving services based on professional skills namely Doctor, Lawyer, Architect, and Chartered Accountant.
- iii. In group housing, and plotted development with multiple dwelling units, professional activity shall be permitted on any floor subject to maximum of 50% of the permissible or sanctioned FAR, whichever is less, of each dwelling unit
- iv. In the case of plotted development with single dwelling unit, professional activity shall be permissible on any one floor only, but restricted to less than 50% of the permissible or sanctioned FAR, whichever is less on that plot.

# 10.9 REGISTRATION OF MIXED USE PREMISES AND PAYMENT OF CHARGES:

In respect of a residential premises already under mixed use or intended to be put to mixed use, the owner/allottee/ resident of the plot/ dwelling unit, in case of plotted development and dwelling unit in the case of group housing, shall be required to declare such mixed-use by filling up a form in this respect and

depositing it with the local body concerned and pay onetime registration charges at rates to be notified with the approval of the Central Government.

- ii. The premises under mixed use shall also be liable for payment of mixed-use charges every year to the local body concerned, at the rates notified with the approval of Central Government, for the period during which the property is put to mixed use. Such payment will be made by the property owner/ allottee voluntarily before 30<sup>th</sup> June of every year in respect of the previous assessment year (April- March).
- iii. No modification to the building for using residential premises for non-residential activities, under the mixed use policy, shall be permitted unless the allottee/ owner has obtained sanction of revised building plans and has paid necessary fees or charges.
- iv. The local body concerned shall be responsible for the conduct of test check of properties under mixed use, whether registered with it or not.
- v. In addition to other penal action available under the relevant Act, properties found to be under mixed use, without registration or in violation of the terms of this notification shall be liable to pay, to the local body, a penalty amounting to 10 times the annual conversion charges for mixed use.

# 10.10 CONSULTATION WITH RWASI

- The Resident Welfare Association (RWA) shall be a body registered before 21.7.2006, under any Statute, such as Societies Registration Act.
- il. Consultation with the RWA concerned for the purposes of declaring mixed use streets shall be done by the local bodies concerned.
- iii. Genuine efforts for meaningful consultations with RWAs shall be made by the local bodies. Such efforts may include wide publicity to the proposed consultations, maintenance of record of consultation and providing access to those records to RWA concerned and public.
- iv. Consultation with the RWA concerned shall be limited to identification of mixed use streets, and not for grant of permission in individual cases. However RWAs shall have a right to be heard in cases of complaints of public nuisance and non-permissible uses.

# 10.11 UNDER WHAT CONDITIONS MIXED USE CAN BE DENIED/ WITHDRAWN/ RESTRICTED:

10.11.1. Permission or registration for mixed use can be cancelled or suspended by the concerned local body in case of violation of any of the conditions under which such mixed use is permissible/ permitted.

10.11.2. The following non-residential activities, not covered under the mixed use policy, shall be permissible in residential areas under the following conditions:

278361/06-6

- (i) Schools operating in residential premises in the Residential use zones shall continue till 18<sup>th</sup> May 2007. The local body concerned may allow the schools to continue thereafter, subject to necessary changes being made in the use-premises/ lay-out plan, by the local body, within its competence, in terms of Sub clause 8 (2) A of the Master Plan for Delhi 2001 (Page 152 -153 under S.O. 606 (E) in the Gazette of India Extraordinary dated 1.8.1990), and for this purpose the schools shall be required to apply to the local body concerned.
- (ii) In addition, Coaching centres and similar educational institutions, running in residential premises, shall be allowed to continue till the end of the current academic year or till 18<sup>st</sup> May 2007, whichever is earlier.

## 10.12 COMMERCIAL STREETS AND AREAS:

- 10.12.1. The following streets/ stretches of streets or areas may be notified as Commercial Streets or Commercial areas by the local authority:
- (a) where more than 70% of the plots abutting roads of ROW exceeding 24m, in a stretch of at least 300m, in regular plotted development are under commercial use, on (provided that no street in colonies in A and B categories shall be notified as commercial street).
- (b) where more than 70% of the properties abutting roads of less width than 24m ROW, in a stretch of at least 100m, in rehabilitation colonies, Regularized-Unauthorized colonies, resettlement colonies, Walled City, Special Area and urban

Villages and local commercial streets declared under MPD 1962 as per para 10.3.1; and

- (c) In E, F and G category colonies, where, [If] 80% of residential plots are under mixed use, or if there are 300 shops, within a contiguous area of 1 hectare.
  - 10.12.2. Identification of such streets/ stretches is to be done on the basis of field survey to be conducted by the local body within a reasonable period of time and with due expedition of the date of this notification coming into force.
  - 10.12.3 After identification is done, notification of commercial stretches/ streets by the local body/ authority with the approval of the Competent Authority would necessitate compliance to the following terms and conditions:
  - i) Preparation of revised lay-out plan Scheme for such areas/ streets with the approval of the local body/ Authority;
  - ii) The lay-out plan/ Scheme for such areas/ streets should indicate adequate provision for circulation, parking, open spaces and other planning norms;
  - iii) Common parking areas would be earmarked taking into account the additional load on traffic and parking consequent upon notification of the street as commercial area/ street. If no parking space is available, land/ plot on the said street/ area may be made available by Traders association, wherever possible, or acquired for construction of parking facilities, preferably, multi level parking. Development of such parking facilities may be done by either the traders Association or by local bodies and may include public-private partnership as a model for implementation.

278395/06-7

iv) On notification of a Commercial street/ area under this clause, such streets/ areas shall be considered as non-hierarchical commercial centres as mentioned in Development Code in Master Plan 2001. The plot owners / allottees on these commercial streets/ areas shall have to pay Special conversion charges at rates approved by the Central Government, in respect of the built up area used for commercial purpose, provided that such built up area shall not exceed the residential development control norms applicable to the plot. This is only a one-time facility for plot allottees/ owners in such Commercial areas/ streets and shall not be construed as relaxation of the development control norms in future.

v). Any other condition that may be prescribed by Government from time to time.

[No.K-13011/2/2006/DDIB]

S. MUKHERJEE, Under Secy.

## Annexure - I

## MIXED USE STREETS IN VARIOUS ZONES OF DELHI

1. Zone 'A' & part 'C' (Walled City)

- Chandni Chowk road ( 100 ft R/W) 1.
- Netaji Subhach Marg (80 ft. R/W) 2.
- Ansari Road (60 ft. R/W) 3.
- Khari Back (80 ft. R/W) 4.
- Naya Bazar Road (80 ft. R/W) 5.
- Shardanand Mary (80 ft. R/W) 6.
- Ajmeri Gate Sazar (60 ft. R/W) 7
- Church Mission Road (60 ft. R/W)
- 8.
- S.P.M. Marg (120 ft. R/W) 9.
- H.C Sen Road (100 ft. R/W) 10.
- Ajmeri Gate Road Bazar Sita Ram, Gali Kucha Pati Ram, Gali Arya Samaj, Gali Kali Masjid, Gali Katra Anikhan.
- Bazar Dilli Darwaza 12.
- Netaji Subbash Marg, Sir Syed Ahmad Marg, Gali Kuncha Chalon, Gall Pataudi House, Gall Kala Mehal,
- 14. Gali Churiwalan Chawri Bazar, Bazar Matia Mahal, Sita Ram Bazar, Gali Pandit Prem Narainh
- Ajmeri Gate Road, Fasil Road, Gali Shah Tara, Gali 15. Kucha Pandit, Gali Sahaganj Farashkhana Road, Lai Kuan Bazar.
- Farash Khana Road, Samosa Wali Gali, Fasil Road, Naya Bans Road, Bazar Khari Baoli, Katra Dariyan Road, Gali Batashawali, Gali Kucha Nawab.
- Netaji Subhash Marg, Dayanand Road, Ansari 17. Road
- Katra Bariyan Road, Lal Kuan Road, Gali 18. Ballimaran, Gali Kashim Jaan, Chawri Bazar, Nai Sarak, Chandni Chowk.
- Nai Sarak, Chandni Chowk Esplanade Road, Dariba 19. Kalan Bazar Gulian, Chawri Bazar, Chatta Shahji, Gali Khajoor, Gali Katra Kushal Rai, Gali Anar Wali, Kinari Bazar, Maliwara Road.
- Chandni Chowk, Katra neel, Church Mission Road, 20. Katra Natwar Area.
- H.C. Sen Road, Chandni Chowk 21.
- Bara Bazar Road. 22.

1111	 	-	-	 	 	IΚΛ	بالالا	/11.7/3	•
							<u></u>		

2.	Zone - A (Part other	than Walled City):
1.		From crossing with Gaushala
<del>-</del> -		Road to Filmistan (On East side)
	Chowk to Filmistan)	
2.	Outub Road	From junction near Sr. Sec.
	(Singhara Chowk to	
	Pul Mithai)	and Western side of the road.
3.	Sadar Thana Road	Sadar Thana to Phoota Road
4.	Idgah Road	Singhara Chowk to crossing with
		Sadar Thana Road (on North
		side of the road)
5.	Azad Market Road	Azad Market Road to Pul Mithai
6.	Chamelian Road	From crossing with Rani Jhansi
		Road to junction with Maharaja
	,	Agrasen Marg.
7.	Maharaja Agrasen	From junction with Rani Jhansi
}	Marg	Road to crossing with Qutub
		Road (Sadar Bazar)
8.	Main Paharganj	From junction with Chemsford
	Road	Road to Ram Krishna Ashram
9.	Desh Bandhu Gupta	Paharganj Police Station
	Road	Crossing to opposite Sheila
10	, Deferme De-2	Cinema.  Junction with Desh Bandhu
10.	1	Gupta Road to junction with
	(Guru Wala road)	main bazaar Paharganj Road
11	Nehru Bazar Road	From junction with Panchkuin
11.	Heilia pazai Koad	Road to junction with main
	•	Paharganj Bazar road
L	<u> </u>	1.0

3:	Zone - B:			
1.	Desh Bandhu Gupta Road	From crossing with Faiz Road to junction with proposed 30 mtr Road (road No.4 in the layout plan)		
2.	Bank Street	From crossing with Faiz road to crossing with Rama Krishna Marg		
3.	Hardhyan Singh Road	-do-		
4.	Arya Samaj Road	From crossing with Faiz Road to crossing with proposed 30 mtrs. wide road(Road No.4 in the layout plan).		

5. Padam Singh Road Girls School road to Crossing with Gurudwara Road 6. New Rohtak Road (South Side) From crossing with Faiz Road to junction with Joshi road (East Side) From crossing with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Tank Road Road to junction with D.B.Gupta Road No.31 of the layout plan From junction with D.B.Gupta Road No.31 of the layout plan Road No.31 of the layout plan From junction with D.B.Gupta Road to junction with Arya Samaj Road 11. Saraswati Marg From junction with Tank Road to junction with Pusa Lane From junction with Pusa Lane From junction with Padam Singh Road 14. Laxmi Dwar Marg From junction with Pusa Land Road to junction with Pusa Land From junction with Bank Street Road to junction with Bank Street Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road 16. Krishna Dass Road From junction with D.B.Gupta Road to junction with Arya
Girls School road to Clossing with Gurudwara Road  6. New Rohtak Road (South Side)  7. RoadNo.4(Proposed 30M wide Road (East Side)  8. New Pusa Road  9. Ram Krishan Dass Marg  10. Vishnu Mandir Marg  11. Saraswati Marg  12. Ajmal Khan Road  13. Gurudwara Road  14. Laxmi Dwar Marg  15. Abdul Aziz Road  6. New Rohtak Road From crossing with Eaiz Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road No.31 of the layout plan  15. Abdul Aziz Road  7. RoadNo.4(Proposed 30M with John Crossing with Jo
with Gurudwara Road  6. New Rohtak Road (South Side)  7. RoadNo.4(Proposed 30M wide Road (East Side)  8. New Pusa Road  9. Ram Krishan Dass Marg  10. Vishnu Mandir Marg  11. Saraswati Marg  12. Ajmal Khan Road  13. Gurudwara Road  14. Laxmi Dwar Marg  15. Abdul Aziz Road  16. New Rohtak Road (From crossing with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road No.31 of the layout plan  16. From junction with D.B.Gupta Road No.31 of the layout plan  17. From junction with D.B.Gupta Road to junction with Pusa Lane  16. New Rohtak Road From crossing with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Pusa Land From junction with Pusa Land Road to junction with Pusa Land From junction with Bank Street Road to junction with D.B.Gupta Road to junction with Bank Street Road to junction with D.B.Gupta Road to junction with Pusa Land From junction with Bank Street Road to junction with D.B.Gupta Road to junction with Pusa Land Road Road Road Road Road Road Road Roa
6. New Rohtak Road (South Side)  7. RoadNo.4(Proposed 30M wide Road (East Side)  8. New Pusa Road  9. Ram Krishan Dass Marg  10. Vishnu Mandir Marg  11. Saraswati Marg  12. Ajmal Khan Road  13. Gurudwara Road  14. Laxmi Dwar Marg  15. Abdul Aziz Road  7. RoadNo.4(Proposed 30M with Joshi road From crossing with D.B.Gupta Road to junction with Padam Singh Road  8. From junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road No.31 of the layout plan  15. Abdul Aziz Road  16. From junction with D.B.Gupta Road to junction with Pusa Land  17. Abdul Aziz Road  18. From junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Pusa Lane  18. From junction with Pusa Lane  19. From junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Pusa Lane  19. Ram Krishan Dass Road From junction with D.B.Gupta Road to junction with Pusa Lane  10. Vishnu Mandir Marg From junction with Padam Samaj Road  11. Saraswati Marg From junction with Padam Singh Road  12. Ajmal Khan Road From junction with Padam Singh Road  13. Gurudwara Road From junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Bank Street Road to junction with D.B.Gupta Road to junction with Pusa Land
(South Side)   junction with Joshi road
(South Side)   junction with Joshi road
7. RoadNo.4(Proposed 30M wide Road (East Side)  8. New Pusa Road Road Road to junction with D.B.Gupta Road to junction with Tank Road  9. Ram Krishan Dass Road Road to junction with D.B.Gupta Road to junction with Road No.31 of the layout plan  10. Vishnu Mandir Marg From junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg From junction with D.B.Gupta Road No.31 of the layout plan  12. Ajmal Khan Road From junction with Arya Samaj Road  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Pusa Lane  14. Laxmi Dwar Marg From junction with Arya Samaj Road  15. Abdul Aziz Road From junction with Bank Street Road to junction with D.B.Gupta
30M wide Road (East Side)   Road to junction with Padam Singh Road   From junction with D.B.Gupta Road to junction with Tank Road Road to junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Road No.31 of the layout plan   From junction with D.B.Gupta Road No.31 of the layout plan   From junction with D.B.Gupta Road No.31 of the layout plan   From junction with D.B.Gupta Road to junction with Arya Samaj Road   From junction with Tank Road to junction with Pusa Lane   From junction with D.B.Gupta Road to junction with D.B.Gupta Road to junction with Padam Singh Road   From junction with Padam Singh Road   From junction with Pusa Land   From junction with Bank Street Road to junction with Arya Samaj Road   From junction with D.B.Gupta   Road to junction with Pusa Land   From junction with Pusa Land
(East Side)  Singh Road  From junction with D.B.Gupta Road to junction with Tank Road  Road to junction with D.B.Gupta Road to junction with Road No.31 of the layout plan  10. Vishnu Mandir Marg  From junction with D.B.Gupta Road No.31 of the layout plan  From junction with D.B.Gupta Road No.31 of the layout plan  From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road  From junction with Tank Road to junction with Pusa Lane  From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land  From junction with Pusa Land  From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road  From junction with Bank Street Road to junction with Arya Samaj Road  From junction with D.B.Gupta
8. New Pusa Road From junction with D.B.Gupta Road to junction with Tank Road  9. Ram Krishan Dass From junction with D.B.Gupta Road to junction with Road No.31 of the layout plan  10. Vishnu Mandir Marg From junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with Bank Street Road to junction with D.B.Gupta Road to junction with Arya Samaj Road
Road to junction with Tank Road  9. Ram Krishan Dass From junction with D.B.Gupta Road to junction with Road No.31 of the layout plan  10. Vishnu Mandir Marg From junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with Bank Street Road to junction with D.B.Gupta Road to junction with Bank Street Road to junction with D.B.Gupta Road to junction with Arya Samaj Road
9. Ram Krishan Dass Road to Junction with Road Road to Junction with Road No.31 of the layout plan  10. Vishnu Mandir Marg From Junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg From Junction with D.B.Gupta Road to Junction with Arya Samaj Road  12. Ajmal Khan Road From Junction with Tank Road to Junction with Pusa Lane  13. Gurudwara Road From Junction with D.B.Gupta Road to Junction with Padam Singh Road  14. Laxmi Dwar Marg From Junction with Arya Samaj Road to Junction with Bank Street Road to Junction with Bank Street Road to Junction with Arya Samaj Road  15. Abdul Aziz Road From Junction with Bank Street Road to Junction with D.B.Gupta
Road to junction with Road  No.31 of the layout plan  From junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg  From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road  From junction with Tank Road to junction with Pusa Lane  From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Bank Street Road to junction with Bank Street Road to junction with Arya Samaj Road  From junction with Bank Street Road to junction with Arya Samaj Road
Marg Road to junction No.31 of the layout plan  10. Vishnu Mandir Marg From junction with D.B.Gupta Road No.31 of the layout plan From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane From junction with D.B.Gupta Road to junction with Padam Singh Road From junction with Arya Samaj Road to junction with Pusa Land From junction with Pusa Land From junction with Pusa Land Road to junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with D.B.Gupta
10. Vishnu Mandir Marg From junction with D.B.Gupta Road No.31 of the layout plan  11. Saraswati Marg From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road
10. Vishnu Mandir Marg Road No.31 of the layout plan Road No.31 of the layout plan Road to junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane From junction with D.B.Gupta Road to junction with Padam Singh Road From junction with Arya Samaj Road to junction with Pusa Land From junction with Pusa Land From junction with Pusa Land Road to junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with D.B.Gupta
Road No.31 of the layout plan  11. Saraswati Marg  From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmal Khan Road  From junction with Tank Road to junction with Pusa Lane  From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land  From junction with Pusa Land  From junction with Pusa Land  Road to junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road  From junction with Bank Street Road to junction with Arya Samaj Road
11. Saraswati Marg From junction with D.B.Gupta Road to junction with Arya Samaj Road  12. Ajmai Khan Road From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  17. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road
Road to junction With Arya Samaj Road  12. Ajmal Khan Road  From junction with Pusa Lane  13. Gurudwara Road  From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land  From junction with Pusa Land  From junction with Pusa Land  Road to junction with Bank Street Road to junction with Arya Samaj Road  From junction with Bank Street Road to junction with Arya Samaj Road
Samaj Road  12. Ajmal Khan Road From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land From junction with Pusa Land Road to junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with D.B.Gupta
12. Ajmai Khan Road  From junction with Tank Road to junction with Pusa Lane  13. Gurudwara Road  From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land  From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road  From junction with Bank Street Road to junction with Arya Samaj Road
junction with Pusa Lane  13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land From junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road
13. Gurudwara Road From junction with D.B.Gupta Road to junction with Padam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road
Road to junction With Fadam Singh Road  14. Laxmi Dwar Marg From junction with Arya Samaj Road to junction with Pusa Land From junction with Bank Street Road to junction with Arya Samaj Road  15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  16. Abdul Aziz Road From junction with D.B.Gupta
Singh Road  14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land  From junction with Bank Street Road to junction with Arya Samaj Road  From junction with Arya Samaj Road  Samaj Road  From junction with D.B.Gupta
14. Laxmi Dwar Marg  From junction with Arya Samaj Road to junction with Pusa Land Road to junction with Bank Street Road to junction with Arya Samaj Road Samaj Road From junction with D.B.Gupta
Road to junction with Pusa Land  15. Abdul Aziz Road  From junction with Bank Street Road to junction with Arya Samaj Road  From junction with D.B.Gupta
15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road Samaj Road From junction with D.B.Gupta
15. Abdul Aziz Road From junction with Bank Street Road to junction with Arya Samaj Road  From junction with Bank Street Road to junction with D.B.Gupta
Road to junction with Arya Samaj Road  Samaj Road  D.B.Gupta
Samaj Road  Samaj Road  Westign with D.B.Gupta
inction with U.D. Gupta
16. Krishna Dass Road The junction with Arya
Road to junction with 7475
Campi Poad
1 1 / 1 Saturation
Girls School Marg Road to junction with room
(West Side)  From junction with New Rohtak  Road  From junction with D.B.
18 Joshi Road From Junction With D.B.
Road to Junction
Gupta Road
10 Abdul Rehman From junction with D.B.Gupta
119. Abdus
Road Samaj Road
-do-
20. Ilahi Baksh Marg  21. Faiz Road (West -do-
21. Faiz Road (West   Side)

4.	Zone - C:		
1.	Roshnara Road	1.00	
2.	G.T.Road	2.18	
_	Shakti Marg (Nagia Park round about)	0.32	
4.	1	0.15	
5.	Mandella Road	0.06	
6.		0.06	
٠.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0.00	

## Zone – D.:

Malka Ganj Road

- 1. Temple Road, Bhogal
- 2. Shahi Hospital Road, Bhogal
- 3. Central road, Bhogal
- 4. Masjid Road, Bhogal
- 5. Gurudwara Road, Lajpat Nagar-IV
- 6. New Delhi South Extn. Part-I Service Road along Ring Road.

0.88

- 7. Main Road (24 M wide) between blocks 'O' & 'K', Lajpat Nagar-II
- 8. Central Market & Lajpat Nagar-II
- 9. Alankar Cinema Road/Pushpa Market Road (Lajpat Nagar)
- 10. Bhisham Pitamah Road (Defence Colony)
- 11. In addition, shops, plots forming part of an approved layout of the competent authority.

## 6. Zone - E:

- 1. Shopping Centre, Krishna Nagar
- 2. Chhota Bazar, Shahdara
- 3. Main Gandhi Nagar Bazar
- 4. Bara Bazar, Shahdara .
- 5. Anaj Mandi, Shahdara
- 6. Shopping Area o Viswas Nagar
- 7. Shopping Area of Seelampur/ Salimpur
- 8. Farash Bazar, Shahdara

9. Railway Road,	
Shahdara 10, Main Road Gandhi Nagar	From Marginal Bandh to Jheel Bus Terminal
11. Main Vikas Marg	From Marginal Bandh to Patparganj Road
12. Vijay Chowk Road (Laxmi Nagar Main Road)	From Vikas Marg to Patparganj Road
13. Patparganj Road	From Jheel Bus Terminal to Madhuvan Railway Crossing excluding the GHBS and Rehabilitation Colonies
14. Road No.57	From GT Railway Line to Parwana Road excluding CGHS and facility centres
15. Bhola Nath Nagar Road	Ram School
16. Mandir Marg Road	From Raghunath Mandir to Road No.57
17. Road No.35A	From Vikas Marg to Mother Dairy excluding bridge area and Mother Dairy Plant
18. 60 ft. wide Road	From Teliwara to Babu Ram School
19. Proposed Master Plan Road No.67 in Maujpur area	
20. Loni Road	From G.T. Road to Road No.68
21. G.T. Road	From Radhu Cinema to Loni Road
22. Road No.66	From G.T. Road to Road No.68 on Western side only.
23. Brahmpuri Main Road	From Ghonda Chowk to New Seelampur Market, Road
24. Yamuna Vihar Road	From Ghonda Chowk to DTC Depot.
25. 60 ft wide road Balbir	From Eastern Yamuna

Nagar	(Babur	Pur	Canal	to G.T. Road	j
Road)					
26. 100 ft.	Road No.6	58	-	Eastern Y upto Railwa ng	
27. Wazirat				Marginal Yamuna	
			Schemonly)	ne (on Sout	th side
					•
Zone - F:					•

- New Delhi South Ext.Part-II(Portion fronting on Ring Road)
- Kalkaji Main Road (Between Block G&H and E&F). (b)
- Malviya Nagar (Main Market Road) (c)
- Road between Govindpuri and Govindpuri (d) extension
- Shop-plots, forming part of an approved layout . plan of the competent authority

#### Zone - G: 8.

- Main Najafgarh Road from Laxman Sylvania, New a) Moti Nagar Chowk to Outer Ring Road Crossing i.e. Ganesh Nagar
- Between Kirti Nagar Maya Puri Chowk to Kirti Nagar Patel Nagar Chowk
- Lajwanti Garden Chowk to Nangal Raya c)
- Subhash Nagar to Din Dayal Upadhyaya Hospital d)
- Tilak Nagar Chowk to Nangal Raya Flyover i.e. Jail e) Road
- f) H-Block, Bali Nagar Najafgarh Road to B-Block, Bali Nagar.

## Zone - H:

1.	Road No.43, Rani Bagh	200 ft.
2.	Main Bazar, Rishi Nagar	50 ft
3.	Main Bazar (Road Rani Bagh)	50 ft.
4.	Main Road, Raja Park	100 ft.
5.	Main Road, Shastri Nagar	200 ft.
6.	Main Road, Tri Nagar	50 ft.
7.	Road No.41, Rohini	45 mt.



No. K-20013/4/2006-DDVA Government of India Ministry of Urban Development (Delhi Division)

Nirman Bhawan, New Delhi-110 011 Dated the 24 August, 2006.

To

The Vice-Chairman, Delhi Development Authority, Vikas Sadan, INA Colony, New Delhi-110 023.

Sub: Amendment of the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981 - Disposal of Senior Secondary School sites.

LHP

Sir,

Please refer to DDA's letter dated 3.2.2006 enclosing therewith a copy of the resolution relating to Agenda Item No.10/2006 of the Authority meeting held on 19.1.2006 on the above mentioned subject.

The proposal contained in Item No.10/06 of the Authority meeting Sheld on 19.1.2006 has been approved by the Government and accordingly the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981 have been amended vide notification dated 19.4.2006. A copy of the said notification is also enclosed herewith.

Yours faithfully,

(Prem Kumar)

Under Secretary to the Govt. of India **2** # 2306 1478

Enci: As above.

## Copy to:

1. The Secretary (Education), GNCTD, Old Secretariat, Delhi-110 054.

2. The Director (Education), GNCTD, Old Secretariat, Delhi-110 054. A copy of resolution relating to Item No.10/2006 of the Authority meeting Marken, held on 19.1.2006 and Amendment Notification dated 19.4.2006 are

enclosed herewith for information.

DD (Jup. )

(Prem Kumar) **Under Secretary** 

# Hechan Usignalia The Gazette of India

असाधारण EXTRAORDINARY भाग II—खण्ड 3—उप-खण्ड (i) PART II—Section 3—Sub-section (i) प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 157]

No. 157]

मई दिल्ली, बुधवार, अप्रैल 19, 2006/चैत्र 29, 1928

NEW DELHI, WEDNESDAY, APRIL 19, 2006/CHAITRA 29, 1928

## शहरी विकास मंत्रालय

## अधिसूचना

नई दिल्ली, 19 अप्रैल, 2006

सा.का.नि. 220(अ).—केन्द्रीय सरकार, दिल्ली विकास अधिनियम, 1957 (1957 का 61) की धारा 22 की उप-धारा (3) के साथ पठित धारा 56 की उप-धारा (2) के खंड (अ) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए दिल्ली विकास प्राधिकरण से परामर्श के पश्चात् दिल्ली विकास प्राधिकरण (विकसित नजूल भूमि का व्ययन) नियम, 1981 का और संशोधन करने के लिए निम्नलिखित नियम बनाती है, अर्थात् :—

- 1. (1) इन नियमों का संक्षिप्त नाम दिल्ली विकास प्राधिकरण (विकसित नजूल भूमि का व्ययन) संशोधन नियम, 2006 है।
  - (2) ये राजपत्र में प्रकाशन की तारीख से प्रवृत्त होंगे।
- 2. विल्ली विकास प्राधिकरण (विकसित नजूल भूमि का व्ययन) नियम, 1981 (जिसे इसमें इसके पश्चात् उक्त नियम कहा गया है) के नियम 4 में:-
  - (i) उप-नियम(1) में "व्यक्ति निकायों " शब्दों के स्थान /पर "व्यक्ति-निकाय, फर्मी, कंपनियों " शब्द रखे जाएंगे।
  - (ii) उप-नियम(2) के स्थान पर निम्नलिखित उप-नियम रखा जाएगा, अर्थात्:-
    - "(2) प्राधिकरण योजनाओं के अनुरूप तथा इन नियमों के उपबंधों के अध्यधीन नजूल भूमि का व्ययन निम्नलिखित संस्थाओं को नीलामी द्वारा करेगा:-
      - (क) अस्पताल,
      - (ख) औषधालय (डिस्पेंसरी)
      - (ग) नर्सिंग होम
      - (घ) उच्चतर अथवा तकनीकी शिक्षा संस्थान,
      - (इ.) सामुदायिक हॉल,
      - (च) वलब,
      - (छ) विद्यालय,

परन्तु इस उप-नियम की कोई बात उक्त प्रयोजन के लिए केन्द्रीय सरकार, राज्य सरकार, संघ राज्य क्षेत्र और स्थानीय निकाय को भूमि के आवंटन को प्रभावित नहीं करेगी।"

- 3. ्रें उक्त नियमों के नियम 5 में;
  - (i) "प्राधिकरण" शब्द के स्थान पर " नियम 4 के उप-नियम (2)के उपबंधों के अध्यधीन प्राधिकरण " शब्द रखे जाएंगे;
  - (ii), स्पष्टीकरण को लोप किया जायेगा ।
- 4. उक्त नियमों में, नियम 8 के स्थान पर निम्नलिखित नियम रखा जाएगा, अर्थात्:-
  - "8. निमय 4 के उप नियम(2), नियम 5,6, और 7 में अन्यथा उपबंधित के सिवाय, किसी प्रयोजन के लिए नजूल भूमि का आवंटन ऐसे प्रीमियम के भुगतान पर किया जाएगा जितना कि इन नियमों के यथास्थिति अध्याय-3 या अध्याय-4, के उपबंधों के अनुसार या तो नीलामी द्वारा या निविदा द्वारा अवधारित किया जाए।"
- 5. उक्त नियमों के नियम 16 में, आरंभिक पैरा में "व्यक्ति जिनके अंतर्गत निम्नलिखित व्यक्ति प्रवर्ग" भी हैं, शब्दों के स्थान पर "व्यक्ति जिनके अन्तर्गत निम्नलिखित व्यक्ति प्रवर्ग भी हैं, कम्पनी और फर्म" शब्द रखे जाएगें।
- 6. उक्त नियमों के नियम 20 में, निम्निलिखित परन्तुक अंतःस्थापित किया जाएगा, अर्थात्ः-"परन्तु इस नियम की कोई बात नियम 4 के उपनियम(2) के उपबंधों को लागू नहीं होगी।"
- 7. उक्त नियमों के नियम 42 में निम्नलिखित परन्तुक अन्तःस्थापित किए जाएगें अर्थात्ः

"परन्तु इस नियम में किसी बात के होते हुए भी प्राधिकरण, रिहायशी प्रयोजन अथवा वाणिज्यिक प्रयोजन के लिए नीलामी अथवा निविदा के माध्यम से फ्रीहोल्ड आधार पर नजूल भूमि आबंटित कर सकता है।"

"यह और भी कि फ्रीहोल्ड आधार पर आबंटन के मामले में आबंटिती प्रारुप ख क में हस्तांतरण विलेख निष्पादित करेगा।"

8. उक्त नियमों में प्रारुप ख के पश्चात निम्नलिखित प्रारुप अंतःस्थापित किया जाएगा अर्थात्ः

# फार्म ख क (नियम ४२ देखें) हस्तांतरण विलेख

(नीलामी अथवा निविदा के जरिए फ्रीहोल्ड आधार पर आबंटित रिहायशी और वाणिज्यिक संपितियों के लिए)

यह हस्तांतरण विलेख एक पक्षधर के रूप में भारत के राष्ट्रपति, जिन्हें इसमें आगे विल्ली विकास प्राधिकरण, विकास सदन, नई दिल्ली के जरिए विक्रेता कहा गया है (इसके अन्तर्गत उनके उत्तरवर्ती तथा समनुदेशिती भी हैं, जब तक कि संदर्भ में अन्य तथा भिन्न अर्थ अपेक्षित न हो)और करे
जिल्ला का अर्थ विसार के
न जिल्ला सम्बद्धाराता भी शामिल
***************************************
तारीखके अधीन रुपएका प्रतिफल लेकर क्रेता को आबंदित किया गया था जो कि उक्त आबंदन पत्र में उल्लिखित सीमान निबंधनों और शर्तों के अध्यधी प्राप्त किया गया है
संपत्ति, जिसका वास्तविक कब्जा उन्हें तारीखको सौंपा गया था, में फ्रीहोल्ड स्वामित्व अधिकारों के लिए अंतरण विलेख निष्पादित करने हेतु आवेदन किया है तथा उसमें आगे दी गई शर्ती व
मेंरा० इस बात का साक्षी है कि आवंटन के समय संदत्तरा०(शब्दों मेंरा०(शब्दों प्राप्ति विक्रेता इसके द्वारा स्वीकार और अभिस्वीकार करता है) के प्रित फलस्वरुप, पूर्वोक्त विलेख और यहां इसमें आगे उल्लिखित सीमाओं के अध्यधीन विक्रेता द्वारा आवासीय योजना के प्लाट सं०में उक्त क्रेता फ्रीहोल्ड स्वामित्व के लिए अनुदत्त हस्तांतरण, विक्रय, निर्मोचन और अंतरण, समनुदेशन तथा आश्वासन पूर्वोक्त क्रेता को करता है।
1. विक्रेता उक्त संपत्ति में या उसके अन्तर्गत सभी खानों और खनिज पदार्थों को, चाहे वे किसी भी स्वरूप के हों, अपने पास सुरक्षित/रखेगा और इसके साथ-साथ विक्रेता उसके अभिकर्ताओं और कर्मकारों को यह पूर्ण स्वतंत्रा होगी कि वे उक्त संपत्ति के किसी भाग में या सभी जगह तलाशी लेने के लिए, उसे पाने के लिए, विक्रय योग्य बनाने के लिए, उस समस्त संपत्ति या उसके किसी भाग में किसी भी समय प्रवेश कर सकें और उक्त संपत्ति के अन्तर्गत या उस पर या विक्रेता की भूमि से संलग्न किसी भूमि पर उक्त खानों और खनिज पदार्थों को ले जा सकें तथा उक्त समस्त संपत्ति या उसके किसी भाग की सतृह का और उस संपत्ति के अंतर्गत आने वाले किन्ही भवनों या उस पर इसके बाद बनाए जाने वाले भवनों का

निर्धारण कर सकें ताकि आदेशानुसार उसकी ओर से किए गए नुकसान के लिए क्रेता को उचित मुआवजा दिया जा सके बशर्ते उक्त संपत्ति के संबंध में भू-राजस्व या देय अन्य करों का भुगतान कर दिया गया हो, जो विधिपूर्ण रूप से उक्त संपत्ति के संबंध में देय हो या देय हो सकते हों, और सभी सार्वजनिक अधिकार या उससे प्रभावित होने वाले भोगाधिकार भी दे दिए गए हों।

- संपत्ति के इस विलेख के पूरा होते हुए भी, मास्टर प्लान/जोनल विकास प्लान/ले-आउट प्लान के उपबंधों के उल्लंघन की किसी भी प्रकार से अनदेखी नहीं की जाएगी तथा दिल्ली विकास प्राधिकरण को दिल्ली विकास अधिनियम की धारा-14 या तत्समय प्रवर्त किसी अन्य विधि के उल्लंघन के संबंध में समुचित कार्रवाई करने का अधिकार होगा ।
- क्रेता भवन, जल-निकास संबंधी तथा समुचित नगरपालिका या तत्समय प्रवर्त अन्य प्राधिकरणों के उप-नियमों का अनुपालन करेगा।
- उक्त प्लाट का आवंटन 'यथावत' आधार पर किया जाता है तथा क्रेता द्वारा इस प्लाट में अथवा उसके आसपास कोई परिवर्तन/परिवर्द्धन/अतिक्रमण/अवैध निर्माण विक्रेता(डीडीए) की लिखित अनुमित के बिना नहीं किया जा सकता जो इस आवेदन को अस्वीकार कर सकते हैं अथवा कुछ शर्तों व निबंधनों के अध्यधीन मंजूर भी कर सकते हैं।

सभी प्रकार के शुल्क, कर, प्रभार, निर्धारण, नगरपालिका अथवा अन्यथा और किसी भी प्रकार के प्रभार को आवंटिती/क्रेता द्वारा वहन किया जाएगा।

- यदि किसी भी समय यह पाया जाता है कि इस विलेख को किसी तथ्य को छिपाकर या गलत और गुमराह करने वाले ब्यौरे देकर या कपटपूर्ण तरीके से प्राप्त किया गया है तो विक्रेता की ओर से यह विलेख अमान्य हो जाएगा तथा विक्रेता को इस विलेख को रद्द करने तथा क्रेता द्वारा अदा की गई राशि को जब्द करने का अधिकार होगा । इस संबंध में विक्रेता का विनिष्चय अंतिम तथा क्रेता के लिए बाध्यकारी होगा और किसी भी स्थिति में उसे वापस नहीं लिया जाएगा।
- क्रेता द्वारा आवंटन/नीलामी/निविदा की शर्तों व निबंधनों का अनुपालन किया जाएगा । 6.
- विक्रेता को आवंटन/नीलामी/निविदा अथवा इस विलेख की शर्तों का उल्लंघन होने की स्थिति में इस विलेख को रद्द करने का अधिकार होगा।
- इस लिखत के संबंध में स्टाम्प डूयूटी तथा रजिस्टरीकरण प्रभार क़ेता द्वारा वहन किए जाएंगे । 8,
- यह हस्तांतरण इस विलेख के रजिस्टरीकरण की तारीख से प्रवृत्त माना जाएगा।

# MINISTRY OF URBAN DEVELOPMENT NOTIFICATION

New Delhi, the 19th April, 2006

G.S.R. 220(E).— In exercise of the powers conferred by clause (j) of subsection (2) of section 56, read with sub-section (3) of section 22 of the Delhi Development Act, 1957 (61 of 1957), the Central Government, after consultation with the Delhi Development Authority, hereby makes the following rules further to amend the Delhi Development Authority (Disposal of Development Nazul Land) Rules, 1981, namely:-

- (1) These rules may be called the Delhi Development Authority (Disposal of Developed Nazul Land) Amendment Rules, 2006.
  - (2) They shall come into force on the date of their publication in the Official Gazette.
- 2. In the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981 (hereinafter referred to as the said rules), in rule 4, -
  - (i) in sub-rule 1, for the words "body of persons", the words "body of persons, firms, companies," shall be substituted;
  - (ii) for sub-rule (2), the following sub-rule shall be substituted, namely:-
  - "(2) The Authority shall, in conformity with plans and subject to the provisions of these rules, dispose the Nazul land by auction to the following institutions:
    - a) hospitals;
    - b) dispensaries;
    - c) nursing homes;

[फा. सं. के-20013/4/2006/डीडीवीए] पी. के. प्रधान, संयुक्त सचिव

टिप्पण:- मूल नियम सं.सा.का-नि. तारीख 26 सितंबर, 1981 द्वारा प्रकाशित किए गए थे और पश्चातवर्ती संशोधन सं0(1) सा.का-नि. 97 तारीख 27 जनवरी, 1989(2)सा.का.नि. 677(अ) तारीख 11 नवम्बर, 1991(3) सा.का.नि. 486(अ) तारीख 5 जुलाई, 2002(4) सा.का.नि. 806(अ) तारीख 3 दिसम्बर, 2002 और(5) सा.का.नि. 801(अ) तारीख 9 दिसम्बर, 2004 द्वारा किए गए।

श्री/श्रीमती....

श्री/श्रीमती....

- d) higher or technical education institutions;
- e) community halls;
- f) clubs;
- g) schools:

Provided that nothing in this sub-rule shall affect the allotment of land to the Central Government, a State Government, a Union territory and the local body for the said purpose."

- 3. In the said rules, in rule 5, -
  - (i) for the words "The Authority may", the words "Subject to the provisions of sub-rule (2) of rule 4, the Authority may" shall be substituted;
  - (ii) the Explanation shall be omitted.
- 4. In the said rules, for rule 8, the following rule shall be substituted, namely:-
  - "8. Save as otherwise provided in sub-rule (2) of rule 4, rules 5, 6 and 7, allotment of Nazul land for any purpose shall be made on payment of such premium as may be determined either by auction or by tender in accordance with the provisions of Chapter III or Chapter IV, as the case may be, of these rules.".
- 5. In the said rules, in rule 16, in the opening paragraph, for the words "individuals, including the following categories of individuals", the words "individuals including the following categories of individuals, companies and firms" shall be substituted.
- 6. In the said rules, in rule 20, the following proviso shall be inserted, a namely:-

"Provided that nothing in this rule shall apply to the provisions of sub-rule (2) of rule 4.".

7. In the said rules, in rule 42, the following provisions shall be inserted, namely:-

"Provided that notwithstanding anything contained in this rule, the Authority may allot Nazul land on free hold basis either through auction or by tender for residential purpose or commercial purpose:

Provided further that in the case of allotment on free hold basis, the allottee shall execute a conveyance deed in Form BA.".

8. In the said rules, after Form B, the following form shall be inserted, namely:-

## FORM BA

(See rule 42)

## **CONVEYANCE DEED**

(For Residential and Commercial Properties allotted on Freehold basis through Auction or Tender)

This deed of convey	ance made on	this		******************	day
of	between Pres	ident of Ir	ndia, her	einafter calle	d "THE
VENDER" through DD	A, Vikas Sadan,	Nèw Delhi (	which ex	pression sha	ll unless
excluded by or repugn	ant to the contex	t be deeme	d to inclu	ide his succe	ssors in
office and	assigns)of	the	one	part ·	and
Shri/Smt/M/S					
••••••••••					
expression shall unles					
include his/her heirs,	administrators, re	epresentativ	es and p	permitted ass	signs) of
the other part.					
WHEREAS				,	
situated in	**************			was allotted	to the
purchaser by Delhi De	evelopment Author	prity vide all	lotment le	etter No.F	.( )./

......(Rupees......) which has been received subject to limitation, terms and conditions mentioned in the said letter of

- 1. The Vendor excepts and reserves unto himself all mines and minerals of whatever nature lying in or under the said property together with full liberty at all property together to search for, win, make merchantable and carry away the said mines, and minerals under or upon the said property or any adjoining lands of the vendor and to lay-down the surface of all or any part of the said property and said property and compensation to the purchaser for damage done unto him thereby, subject to the payment of land revenue or other imposition payable or which may become lawfully payable in respect of the said property and to all public rights or a said property and to all property and to all property and to all property and
- 2. That notwithstanding execution of this Deed, use of the property in contravention of the provisions of Master Plan/Zonal Development Plan/Layout Development Authority shall be entitled to take appropriate action for time being in force.
- 3. The purchaser shall comply with the building, drainage and other byelaws of the appropriate Municipal or other authorities for the time being in force.
- 4. The said plot is allotted on the basis of 'as is' and the purchaser cannot make any alteration/addition/encroachment/unauthorized construction in or'

(VENDOR)

around the same without written permission of Vendor (DDA) who may refuse or grant the same subject to such terms and conditions as deems proper.

All fees, taxes, charges, assessments, Municipal or otherwise and other levies of whatsoever nature shall be born by the allottee/purchaser.

- 5. If it is discovered at any stage that the allotment or this deed has been obtained by suppression of any fact or by any misstatement, misrepresentation or fraud, then this deed shall become void at the option of the vendor, which shall have the right to cancel this deed and forfeit the consideration paid by the purchaser. The decision of the vendor in this regard shall be final and binding upon the purchaser and shall not be called in question in any proceedings.
- 6. That the purchaser shall abide by the terms and conditions of allotment/auction/tender, which shall be treated as a part of these presents.
- 7. That the vendor reserves the right to cancel this deed in event of breach of conditions of allotment/auction/tender and of this deed.
- 8. The stamp duty and registration charges upon this instrument shall be borne by the purchaser.

This transfer shall be deemed to have come into force with effect from the date of registration of the deed.

ln	witness	where	of	Shri/Smt			
set his/he	For and on behalf of and by the order and direction of the Vendor has hereunto set his/her hand Shri/Smt / м/s the purchaser, the hereunto set his/her hand day and year first above written.						
	THIS SC	IEDULE ABOVE REF	ERRED TO				
	of	sq.mtrs (Couryard					
NORTH EAST SOUTH WEST							
Signed by	Shri/Smt						
for and or	behalf of and by	the order and dire		resident of India			

ы <u>п — а</u> (-а 2(1) ]	भारत का राजपत्र : असाधारण	• • •
In the presence of: (1)Shri/Smt	***************************************	
Signed by Shri/Smt		
•		( PURCHASER)
In the presence of: (1)Shri/Smt(2)Shri/Smt	***************************************	· :

[F. No. K-20013/4/2006/DDVA]
P. K. PRADHAN, Jt. Secy.

Note: The principal rules were published vide number G.S.R 872, dated the 26<sup>th</sup> September, 1981 and subsequently amended vide number (1) G.S.R. 97, dated the 27<sup>th</sup> January, 1989, (2) G.S.R. 677 (E), dated the 11<sup>th</sup> November, 1991, (3) G.S.R. 486(E), dated the 5<sup>th</sup> July, 2002, (4) G.S.R. 806 (E), dated the 3<sup>rd</sup> December, 2002, and (5) G.S.R. 801 (E), dated the 9<sup>th</sup> December, 2004.

अनुलग्नक ख

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना 🗔

नई दिल्ली, 31 मई, 2005

का. आ. 741(अ).—यतः दिल्ली मास्टर प्लान, 2001 में निम्नलिखित संशोधन, जिन्हें केंद्र सरकार द्वारा करने का प्रस्ताव है, दिल्ली विकास अधिनियम, 1956 (1957 का 61) की धारा 44 के प्रावधानों के अनुसरण में दिनांक 4 नवंबर, 2004 की असाधारण राजपत्र अधिसूचना सं. का.आ. 1246(अ) द्वारा सार्वजनिक सूचना के रूप में प्रकाशित किए गए थे और उक्त अधिनियम की धारा 11-क की उप-धारा (3) द्वारा यथापेक्षित आपत्तियां/सुझाव उक्त सूचना की नाराख से 30 दिन के अंदर आमंत्रित किए गए थे।

- 2. यतः प्रस्तावित संशोधन के बारे में 710 आपितयां/सुझाव प्राप्त हुए थे और इन आपित्तयों तथा सुझावों पर विचार करके अपनी सिफारिशें प्रस्तुत करने हेतु आयुक्त (आयोजना), दिल्ली विकास प्राधिकरण की अध्यक्षता में एक सिमिति का गठन किया गया था। केन्द्र सरकार ने सिमिति की सिफरिशों पर ध्यानपूर्वक विचार करने के बाद दिल्ली मास्टर प्लान, 2001 को संशोधित करने का निर्णय किया है।
- 3. अत:, अव, केंद्र सरकार उक्त अधिनियम की धारा 11-क की उप-धारा (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से दिल्ली के उक्त मास्टर प्लान, 2001 में निम्नलिखित संशोधन करती है:— उपांतरण

दिनांक 1-8-90 के भारत के राजपत्र (असाधारण) में पृष्ठ सं. 125 (दिल्ली मास्टर प्लान, 2001) की बायों तरफ (3) 'समयपुर बादली-विस्तृत औद्योगिक क्षेत्र' के बाद निम्नलिखित को जोड़ने का प्रस्ताव है :-

'न्यूनतम 4 हेक्टे. सतत क्षेत्र वाले औद्योगिक संकेन्द्रण वाले ऐसे गैर-नियोजित समूहों, जिनमें 70% से अधिक प्लाट निर्माण गतिविधि/उपयोग वाले हो, उन पर सर्वेक्षण के आधार पर तथा राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार के उद्योग विभाग द्वारा अधिसूचना जारी करके पुनर्विकास के लिए विचार किया जा सकता है। पुनर्विकास योजना संबंधित स्थानीय निकायों/डीडीए अथवा सोसायटी (स्वामियों द्वारा बनाई जाने वाली), द्वारा दिल्ली नगर निगम/दिल्ली विकास प्राधिकरण के अनुमोदन से बनाई जाएगी बशर्ते पर्यावरण तथा अन्य सक्षम एजेंसियों की कानूनी मंजूरी ली गई हो और वह निम्नलिखित मानदण्डों/शर्तो पर आधारित हो।

- (i) समूहों में कम से कम 18 मीटर मार्गाधिकार वाली सड़क से सीधा पहुंचा जा सकेगा।
- (ii) पुनर्विकास योजना, प्रदूषण नियंत्रण तथा पर्यावरण प्रवंधन, सेवाओं और पाकिंग का विकास तथा रखरखाव के लिए सोसाइटी द्वारा मदद करना अनिवार्य होगा।

- (iii) केवल अनुमंय उद्योगों, जिन्हें डीपीसीसी से स्वीकृति प्रदान की गई है, को ही अनुमति दी जायेगी।
- (iv) ग्राउंड फ्लोर एरिया पर ही औद्योगिक कार्यकलाचें की अनुमति दी जाएगी। औद्योगिक प्रयोजनों तथा फ्लैट उद्योगों के लिए प्लाटों के और विभाजन अथवा एकीकरण करने की अनुमति नहीं दी जाएगी।
- (v) सभी इकाइयों के डीपीसीसी तथा स्थानीय निकायों सिंहत कानूनी अनुमोदन लेना होगा। औद्योगिक इकाइयों के विजली के कनेक्शन भी अलग होंगे।
- (vi) अन्य शतों में निम्नलिखित शामिल होंगे :--
  - न्यूनतम 10% क्षेत्र परिभ्रमण/सङ्कों/सर्विस लेन के लिए आरक्षित किया जाना है।
  - 100 वर्ग मीटर से क्रम आकार के भूखण्डों मं न्यूनतम 7.5 मीटर मार्गाधिकार होगा।
  - 100 वर्ग मोटर से अधिक आकार के पूखण्डों में
     न्यूनतम 9.0 मीटर मार्गाधिकार होगा।
  - पार्किंग तथा लोडिंग/अनलोडिंग क्षेत्रों के लिए न्यूनतम
     10% अई-पारगम्य सतह।
  - \* 60 वर्ग मीटर से कम के भूखण्डों के लिए सांझा पार्किंग उपलब्ध करावी जानी है जबिक 60 वर्ग मीटर से अधिक के भूखण्डों के लिए पार्किंग तथा लोडिंग और अनलोडिंग हेतु बिना चारिदवारी के फ्रन्ट सेट बेक (न्यूनतम 3 मी.) उपलब्ध करावा
  - सीईटीपी, सब-स्टेशनों, पम्प हाउस, फायर स्टेशन, पुलिस चौकी आदि जैसी अवस्थापना आवश्यकताओं के लिए मानदण्डों के अनुसार कुल क्षेत्र का न्यूनतम 10% क्षेत्र आरक्षित किया जाना है।
  - मिप्नलिखित को तैयार करना :(क) पिप्पंग स्टेशनों, भंडारण टैंकों, भूजल
    पुनर्भरण/वर्षा जल संग्रहण करने को जरूरतों सहित
    दिल्ली जल बोर्ड/केन्द्रीय भूजल प्राधिकरण
    (अपेक्षानुसार) से जल आपूर्ति के लिए योजना।
    (ख) मानदण्डों के अनुसार जल निकासी योजना।
  - (vii) पार्को/ग्रीन बफर के लिए समूह क्षेत्र का 8% क्षेत्र आरक्षित किया जायेगा।
  - (viii) अन्य प्रावधान/विकास नियंत्रण मानदण्ड इत्यादि दिल्ली मास्टर प्लान, 2001 के प्रावधानों के अनुसार लागू होंगे।

भू-स्थितियों के आधार पर डीडीए की तकनीकी समिति मानकों में 10 प्रतिशत तक की छूट दे सकती है।

निम्नलिखित क्षेत्र पुनर्विकास स्कीम के लिए पात्र नहीं होंगे :— बंगला जोन (नई दिल्ली और सिविल लाइन्स), रिज क्षेत्र, नदी तल (जोन ओ), जलाशयों, नहरों के पास के क्षेत्र, सुरक्षा की दृष्टि से संवेदनशील क्षेत्र, संरक्षण तथा हरिटेज क्षेत्र, आरक्षित/संरक्षित जंगल, दिल्ली विकास प्राधिकरण पत्नैद्स, निजी सहकारी सगृह आतास सोसाइटियां; सरकारी फ्लैट/बंगले/नियोजक आवास आदि तथा उनके आसपास के क्षेत्र ।

पुनर्विकास का कार्य सोसाइटियों द्वारा अपने खर्च पर अथवा संबंधित एजेंसियां द्वारा किया जाएगा। यदि एजेंसियां पुनर्विकास कार्य का निष्पादन करती हैं तो वे अलग-अलग उद्योगों से सीधे प्रभार वसूलंगी। भूमि उपयोग में परिवर्तन करने, फर्सी क्षेत्रफल अनुपात (एफएआर) और भूमि लागत में वृद्धि (जहाँ भी लागू हो) संबंधी भगतान संबंधित प्राधिकरण को किया जाना अपेक्षित होगा।

पुनर्विकास का कार्य दिल्ली विकास प्राधिकरण/स्थानीय निकाय

तारा इसके लिए निर्धारित गमय सीमा के भीतर पूग किया जाग चाहिए। जो समूह यथा-निर्दिष्ट अवधि में पुनर्विकास का कार्य पूरा गहीं करेंगे, उन्हें अन्य निर्योजित औद्योगिक क्षेत्रों में पुनर्स्थापित होना होगा और गैर-नियोजित समूहों में चलाए जा रहे यूनिट बंद कर दिए जाएंगे। ऐसे मामलों में, लाइसेंस प्राधिकरण सक्षम प्राधिकारियों से भू-उपयोग संबंधी अनुमति प्राप्त किए बिना औद्योगिक यूनिटों के लाइसेंस का नवीनीकरण/उन्हें लाइसेंस जारी नहीं करेंगे। इसके अलावा, भू-उपयोग संबंधी अनुमति प्राप्त किए बिना गैर नियोजित क्षेत्रों में कोई नया लाइसेंस जारी नहीं किया जाएगा।

> [सं. के~13011/5/2000-डोडीआईबी] एस. मुखर्जी, अवर सचिव

## INDUSTRIES DEPARTMENT

### NOTIFICATION

Delhi, the 30th June, 2006

No. F-1/C. L/Policy/INSITU/Jawahar Nagar/2006/018/616.—Whereas the Central Government, in exercise of the powers conferred by sub-section (2) of Section 11-A of the Delhi Development Act, 1956 (61 of 1957), has, vide Ministry of Urban Development (Delhi Division), Government of India's Notification S. O. 741 (E) dated the 31st May, 2005 published in the Gazette of India: Extraordinary made modification in the Master Plan for Delhi 2001;

And whereas the said notification provides that clusters that could be considered for re-development should have---

- (a) Minimum contiguous area of 4 Ha, and
- (b) More than 70% of the plots within the area (Industrial cluster) should be under manufacturing activity/use only;

And whereas on the basis of survey conducted by DSIDC and further verified by the Sub-Divisional Magistrate Seelam Pur, the Industrial Cluster located at Jawahar Nagar (layout plan enclosed as Annexure-A) and bounded as follows is to be considered for redevelopment in terms of the said notification dated 31st May 2005.

## A. Boundaries:

East: Balraj Nagar

West: Tunda Nagar

North: Ram Vihar


South: Jauhari Puri

Now, therefore, the manufacturing units within the aforesaid area (industrial cluster) are hereby required to form the society of the industry owners within a period of 90 days from the date of issue of this notification and that such society shall take further steps for preparation of re-development plan for the approval of the local body/DDA subject to other statutory environment clearance and clearance from all others as per the terms and conditions of the said Notification dated 31st May, 2005 within a period of 180 days thereafter, under intimation to be undersigned.

All manufacturing units which have availed of any allotment of plot under the scheme of relocation of industries shall have to surrender such plots allotted to them faliling which the manufacturing unit in the aforesaid cluster shall be liable for closure and the plot that would become available as a result of closure of the unit shall be put for such use that may be assigned to that plot under the re-development scheme and also disposal by the Government of NCT of Delhi.

A copy of Govt. on India, Ministry of Urban Development Notification dated the 31st May, 2005 referred to above is Annexure-B to this notification for ready reference.

S. C. PODDAR, Secy. and Commissioner (Industries)



## ANNEXURE-B

## MINISTRY OF URBAN DEVELOPMENT

## (DELHI DIVISION)

## NOTIFICATION

New Delhi, the 31st May, 2005

S.O. 741(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2001 mentioned hereunder were published as Public Notice vide Extraordinary Gazette Notification No. S. O. 1246(E) on 4th November, 2004 in accordance with the provisions of Section 44 of the Delhi Development Act, 1956 (61 of 1957) inviting objections/suggestions as required by Sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.

- 2. Whereas 710 objections/suggestions were received with regard to the proposed modification and a Committee constituted under the Chairmanship of Commissioner (Planning), Delhi Development Authority to consider the objections and suggestions gave its recommendations. The Central Government have, after carefully considering the recommendations of the Committee, decided to modify the Master Plan for Delhi-2001.
- 3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi-2001 with effect from the date of publication of this Notification in the Gazette of India.

## MODIFICATION:

The following shall be added after (3) 'Shamapur Badli—Extensive Industrial Area' on left hand side of page-125 of Gazette of India (Extraordinary) dated 1-8-90 (Master Plan for Delhi-2001).

"Non-conforming clusters of industrial concentration of minimum 4 Ha. contiguous area, having more than 70% plots within cluster under manufacturing activity/use may be considered for redevelopment on the basis of surveys and issue of notification by the Industry Department of Government of National Capital Territory of Delhi. The redevelopment scheme shall be prepared by the concerned local bodies/DDA or by the society of the industries owners with the approval of MCD/DDA subject to statutory environmental clearance and clearance from other competent agencies and based on the following norms and conditions:

- (i) The cluster should have direct approach from a road of at least 18 mtrs. ROW.
- (ii) Formation of Society shall be mandatory to facilitate preparation of redevelopment plan pollution control and environmental management development of services and parking and maintenance.

- (iii) Only permissible industries having clearance from DPCC shall be permitted.
- (iv) Industrial activity shall be permitted only in the ground floor area. Further sub-division or amalgamation of the plots for industrial purposes and flatted industries shall not be permissible.
- (v) All the units shall have to obtain the statutory clearances including clearances from DPCC and local bodies. The industrial units shall also have separate electrical connections.
- (vi) Other stipulations shall include-
  - \* Minimum 10% areas is to be reserved for circulation/roads/service lanes.
  - Plots measuring less than 100 sqm. to have minimum 7.5 mtrs. ROW.
  - Plots measuring more than 100 sqm. to have minimum 9.0 mtrs. ROW.
  - \* Minimum 10% of semi-permeable surface in each plot for parking and loading/unloading areas.
  - \* Common parking to be provided for plots below 60 sqm., whereas for plots above 60 sqm. front set back (min. 3m) shall be provided without boundary wall for parking and loading and unloanding.
  - \* Minimum 10% of total area to be reserved for infrastructure requirements like CETP. Sub-stations. Pump House, Fire Station, Police Post, etc. as per the norms.
  - \* Preparation of:
  - (a) Plan for water supply from DJB/Central Ground Water Authority (wherever required) along with requirement for pumping stations, storage tanks, ground water recharging/rainwater harvesting.
  - (b) Drainage plan as per norms.
  - (vii) 8% of the cluster area shall be reserved for parks/green buffer.
  - (viii) Other provisions/development control norms etc. shall be applicable as per provisions of MPD 2001.

Depending upon ground conditions, the Technical Committee of DDA may relax the norms upto 10%.

The following areas shall not be eligible for redevelopment scheme:—

Bungalow Zones (New Delhi and Civil Lines), the Ridge, River Bed (Zone-O), areas along water bodies, canals, sensitive areas from security point of view, conservation and heritage areas, reserved/protected forests, DDA flats, private cooperative group housing societies,

Government flats/bungalows/Employer housing etc. and their immediate proximity.

The redevelopment work may be undertaken by the societies at their own cost or by the concerned agencies. In case the agencies take up the redevelopment work for execution they shall collect the charges from the individual industries themselves directly. Requisite charges of change of land use, enhanced FAR and land (wherever applicable) would be required to be paid to the concerned Authority.

The redevelopment shall be completed within the period specified by the Delhi Development Authority,

Local Bodies in this regard. Clusters which fail to complete the redevelopment proposals within the period specificu as above, shall have to shift to other conforming industrial areas and the units functioning in non-conforming clusters shall have to close down. In such cases, the licensing authority will not renewissue the licenses to industrial units without obtaining land use clearance from the competent authority. Further no new licenses will be issued in non-conforming areas, without obtaining land use clearance."

[No. K-13011/5/2000-DDIB] S. MUKHERJEE, Under Secy.

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054

## No. K- 13011/9/2006-DDIB Government of India Ministry of Urban Development (Delhi Division IB)

Nirman Bhavan, New Delhi Dated the 3 Oct. 2006.

Subject:

Extraordinary Gazette Notification regarding Development Control Norms for residential plotted development.

A copy of Notifications dated 022.9.06 published in the Gazette of India Extraordinary on the subject cited above are sent herewith for information and necessary action.

Copy to:

(S.Mukheriee) Under Secretary to the Government of India

Telfax. No. 23061681

Jalyo

1. The Vice-Chairman, DDA, Vikas Sadan, New Delhi.

2: The Director General, CPWD (Works), Nirman Bhawan, N.Delhi.

3 The Chairperson, NDMC, Palika Kendra, New Delhi.

4 The Commissioner, MCD, Town Hall, Delhi.

The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi.

6. The Commissioner (Planning), DDA, Vikas Minar, ITO, New Delhi.

7. The Principal Secretary, (UD), Government of NCT Delhi, O Wing, Delhi Secretariat, IP Estate, New Delhi.

8. The Chief Planner, TCPO, IP Estate, New Delhi.

PC-Sery Com(119)



असाधारण EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 1115] No. 1115] नई दिल्ली, शुक्रवार, सितम्बर 22, 2006/भाद्र 31, 1928 NEW DELHI, FRIDAY, SEPTEMBER 22, 2006/BHADRA 31, 1928

> शहरी विकास मंत्रालय (दिल्ली प्रभाग)

> > अधिसूचना

नई दिल्ली, 22 सितम्बर, 2006

का.आ. 1591(अ).—यत: दिल्ली मास्टर प्लान-2001 में केन्द्र सरकार का जिन कुछ संशोधनों को करने का प्रस्ताव था उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) की धारा 44 के प्रावधानों के अनुसार दिनांक 21 जुलाई, 2006 के सं. का.आ. 1160(अ) के तहत सार्वजिनक सूचना के रूप में भारत के राजपत्र, असाधारण में प्रकाशित किया गया था जिसमें उक्त अधिनियम की धारा 11-क की उप-धारा (3) के तहत यथा अपेक्षित उक्त नोटिस की तारीख के तीस दिन के भीतर आपत्तियां और सुझाव आमंत्रित किए गए थे;

- 2. यतः प्रस्तावित संशोधनों के बारे में प्राप्त आपित्तयों और सुझावों पर दिल्ली विकास प्राधिकरण द्वारा संगत नियमों के तहताविधिवत गठित जांच बोर्ड द्वारा विचार किया गया था और प्राधिकरण ने उक्त बोर्ड की रिपोर्ट पर विचार करने के पश्चात, दिल्ली मास्टर प्लान 2001 में, उक्त सार्वजनिक सूचना में यथा उल्लिखित संशोधन की, कुछ परिवर्तनों के साथ सिफारिश की है;
- 3. और यतः केन्द्र सरकार ने मामले के सभी संगत पहलुओं पर ध्यानपूर्वक विचार करने के पश्चात दिल्ली मास्टर प्लान 2001 को संशोधित करने का निर्णय लिया है ;
- 4. अतः अब उक्त अधिनियम की धारा 11-क की उपधारा (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए केन्द्र सरकार, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से उक्त दिल्ली मास्टर प्लान 2001 में एतद्द्वारा निम्निलिखित संशोधन करती है:-

(1)

2997 GI/2006

# संशोधन:

दिनांक 23 जुलाई, 1998 के भारत की राजपत्र अधिसूचना के द्वारा यथा संशोधित दिनांक 1 अगस्त, 1990 के भारत के राजपत्र के अग्रेंजी पाठ के पृष्ठ 159 पर (दायीं तरफ), दिनांक 23 जुलाई, 1998 की उक्त अधिसूचना में निर्धारित मानदण्डों के संशोधन में रिहायशी भूखण्ड विकास(001) के संबंध में निम्नलिखित विकास मानदण्डों को प्रतिस्थिपत किया जाएगा और ये निम्नलिखित निबंधनों और शर्तों के अध्यधीन होगें :-

# रिहायशी भूखण्ड विकास(001)

क्र0सं0	भूखण्ड का क्षेत्रफल(वर्ग मीटर)	अधिकतम भूमि	अधिकतम तल	अधिकतम ऊँचाई
1	(1)	कवरेज %	क्षेत्र अनुपात	मीटर में
			(एफएआर)	
1	32 से कम	90(2)	350	15
2	32 से अधिक 50 तक	90(2)	350	15
3	50 से अधिक 100 तक	90(2)	350	15
4	100 से अधिक 250 तक	75(3)	300(3)	15
5	250 से अधिक 500 तक	75	225	15
6	500 से अधिक 1000 तक	50	150	15
7	1000 से अधिक 1500 तक	40	120	15
8	१५०० से अधिक २२५० तक	40	120	15
9	2250 से अधिक 3000 तक	40	120	15
10	3000 से अधिक 3750 तक	40	120	15 .
11	3750 से अधिक	40	120	15

## ं नोट:

- 1. क्षेत्र को वर्ग गज से वर्ग मीटर में परिवर्तित करने से उत्पन्न भूखण्ड आकार में 2% तक की विभिन्नता की अनदेखी करने तथा नीचे दिए गए पैरा (ii) के अनुसार भूखण्ड आकार की निम्नतर श्रेणी के लिए लागू मानदण्डों की अनुमित प्रदान करने हेतु संबंधित स्थानीय निकाय सक्षम होगा।
- 2. इस अधिसूचना में विए गए प्रभारों का भुगतान करने पर इस अधिसूचना की तारीख को पहले से यथा मौजूद निर्माण के नियमितिकरण के लिए 100% भूमि कवरेज किया जा सकता है।
- 3. 100 से 175 वर्ग मीटर तक के आकार के भूखण्ड के संबंध में इस अधिसूचना में दिये गए प्रभारों का भुगतान करने पर इस अधिसूचना की तारीख को यथा मौजूद निर्माण के नियमितीकरण के लिए 100 प्रतिशत तल कवरेज और 350 तल क्षेत्र अनुपात पात्र होगा ।

# शर्तें और निबंधन

[भाग II—खण्ड 3(ii)

- जब तक स्थानीय निकाय द्वारा अवस्थापना और सेवाओं को बढ़ाया नहीं जाता तथा क्षेत्र की ले-आउट योजना और सेवा योजना का तदनुसार उचयन नहीं किया जाता, तब तक दिनांक 15 मई, 1995 की अधिसूचना के अन्तर्गत अनुमेय रिहायशी इकाइयों से अधिक (i) किसी अतिरिक्त रिहायशी इकाई की अनुमित नहीं दी जायेगी । इसलिए, आवेदक, भूखण्ड स्वामी/आवंटी को इस आंशय की वचनबद्धता देनी होगी कि दिनांक 15 मई, 1995 की अधिसूचना के तहत अनुमेय रिहायशी इकाई से अधिक कोई अतिरिक्त रिहायशी इकाई स्जित नहीं की गई है अथवा स्जित की जानी है।
- किसी श्रेणी के किसी भी भूखंड में अनुमेय कुल कवरेज तथा तल क्षेत्र अनुपात (एफएआर) अगली निम्नतर श्रेणी में सबसे बड़े भूखंड के लिए अनुमेय और उपलब्ध, (ii)कवरेज तथा तल क्षेत्र अनुपात से कम नहीं होगा।
  - भूखंडों का उप विभाजन अनुमत्य नहीं हैं। तथापि, यदि एक रिहायशी भूखंड में एकसे अधिक भवन हैं तो निर्मित क्षेत्र तथा सभी ऐसे भवनों के तल कवरेज का योग उस भूखंड में निर्मित क्षेत्र तथा अनुमत्य तल कवरेज से अधिक नहीं होगा। (iii)
  - मेजनीन तल तथा सर्विस तल, यदि निर्मित किया गया हो तो उसे तल क्षेत्र अनुपात में (iv) गिना जाएगा ।
  - भूखंड विकास के मामले में यदि बेसमेंट का निर्माण किया गया है तो वह तल क्षेत्र अनुपात में शामिल नहीं होगा । बेसमेंट क्षेत्रफल यथा अनुमत्य और स्वीकृत निर्मित क्षेत्र के अनुसार भूतल पर कवरेज से अधिक नहीं बढाया जाएगा लेकिन आंतरिक आंगन (v) (कोर्टयार्ड) तथा शांपट के नीचे के क्षेत्र तक बढाया जा सकता है ।
  - रिहायशी भूंखंड के भीतर पार्किंग स्थल निम्नलिखित अनुसार मुहैया कराया जाएगा:-(vi)
    - क. 250 से 300 वर्ग मीटर तक के भूखंडों में 2 समतुल्य कार स्थान(ईसीएस)
      - 300: वर्ग मीटर से अधिक के भूखंडों में प्रति 100 वर्ग मीटर निर्मित क्षेत्र के लिए एक संमतुल्य कार स्थान (ईसीएस)

बशर्त कि यदि किसी भूखंड में उपर्युक्त पार्किंग मान्दंडों के अनुसार अनुमय कवरेज 'और तल क्षेत्र अनुपात नहीं है तो पूर्ववर्ती श्रेणी के पार्किंग मानदंड अनुमत्य होंगे ।

यदि पार्किंग के लिए प्रयुक्त गैर-निवास योग्य ऊ चाई (2.4 मीटर से कम) के स्टिल्ट क्षेत्र के साथ भवन निर्मित किया गया है तो ऐसे स्टिल्ट क्षेत्र को तल क्षेत्र अनुपात में . शामिल नहीं किया जाएगा बल्कि भवन की ऊ चाई के लिए गिना जाएगा । (iiv)

(Viii) जब तक अन्यथा निर्धारित न किया जाए तब तक न्यूनतम सैटबेक निम्नलिखित सारणी में दिए अनुसार होगा:-

क्र. सं.	भूखंड का आकार (वर्ग मीटर में)		न्यूनतम सैटबैक (मीटर में)			
		सामने	पृष्ठ	साइड (1)	साइंड (2)	
1	100 से कम -	0	0	0	0	
2	100 से अधिक 250 तक	3	0	0	0	
3	250 से अधिक 500 तक	3.	3	3	0	
4	500 से अधिक 2000 तक .	6	3	3	3	
5	2000 से अधिक 10000 तक	9	6	6 .	6	
6	10000 से अधिक	15	9	9	9	

- (क) यदि भूखण्ड में अनुमेय कवरेज उपर्युक्त सैटबैक के साथ नहीं की जाती है तो पूर्ववर्ती श्रेणी के सैटबैक की अनुमित होगी ।
- (ख) भविष्य में निर्माण के मामले में 50 वर्ग मीटर से 100 वर्ग मीटर क्षेत्रफल के आवासीय भूखंड में कम से कम 2 मीटर x 2 मीटर खुले आंगन की व्यवस्था की जाएगी ।
- (ix) जो भूखंड स्वामी/आवंटी 23 जुलाई, 1998 की राजपत्र अधिसूचना के अलावा उपर्युक्त मानदंडों के अनुसार अतिरिक्त कवरेज, अतिरिक्त फ्लोर अथवा उसका एक भाग बनाना चाहते हैं, उनसे सरकार द्वारा समय-समय पर अनुमोदित अधिसूचित दरों पर सुधार प्रभार(अथवा अतिरिक्त तल क्षेत्र अनुपात प्रभार) लिया जाएगा । यह प्रभार दिनांक 23 जुलाई, 1998 की अधिसूचना द्वारा अनुमेय से अतिरिक्त तल क्षेत्र अनुपात और दिनांक 15 मई 1995 की अधिसूचना द्वारा अनुमेय अतिरिक्त तल क्षेत्र अनुपात के लिए देय प्रभार से अलग होगा ।
- (X) जो भूखंड स्वामी /आवंटी इस अधिसूचना के अंतर्गत अनुमेय अतिरिक्त कवरेज के संबंध में निर्माण नियमित कराना चाहते हैं, उन्हें उपर्युक्त पैरा (ix) में उल्लिखित सुधार प्रभार के अलाव अर्थदण्ड और सरकार के अनुमोदन से अधिसूचित प्रशमनकारी (कम्पाउंडिंग) प्रभार का भुगतान करना होगा।
- (Xi) जो भूखंड स्वामी /आबंटिती इस अधिसूचना के संबंध में अतिरिक्त ऊंचाई नियमित कराना चाहते हैं, उन्हें उपर्युक्त पैरा (x) में उल्लिखित सुधार प्रभार के अलावा सरकार के अनुमोदन से अधिसूचित अर्थदण्ड और विशेष प्रशमनकारी (कम्पाउंडिंग) प्रभारों का भुगतान करना होगा।

- (XII) इस प्रकार से प्राप्त राशि संबंधित स्थानीय निकाय द्वारा एक एस्क्रो एकाउंट में जमा कराई जाएगी जिसे पार्किंग स्थलों के विकास, सुविधाओं/अवस्थापना को बढ़ाने तथा पर्यावरण सुधार कार्यक्रमों पर खर्च किया जाएगा और इस खाते के आय-व्यय का तिमाही विवरण स्थानीय निकायों द्वारा सरकार को प्रस्तुत किया जाएगा।
- (xiii) सरकारी भूमि पर अतिक्रमण को नियमित नहीं किया जाएगा और स्थानीय निकाय द्वारा अतिरिक्त निर्माण/ऊंचाई के नियमितीकरण के लिए स्वीकृति देने से पहले अतिक्रमण हटाया जाएगा।
- (XiV) अतिरिक्त तल क्षेत्र अनुपात तथा/अथवा ऊंचाई की स्वीकृति अथवा उसे नियमित कराने के इच्छुक प्रत्येक आवेदक को संरचना इंजीनियर से संरचना सुरक्षा का प्रमाणपत्र लेना होगा । यदि इस प्रकर का प्रमाणपत्र प्रस्तुत नहीं किया जाता अथवा अन्यथा भवन को संरचनात्मक रूप से असुरक्षित पाया जाता है तो संबंधित स्थानीय निकाय द्वारा भवन स्वामी को एक औपचारिक नोटिस दिया जाएगा कि वे एक उचित निर्धारित अवधि में संरचना की किमयों को सुधार लें अन्यथा संबंधित स्थानीय निकाय द्वारा भवन को असुरक्षित घोषित कर दिया जाएगा और इसे भवन स्वामी अथवा स्थानीय निकाय द्वारा गिरा दिया जाएगा ।

[सं. के-13011/9/2006-डीडी आईबी] एस. मुखर्जी, अवर सचिव

### MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

# NOTIFICATION

New Delhi, the 22nd September, 2006

- S.O. 1591(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2001, were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.C. 1160(E), dated 21st July, 2006 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections and suggestions as required by Sub-section (3) of Section 11A of the said Act, within thirty days from the date of the said notice;
- 2. Whereas the objections and suggestions received with regard to the proposed modifications were considered by a Board of Enquiry duly constituted by Delhi Development Authority under the relevant rules, and the Authority, after having considered the report of the Board, has recommended the modification of the Master Plan 2001, as envisaged in the said public notice, with certain changes;
- And whereas, the Central Government has, after carefully considering all relevant aspects of the matter, decided to modify the Master Plan for Delhi 2001; 2997 61/66-2

4. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11 A of the said Act, the Central Government hereby makes the following modifications in the said Master Plan for Delhi- 2001 with effect from the date of Publication of this Notification in the Gazette of India.

### Modification:

On page 159 (RHS) of the Gazette of India dated 1<sup>st</sup> August 1990, as modified vide Gazette of India Notification dated 23<sup>rd</sup> July 1998, the following development control norms shall be substituted in respect of Residential Plotted Development (001) in modification of norms laid down in the said Notification dated 23<sup>rd</sup> July 1998, and subject to the terms and conditions given below:-

# Residential Plotted Development (001)

SI.	Area of the plot	Maximum	NA-	1.4
No.	(sqm) (1)	Maximum ground coverage %	Maximum FAR	Maximum height in metres
1	Below 32	90(2)	350	15
2	Above 32 to 50	90 (2)	350	15
3	Above 50 to 100	90 (2)	350	15
4	Above 100 to 250	75 (3)	300 (3)	15
5	Above 250 to 500	75	225	15
6	Above 500 to 1000	50	150	15
7	Above 1000 to 1500	40	120	15
8 `	Above 1500 to 2250	40	120	15
9	Above 2250 to 3000	40	120	15
10	Above 3000 to 3750	40	120	15
11	Above 3750	40	120	15

# Note:

- The local body concerned shall be competent to disregard variation of upto 2% in plot size, arising from conversion of area from sq.yard to sqm and to grant the norms applicable to the lower category of plot size in accordance to para (ii) below.
- 2. 100 % ground coverage shall be eligible for regularization of construction, already existing as on the date of this notification on payment of charges as given in this notification.
- 3. 100 % ground coverage and 350 FAR shall be eligible for regularization of construction already existing as on the date of this

notification on payment of charges as given in this notification, in respect plot size between 100 to 175 sqm.

# Terms and conditions:

- No additional dwelling unit beyond that permissible under notification dated 15th May 1995 shall be permitted, unless the infrastructure and (i). services have been augmented by the local body and the lay-out plan and services plan of the area have been accordingly upgraded. The applicant plot owner/ allottee shall therefore have to give an undertaking to the effect that no additional dwelling unit has been or is sought to be created beyond that permissible vide notification dated 15th May 1995.
- The total coverage and FAR permissible in any plot in a category, shall not be less than that permissible and available to the largest plot in the (ii) next lower category.
- Subdivision of plots is not permitted. However, if there are more than one buildings in one residential plot, the sum of the built up area and ground (iii) coverage of all such buildings, shall not exceed the built up area and ground coverage permissible in that plot.
- The mezzanine floor and service floor, if constructed, shall be counted in (iv) the FAR.
- Basement in case of plotted development, if constructed, shall not be included in FAR. Basement area shall not extend beyond the coverage (v)on the ground floor as per permissible and sanctioned built up area, but may extend to the area below the internal courtyard and shaft.
- Parking space shall be provided for within the residential plot as follows: (vi)
  - a. 2 Equivalent Car Space (ECS) in plots of size 250-300 sqm;
  - b. 1 ECS for every 100 sqm built up area, in plots exceeding 300 sqm

Provided that if the permissible coverage and FAR is not achieved with the above-mentioned parking norms in a plot, the parking norms of the preceding category shall be allowed.

(vii). If the building is constructed with stilt area of non-habitable height (less than 2.4m), used for parking, such stilt area shall not be included in FAR but would be counted towards the height of the building.

199761106-3

(viii) The minimum setbacks shall be as given in the following table unless otherwise prescribed.

S.No.	Plot size (in sqm)		Minimum Setbacks ( in metre)					
		Front		Side (1)	Side (2)			
1 :	Below 100	0	0	0	, 0			
<u>.</u> 2	Above 100 and upto 250	3	0	. 0	0			
3	Above 250 and upto 500	3	3	3	0			
4	Above 500 and upto 2000	6	3	3	3			
5	Above 2000 and upto 10000	9	6	6	6			
6	Above 10000	15	9	9	9			

- a) In case the permissible coverage is not achieved with the abovementioned setbacks in a plot, the setbacks of the preceding category may be allowed.
- b) In the case of construction in the future, a minimum 2m X 2m open courtyard shall be provided for in residential plots of area of 50sqm to 100 sqm.
- (ix) Plot owners/ allottees seeking extra coverage, additional floor or part thereof, over and above Gazette Notification dated 23<sup>rd</sup> July 1998, as per above mentioned norms, shall be charged betterment levy ( or additional FAR charges ) at the rates notified with the approval of the Government, from time to time. This is in addition to the levy payable on the additional FAR allowed vide notification dated 23<sup>rd</sup> July 1998 and over the FAR allowed vide notification dated 15<sup>th</sup> May 1995.
- (x) Plot owners/ allottees seeking regularization of construction in terms of the additional coverage allowed under this notification, shall have to pay a penalty and compounding charges notified with the approval of the Government, over and above the betterment levy referred to in para (ix) above.
- (xi) Plot owners / allottees seeking regularization of additional height in terms of this notification, will have to pay penalty and special compounding charges notified with the approval of the Government, in addition to betterment levy referred to in para (x).
- (xii) The amount so collected shall be deposited in an ESCROW.ACCOUNT by the local body concerned for incurring expenditure for developing

parking sites, augmentation of amenities/ infrastructure and environmental improvement programmes and a quarterly statement of the income and expenditure of the Account shall be rendered by the local bodies to the Government.

- (xiii) Encroachment on public land shall not be regularized and shall be removed first before the local body grants sanction for regularization of additional construction/ height.
- (xiv) Every applicant seeking sanction or regularization of additional FAR and / or height shall submit a certificate of structural safety obtained from a structural engineer. Where such certificate is not submitted or the Building is otherwise found to be structurally unsafe, formal notice shall be given to the owner by the local body concerned, to rectify the structural weakness within a reasonable stipulated period, failing which the building shall be declared unsafe by the local body concerned and shall be demolished by the owner or the local body.

[No. K-13011/9/2006-DD IB] S. MUKHERJEE, Under Secy.

### DELHI DEVELOPMENT AUTHORITY (Meeting Cell)

No. F.1( Misc.)2006/MC/DDA/

Dated: 31.10.2006

The Officer on Special Duty to Lt. Governor, Delhi vide his reference dated 27.10.2006 (PUC-Page-1/C) has mentioned that during the discussion in the Authority Meeting on the agenda item pertaining to "Performance Budget", non-official members wanted a Monitoring Committee to be set up in DDA so that all the schemes on quarterly basis would be brought before the said Committee. It was also discussed that non-official members may be part of the Committee.

OSD to LG further mentioned that the Lt. Governor has desired that said Monitoring Committee should be set up within seven days.

A copy of the Resolution passed by the Authority vide Item No. 102/2006 dated 19.10.2006 is as below:

Performance Budget 2005-06.

F.4(3) Budget/PF/2005-06

The Lt. Governor thanked Shri Mahabal Mishra for his suggestions regarding the presentation of performance Budget in the Authority.

Shri Mahabal Mishra started the discussions and expressed concern over shortfall in expenditure against several heads. He sought specific details of activities taken up during the year and non-completion of various projects.

He pointed out that appointment of Consultants for the Common Wealth Games was being delayed for unexplained reasons and the related projects were also thus getting delayed. Shri Mishra advised that all pending decisions should be immediately taken in accordance with the guidelines of the Ministry of Finance and the CVC.

He also sought appointment of a Monitoring Committee to regularly review performance of DDA under different heads of account and for quarterly Performance Budget reviews by the Authority.

- The Engineer Member gave details of the flats taken up for construction/completed during the years 2005-06 and 2006-07.
- The Vice Chairman informed that the matter regarding appointment of Consultants for the Common Wealth Games will be discussed by the Committee of Secretaries on 31st October 2006. He assured that all the projects will be completed before the given deadlines.
- Shri Mange Ram Garg suggested that DDA should compile upto date records of lands under unauthorized encroachment/possession without any further delay. He expressed resentment that letters written by the Authority members were not being replied and there were long delays in completion of various transactions in DDA. He also pointed out that DDA had not removed 260 unauthorized jhuggies inspite of repeated reminders for almost

The Lt. Governor directed immediate action on all the points raised by the members without awaiting formal minutes of the meeting. He assured that separate meetings will be held to review the Budget Performance and appreciated the idea of quarterly reviews by the Authority.

Submitted for consideration and further orders please.

Dy. Director (Parkt./MC)

Pr. Commr.-cum-Secretary

Vice Chairman

ヤてひ

The monitoring committee may consist of

The monitoring committee may consist of

En, CAO, CE(Hque), concerned CEI CES. In addition VC

The monitoring committee of the concerned one councillary to the

many please arminable one med and one councillary to the Committee, who will constitute the kon-officed inspresentation. Mr Mahahal Mohra MLA

2 Mr Isswar Das M. Counciller

are nominated. Draft order for constitution of Monitoring Committee on Performance Budget has been prepared and placed opposite for approval <sup>;≽</sup>please. May kindly advise who ---- will be nominated as Member Secretary. may lindly see bother Dy. Director (Parlt. Cell/MC)

-

### **DELHI DEVELOPMENT AUTHORITY** (Meeting Cell)

No. F.1(Misc.)2006/MC/DDA//33

Dated: 21th November, 2006

Sub: Monitoring Committee on Performance Budget.

A Monitoring Committee consisting of the following is hereby constituted to regularly review the Budget Performance of the DDA under different heads of account:

- 1. Finance Member
- 2. Engineer Member
- 3. Shri Mahabal Mishra, MLA
- 4. Shri Ishwar Dass, Councillor, MCD
- 5. Chief Engineer [Head Quarters]6. Concerned Chief Engineer(s)
- 7. Chief Accounts Officer Convener

[V M BANSAL] Pr. Commr.-cum-Secretary

### All Concerned.

Copy to:

1. OSD to Lt. Governor, Delhi.

OSD to Vice Chairman, DDA 2.

Dy. Director (Meeting Cell)



EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ii) PART II — Section 3— Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 586] No. 586] नई दिल्ली, बुधवार, जून 7, 2006/ज्येष्ठ 17, 1928 NEW DELHI, WEDNESDAY, JUNE 7, 2006/JYAISTHA 17, 1928

दिल्ली विकास प्राधिकरण

### अधिसूचना

नई दिल्ली, 6 जून, 2006

का.आ. 861(अ).—एतद्द्वारा अधिसूचित किया जाता है कि दिल्ली विकास अधिनियम, 1957 की धारा 5(2)(एच) के अन्तर्गत भारत सरकार शहरी विकास मंत्रालय ने अपने पत्र संख्या के-11011/14/2004-डी.डी.आई.ए. दिनांक 31 मई, 2006 के माध्यम से सूचित किया है कि श्री जयप्रकाश अग्रवाल, संसद सदस्य, राज्य सभा को दिल्ली विकास प्राधिकरण की सलाहकार परिषद् के सदस्य के रूप में चुना गया है।

[सं. एफ. 1 (2) 2004/ए.ओ./एम.सी./दि.वि.प्रा./65]

विश्व मोहन बंसल, प्रधान आयुक्त एवं सचिव

# DELHI DEVELOPMENT AUTHORITY NOTIFICATION

New Delhi, the 6th June, 2006

S.O. 861(E).—It is hereby notified that under Section 5(2)(h) of the Delhi Development Act, 1957 the Government of India, Ministry of Urban Development have *vide* their letter No. K-11011/14/2004-DDIA dated 31st May, 2006 communicated that Shri Jai Prakash Aggarwal, M.P., Rajya Sabha has been elected to be member of the Advisory Council of the Delhi Development Authority.

[No. F. 1 (2)2004/AO/MC/DDA/65]

V. M. BANSAL, Pr. Commr.-cum-Secy.

1731 GI/2006

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054.

No. 11013 D 5 2002 Pol 1 Government of India Ministry of Urban Development

> Room No. 335-C, Nirman Bhávan, New Dellii-110001.

> > Dated 13th October 2006.

Subject:

Minutes of the meeting held on 10.10.2006 at 11.00 A:M. under the Chairmanship of Secretary (UD) regarding construction of multi-storied office as well as residential complex for Regulatory Authroties, Commissions at Delhi.

The undersigned is directed to enclose herewith the minutes of the meeting held on 10.10 2006 at 11.00 AM under the Chairmanship of Secretary (UD) regarding construction of multi-storied office as well as residential complex for Regulatory Authrotics, Commissions at Delhi, for information and necessary action.

> Under Secretary to the Govt. of India Tel. No.2306 1010

1. DG(W), CPWD, Nirman Bhavan 2. Vice Chairman, DDA, VI 1/24 A. 11 D.

3. JS(D&L), MoUD.

4. Director of Estates, Nirman Bhavan

13119 6. ADG(Arch), CPWD.

13119 6. ADG(Arch), CPWD.

Copy to:

- Sr. PPS to Secretary(UD).
- 8. PS to AS(UD), MoUD
- 9. PA to Director(Works), MoUD

all Concerns with Son /

Copy to Commille ), Commilland)

Minutes of the Meeting held on 10.10 2006 at 11.00 am in the chairmanship of Secretary (UD) regarding construction of multi-storied office as well as residential complex for Regulatory Authorities, Commissions at Delhi

A meeting regarding construction of multi-storied office as well as residential complex for Regulatory Authorities, Commissions at Delhi was held under the chairmanship of Secretary (UD) on 10.10.2006 at 11.00 am. A List of the participants is enclosed.

At the outset, AS(UD) mentioned about the directions of Cabinet Committee on Accommodation dated 07.03.2002 and 07.01.2004 regarding construction of Office/Residential Complex for Regulatory Authorities and construction of accommodation for Chairpersons and members of Regulatory Authorities in Gurgaon or Noida respectively.

The following decisions were taken :-

- 1. Actual requirement of office and residential accommodation for the purpose needs to be compiled based on the information available with Directorate of Estates and information furnished by various Ministries. In case some Ministries have not responded, DO letters may be put up to the Secretaries of the concerned Ministries from Secretary (UD) asking them to furnish the details immediately (Action: Director of Estates to draft letters to concerned Secretaries).
- 2. Regarding the land available at Ghitorni, details about land use in the present Master Plan and in the Master Plan 2021, use in Zonal Plan may be intimated at the earliest (Action: DDA)
- The availability of land for the purpose within Delhi (at Narela, Rohini, Dwarka etc) covering an area of 50 to 75 acres taking into consideration the general suitability for residential and office purposes needs to be identified. The extent of water, sewerage, electricity, drainage, road and metro connectivity and other related infrastructure are to be examined and intimated to Director (Works).

In this context, Secretary (UD) expressed concern about the way the development is being planned at Dwarka. He stressed on the need to have an integrated approach towards development so that residential growth also takes into account the commercial and institutional requirement of the population. This is necessary so that problems now being faced in Delhi may not resurface at Dwaraka at a later time (Action: DDA)

- Regarding land available at Ghaziabad. Master Plan and Lay Out Plan to be examined and feasibility of having an integrated complex for the purpose be the residential complex proposed. In planning for the area, care is to be taken to provide for a quite residential core. Office and Commercial activity be kept isolating the residential heart from becoming a vehicular thoroughfare. While working out details, feasibility of density range within which plot of emphasized that while proposing utilization of land for the purpose, utilizations. (Action: CPWD)
- All the above options to be examined with merits/demerits pointed out when appropriate orders.

  All the above options to be examined with merits/demerits pointed out when appropriate orders.

The meeting ended with a vote of thanks to the chair.

# List of Participants

- 1. Shri Anil Baijal, Secretary (UD) in chair
- 2. Shri S.M. Acharya, AS(UD)
- 3. Shri M.M. Kutty, JS(D&L)
- 4. Shri Subhash Kapoor, ADG(Arch.), CPWD
- 5. Shri Rakesh Kumar, Director (Works).
- 6. Shri R.K. Sinha, L&DO
- 7. Shri D. Suresh, Director of Estates
- 8. Shri V.M. Bansal, Principal Secretary & Commissioner, DDA
- 9. Shri R.K. Kakkar, Senior Architect (Headquarters -1), CPWD

\*\*\*\*

### No. K-13011/1/2004- DDIB Government of India Ministry of Urban Development Delhi Division

Nirman Bhavan, New Delhi Dated the 6 February 2007

Subject:

Extraordinary Gazette Notification - circulation of Notification S.O. No. 29(E) dated 10.01.07 regarding change of land use for Old Police Lines.

A copy of Notification dated 10 January, 2007 published in the Gazette of India Extraordinary is sent herewith for information and necessary

Jkbye (S.Mukherjee) Under Secretary to the Government of India Telefax.: 23061681

Vice Chairman, DDA, Vikas Sadan, New Delhi

Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New

The Commissioner (Planning), DDA, Vikas Minar, New Delhi

4. The Commissioner (LD), DDA, Vikas Sadan, New Delhi

5. The Commissioner (LM), DDA, Vikas Sadan, New Delhi

6. The Principal Secretary (UD), GNCTD, Delhi.

7. The Chief Planner, TCPO, IP Estate, New Delhi.

8. The L&DO, Nirman Bhawan, New Delhi. 9. The Secretary, NDMC, Palika Kendra, New Delhi.

10. The Commissioner, MCD, Town Hall, Delhi.

11. The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi

Road, New Delhi
12. The Commissioner, Dolli Police, MSO Bldg. I.P. Estate
Cloud Solling.

Copy to :-

PS to UDM / PS to MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS (D&L)

C. 950 cy

# HRA AN USIUS The Gazette of India

EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ii) PART II — Section 3 — Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 28]

नई दिल्ली, बुधवार, जनवरी 10, 2007/पौष 20, 1928

No. 281

NEW DELHI, WEDNESDAY, JANUARY 10, 2007/PAUSA 20, 1928

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना

नई दिल्ली, 10 जनवरी, 2007

का.आ. 29(अ).—यत: कंन्द्र सरकार का दिल्ली मास्टर प्लान, 2001 में निम्निलिखित क्षेत्र के संबंध में जिन कुछ संशोधनों को करने का प्रस्ताव है उन्हें दिल्ली विकास अधिनियम, 1956 (1957 का 61) की धारा 44 के प्रावधानों के अनुसरण में दिल्ली विकास प्राधिकरण द्वारा दिनांक 30 मार्च. 2005 की सार्वजनिक सृचना सं. का.आ. 447(अ) द्वारा भारत के राजपत्र, असाधारण में प्रकाशित किया गया था और जिनके संबंध में उक्त अधिनियम की धारा 11क की उप-धारा (3) द्वारा यथापेक्षित आपत्तियां/सुझाव उक्त सृचना के प्रकाशन की तारीख से तीस दिन के अंदर आमन्त्रित किए गए थे।

2. यत:, प्रस्तावित संशोधन के संबंध में कोई आपत्ति/सुझाव प्राप्त नहीं हुए और यत: केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली मास्टर प्लान, 2001 में संशोधन करने का निर्णय किया है।

3. अत:, अत्र, कोन्द्र सरकार उक्त अधिनियम की धारा 11क की उप-धारा (2) द्वारा प्रदत्त राक्तियों का प्रयोग करते हुए दिल्ली के उक्त मास्टर प्लान, 2001 में, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से, एतद्द्वारा निम्नलिखित संशोधन करती है:

### संशोधन

''पुरानी पुलिस लाइन्स, राजपुर रोड में, 7.99 हेक्टेयर भूमि का भू-उपयोग निम्नलिखित विवरण के अनुसार परिवर्तित किया जाता है :--

स्था्न	क्षेत्रफल (हेंक्टेयर में)	भू-उपयोग (मास्टर प्लान, 2001 में)	परिवर्तित भू-उपयोग	सीमाएं .
्रपुरानी पुलिस ्लाइन्म, राजपुर -रोड (जोन-सी)	-	रिहायशी	सार्वजनिक और अर्द्ध- सार्वजनिक सुविधाएं (पुलिस मुख्यालय और पुलिस लाइन्स)	उत्तर : कोर्ट रोड (24 मीटर मार्गाधिकार) दक्षिण : बुलवर्ड रोड (60 मीटर मार्गाधिकार) पूर्व : कोर्ट रोड (24 मीटर मार्गाधिकार) पश्चिम : राजपुर रोड (24 मीटर मार्गाधिकार)''
				2000

[सं. के-13011/1/2004-डीडीआईबी]

एस. मुखर्जी, अवर सचिव

### (DELHI-DIVISION) NOTIFICATION

New Delhi, the 10th January, 2007

S.(). 29(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi, 2001 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Rublic Notice vide No. S.O. 447(E), dated 30th March, 2005 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1956 (61 of 1957) inviting objections/suggestions as required by Sub-section (3) of Section 11-Λ of the said Act, within thirty days from the date of the said notice.

2. Whereas no objection/suggestion was received with regard to the proposed modification and whereas the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master Plan for Delhi, 2001. Delhi, 2001.

3. Now, therefore, in exercise of the powers conferred by Sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi, 2001 with effect from the date of publication of this Notification in the Gazette of India

"The land use of an area measuring 7.99 ha. at Old Police Lines, Rajpur Road is changed as per description listed below:

Location	Area (in Ha.)	Land Usc (MPD-2001)	Land Use changed to	r. St. 😘	Boundaries		4
Old Police Lines, Raipur Road (Zone C)	7.99 ha.	Residential	Public and semi-public facilities (Police Headquarters and Police Lines).	South: East:	Court Road (24 mt Boulevard Road (6 Court Road (24 mt Rajpur Road (24 m	0 mtr. R/W) r. R/W) tr. R/W)."	ないできる。 に対していた。 では、 に対していた。 に対していた。 に対していた。 に対していた。 に対していた。 に対していた。 には、 には、 には、 には、 には、 には、 には、 には、

[No. K-13011/1/2004-DDJB] S. MUKHERJEE, , Under Secy

. . . . .

### No. K-13011/1/2004- DDIB Government of India Ministry of Urban Development Delhi Division

Nirman Bhavan, New Delhi Dated the 6 February 2007

Subject:

Extraordinary Gazette Notification - circulation of Notification S.O. No. 29(E) dated 10.01.07 regarding change of land use for Old Police Lines.

A copy of Nolification dated 10 January, 2007 published in the Gazette of India Extraordinary is sent herewith for information and necessary action

> Jkby (S.Mukherjee) Under Secretary to the Government of India Telefax.: 23061681

1. Vice Chairman, DDA, Vikas Sadan, New Delhi

Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New

3. The Commissioner (Planning), DDA, Vikas Minar, New Delhi

4. The Commissioner (LD), DDA, Vikas Sadan, New Delhi

5. The Commissioner (LM), DDA, Vikas Sadan, New Delhi

The Principal Secretary (UD), GNCTD, Delhi.

7. The Chief Planner, TCPO, IP Estate, New Delhi.

8. The L&DO, Nirman Bhawan, New Delhi.

9. The Secretary, NDMC, Palika Kendra, New Delhi.

10. The Commissioner, MCD, Town Hall, Delhi.

11 The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi

Road, New Delhi
12. The Commissioner, Delhi Police, MSO Bldg. I.P. Estate Chow Dolling

Copy to :-

PS to UDM / PS to MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS (D&L)

# He Gazette of India

EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ji) PART II — Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 28| No. 28|

नई दिल्ली, बुधवार, जनवरी 10, 2007/पौष 20, 1928

NEW DELHI, WEDNESDAY, JANUARY 10, 2007/PAUSA 20, 1928

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना

नई दिल्ली, 10 जनवरी, 2007

का.आ. 29(आ),—यत: केन्द्र सरकार का दिल्ली मास्टर प्लान, 2001 में निम्नलिखित क्षेत्र के संबंध में जिन कुछ संशोधनों को करने का प्रस्ताव है उन्हें दिल्ली विकास अधिनियम, 1956 (1957 का 61) की धारा 44 के प्रावधानों के अनुसरण में दिल्ली विकास प्राधिकरण द्वार दिनांक 30 मार्च, 2005 की सार्वजनिक सूचना सं. का.आ. 447(अ) द्वारा भारत के राजपत्र, असाधारण में प्रकाशित किया गया था और जिनके संबंध में उबत अधिनियम की धारा 11क की उप-धारा (3) द्वारा यथापेक्षित आपत्तियां/सुझाव उक्त सूचना के प्रकाशन की तारीख से तीस दिन के अंदर आमन्तिन किए गए थे।

2. यत:. प्रस्तावित यंशोधन के संबंध में कोई आपत्ति/सुझाव प्राप्त नहीं हुए और यत: केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली मास्टर प्लान, 2001 में संशोधन करने का निर्णय किया है। '

3. अत:, अत्र, केन्द्र सरकार उक्त अधिनियम की धारा । कि की उप-धारा (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए दिल्ली के उक्त माम्न्टर प्लान, 2001 में, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से, एतद्द्वारा निम्नलिखित संशोधन करती है: संशोधन

''पुरानी पृलिस लाइन्य, राजपुर रोड में, 7.99 हेक्टेयर भूमि का भू-उपयोग निम्नलिखित विवरण के अनुसार परिवर्तित किया जाता है :--

ग्न्यान क्षत्रफल (हैक्टेयर में) भृ- उपयोग (भारटर परिवर्तित भू-उपयोग सीमाएं प्लान, 2001 में) पुरानी पुलिस 7.99 हक्टेयर रिहायशी सार्वजनिक और अर्द्ध-कोर्ट रोड (24 मीटर मार्गाधिकार) लाइन्य, राजप्र सार्वजनिक सुविधाएं दक्षिण : बुलवर्ड रोड (60 मीटर मार्गाधिकार) रोड (जोन-सी) 🕟 (पुलिस मुख्यालय और कोर्ट रोड (24 मीटर मार्गाधिकार) पूर्व : पुलिस लाइन्स) पश्चिम : राजपुर रोड (24 मीटर मार्गाधिकार)''

[सं. के-13011/1/2004-डीडीआईबी]

एस. मुखर्जी, अवर सचिव

### MINISTRY OF URBAN DEVELOPMENT

## NOTECATION

New Delhi, the 10th January, 2007

S.O. 29(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi, 2001 regarding the area mentioned hereunder over published in the Gazette of India, Extraordinary, as 1 ublic Notice vide No. S.O. 447(E), dated 30th March, 2005 by 1. Delhi Development Authority in accordance with the proxision of Section 44 of the Delhi Development Act, 1956 (61 of 1957) inviting objections/suggestions as required by Sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.

2. Whereas no objection/suggestion was received with regard to the proposed modification and where is the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master P in 167 Delhi, 2001.

Delhi, 2001;

3. Now, therefore, in exercise of the powers conferred by Sub-section (2) of Section 11-A of the said Act the Central Government hereby makes the following modification in the said Master Plan for Delhi, 2001 with effect from the date of publication of this Notification in the Gazette of India:

Modification:

"The land use of an area measuring 7.99 ha, at Old Police Lines, Rajpur Road is changed as per description listed be own.

Location	Arca (in Ha.)	Land Use Land Use changed to (MPD-2001)	Boundaries
Old Police Lines, Rajpur Road (Zone C)	7.99 ha.	Residential Public and semi-public facilities (Police  Headquarters and Police  Lines)	North: Court Road (24 mtr. R/W) South: Boulevard Road (60 mtr. R/W) East: Court Road (24 mtr. R/W) West: Rajpur Road (24 mtr. R/W)

[No. K-13011/1/200]-DDIB]

S. MUKHERJEE., Un le

# Department of Environment, Govt. of NCT of Delhi, Delhi Secretariat, IP Estate, New Delhi-02

			Jew <sup>a</sup>	•					
\$	No.	F. 10(12)/DG	6/Env. /20	: )04-2005/ <u>ব</u> ্	LS-352		Dated;	19/4/20	10 L
	To				, N	Det 2 a		1	10 T
		Vice Chairma Vikas Sadan,	n, DDA	agroff of		2.3 APR	2007年 元		TÉRVAN É
	•	Near INA Mar New Deihi	ket,		201	RUA	1.1	Zinta 94	%L\$\$ #4 r== #################################
	Sub:	Fly Ash Not	ification	- Replacem	ent of the	a evicting	ana with	A TOWN STATE OF THE STATE OF TH	(۱۳۱۶)
		notification -	Draft	·		e existing	OHE	r∴a∞ new	
	Sir,								
0 W.	11 <sup>th</sup> A	l am directed t April 2007 of Mo ation is also en	ノベア・しっしょし	herewith a c regarding th	opy of the le e above su	etter no. 9-8/ bject. A cop	2005-HSN by of the s	MD dated aid draft	
Sold Market		It is requested	to kindly	y send your	comments	regarding th	ne draft i	fany to	
2 1 VI	MoEF to this	, GOI within the Department.	time stip	oulated in the	draft notifi	cation with a	copy of t	he same	
is the second of							Vo	:-:::	
	1500	D.A					rours	aithfully,	٠
	10 131	(O)					(Nigam A		
Juc							Scientis	st (Env.)	, F ,
02 /2	Encl ·	As above	· ·						; ;
02 Molac 24/4/17		,	F. T	1,	_	-			:
	. 1		Pc.	Seey					:
1 y ne	st		(ハ)	<u>0</u> , <i>u</i>					
FN	くま	they, ca	$\overline{M}$	~			•		
1 ,		l.	2	0/4					; ;
•		لا	••	Andrew Property and American					:
D	220	= 24/9							
		L)						•	
(fob	12507	Α .							
Zut	1/02	( FOLKING)	<i>!</i> .			·			:
			Ç)						
Mark Contraction of the Contract	/) 	/ Ky		ASS 17 -					
•	~		<u> </u>	Please	e latee	מה ה ממחום	ی نقید	Maril al	
		•		A					:
					·	•	•	4	
				A	2016		_	<u> </u>	

4

No.9-8/2005 -HSMD Government of India Ministry of Environment and Forests **HSM Division** 

> Paryavaran Bhawan CGO Complex, Lodi Road New Delhi -110 003

> > Dated: 11th April, 2007

Τo

Electionaluti

Secretary (em Department of Environment,

Government of National Capital Territory, Delhi,

Delhi Secretariat, Indraprastha Estate,

New Delhi -110 002

Subject:

Fly Ash Notification - Replacement of the existing one with a new notification - Draft.

Enclosed please find 10 copies of the above draft notification. Since matter concerns a number of Departments such as Public Works Department, Road Construction Department, Building Construction Department, Local Bodies Department etc, You may like to bring to it to the attention to all concerned. This is only a draft notification and the comments, if any, should reach the Ministry of Environment and Forests, Government of India within the times stipulated in the draft notification.

Yours faithfully,

Encl. As above

(R. Anandakumar) Adviser

Telephone No.:011-24364592

# He Gazette of India

असाधारण

### **EXTRAORDINARY**

भाग II — खण्ड 3 — उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

H. 833] No. 833]

नई दिल्ली, बृहस्पतिवार, जुलाई 5, 2007/आषाढ़ 14, 1929 NEW DELHI, THURSDAY, JULY 5, 2007/ASADHA 14, 1929

## शहरी विकास मंत्रालय

(दिल्ली प्रंभाग)

# अधिसूचना

नई दिल्ली, 5 जुलाई, 2007

का.आ. 1103(अ),—यत: यहां नीचे उल्लिखित क्षेत्र के संबंध में दिल्ली के मास्टर प्लान में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास अधिनियम, 1956 (1957 का 61) के खण्ड 44 के प्रावधानों के अनुसार दिनांक 26 अप्रैल, 2007 की सं.का.आ. 656(अ) की सार्वजनिक सूचना द्वारा भारत के राजपत्र, असाधारण में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (3) द्वारा यथा-अपेक्षित आपत्तियां/सुझाव आमंत्रित किए गए।

- 2. यत: प्रस्तावित संशोधन के संबंध में कोई आपत्तियां/सुझाव प्राप्त नहीं हुए तथा यत: केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के **बाद दिल्ली के मा**स्टर प्लान-2021 में संशोधन करने का निर्णय लिया है।
- 3. अतः, अब उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती है :

जोन "डी" में कस्तूरबा गांधी मार्ग (कर्जन रोड) पर 2.328 हेक्टे. (5.75 एकड़) माप वाले निम्नलिखित क्षेत्र के भू-उपयोग को

स्थिति	क्षेत्र	भू-उपयोग (एपीडी 2021)	परिवर्तितं भू-उपयोग	सीमाएं
कस्तूरबा गांधी मार्ग (कर्जन रांड)	2.328 हेक्टे. (5.75 एकड़)	ं रिहायशी	सरकारी कार्यालय	उत्तर – सरकारी भूमि दक्षिण – जसवंत सिंह मार्ग (केनिंग लेन) पूर्व – कस्तूरबा गांधी मार्ग (45.72 मी. मार्गाधिकार) पश्चिम – लेडी इरविन स्कूल

[सं. के-13011/1/2007-डीडी ] बी

पी. के. सांतरा, अवर सचिव

3039 GI/2007

### MINISTRY OF URBAN DEVELOPMENT

### (DELHI DIVISION)

### NOTIFICATION

New Delhi, the 5th July, 2007

S.O. 1103(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 656(E) dated 26th April, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1956 (61 of 1957) inviting objections/suggestions as required by Sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.

2. Whereas no objection/suggestion was received with regard to the proposed modification and whereas the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master Plan for Delhi-2021.

3. Now, therefore, in exercise of the powers conferred by Sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi-2021 with effect from the date of publication of this Notification in the Gazette of India:—

### MODIFICATION:

The land use of the following area measuring 2.328 ha. (5.75 acres) at Kasturba Gandhi Marg (Curzon Road) in Zone "D" be changed as per description listed below:

Location	Area	Land Use (MPD-2021)	Land Use Boundaries Changed
Transaction Continues 117 mg	2.328 ha. 5.75 acres)	Residential	Government Office North - Government land, South - Jaswant Singh Marg (Canning Lane) East - Kasturba Gandhi Marg (45.72m R/W) West - Lady Irwin School

[No. K-1301 I/1/2007-DD IB]
P. K. SANTRA, Under Secy.

हि है, 🗷 📝 संसद एवं समन्यय दिभार BURN, I PARLT, & CO-ORDN, BRANCH क्षानतीः पर्द 💉 DIARY 🚾 🚉

No. K- 13011/16/2005-DD-IB Government of India Ministry of Urban Development Deihi Division

> Nirman Bhavan, New Delhi Dated the 3<sup>rd</sup> September, 2007

Subject:

Extraordinary Gazette Notification for change of land use of measuring 4.4 acre at Plot No. 12, Rajpur Road (Zone 'C').

A copy of Notification dated 2<sup>nd</sup> August, 2007 published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

Encl. As above.

Under Secretary to the Government of India Telefax.: 23061681

Τo

दिनांक ... २ ... ... ... ... ... ... ...

वैटक कक्ष, दि वि प्रा

1. The Vice Chairman, DDA, Vikas Sadan, New Delhi

- 2. The Director General of Works, CPWD, Nirman Bhawan, New Delhi
- 3. The Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi
- 4. The Commissioner (Planning), DDA, Vikas Minar, New Delhi
- 5. The Commissioner (LD), DDA, Vikas Sadan, New Delhi
- 6. The Commissioner (LM), DDA, Vikas Sadan, New Delhi
- 7. The Secretary, Land & Building Department, GNCTD, Delhi.
- 8. The Chief Planner, TCPO, IP Estate, New Delhi.
- 9. The L&DO, Nirman Bhawan, New Delhi.
- 10. The Secretary, NDMC, Palika Kendra, New Delhi.
- 11. The Commissioner, MCD, Town Hall, Delhi. 12. The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi
- 13. Maj. Gen Nilendra Kumar, AVSM, VSM, Judge Advocate General, Army Headquarters, Sena Bhawan, New Delhi-110011.

get it pasted in

# HICE Gazetie of India

असाधारण

EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (il) PART II—Section 3—Sub-section (ii)

प्राथिकार से प्रकाशित PUBLISHED BY AUTHORITY

ਜਂ. 955] No. 955] नई दिल्ली, वृहस्यतिवार, अगस्त 2, 2007/श्रावण 11, 1929

NEW DELHI, THURSDAY, AUGUST 2, 2007/SRAVANA 11, 1029

शहरी विकास मंत्रालय

(,दिल्ली प्रधाग)

### अधिसूचना

नई दिल्ली, 2 अगस्त, 2007

का.आ. 1351(अ),—यत: यहां नीचे डिल्लिखित क्षेत्र के संबंध में दिल्ली के मास्टर प्लान में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली दिकास अधिनियम, 1956 (1957 का 61) के खण्ड-44 के प्रावधानों के अनुसार दिनांक 4 जनवरी, 2007 की सा.का.आ. 8(अ) को सार्वजनिक सूचना द्वारा भारत के असाधारण राजपत्र में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड ::-ए के उप-खण्ड (3) द्वारा यथाअपिशत आपत्तियां/सुझाव आमंत्रित किए गए।

2. यत: प्रस्तावित संशोधन के संबंध में कोई आपित्तयां/सुझाव प्राप्त नहीं हुए तथा यत: केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान-2021 में संशोधन करने का निर्णय लिया है।

3. अत:, अब उक्त अधिनियम के खण्ड 11-ए के उप-खंड-2 द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वार निम्नलिखित संशोधन करती है।

### संशोधन:

''प्लाट सं. 12, राजपुरा रोड (जोन 'सी') में 4.4 एकड़ के क्षेत्रफल के निम्नलिखित भू-उपयोग भें निम्नलिखित विवरण के अृंनुसार परिवर्तन किया जाता है '':—

क्षेत्रफल का व्योग	क्षेत्रफल एकड में	से	<b>i</b>
उत्तर-पश्चिम में मनोरंजक क्षेत्रों, उत्तर-पूर्व में एमसीडी कर्मचारी आवास, दक्षिण-पूर्व में राजपुर रोड और दक्षिण-पश्चिम में एमसीडी कर्मचारी आवास से घिरा।		''रिहायशी''	'अधिकतम एफएआर 75 वाली सार्त्रजनिक और अर्द्धसार्वजनिक सुविधाएं जिसमें (सेना विधि संस्थान) भूमि कवरेज 25 प्रतिशत और कँचाई 11 मीटर हो''

[सं. के-13011/16/2005-डी डी आई बी]

पी. के. सांतरा, अवर सचिव

3382 GI/2007

.(1)

### MINISTRY OF URBAN DEVELOPMENT

### (DELHI DIVISION)

# NOTIFICATION

### New Delhi, the 2nd August, 2007

S.O. 1351(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 8(E), dated 4th January, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1956 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11. A of the said Act, within thirty days from the date of the said notice.

2. Whereas no objection/suggestion was received with regard to the proposed modification and whereas the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master Plan for Delhi-2021.


3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi-2021 with effect from the date of Publication of this Notification in the Gazette of India.

### Modification:

"The land use of the following area measuring 4.4 acre of land at plot no. 12, Rajpur Road (Zone 'C') is changed as per description listed below:—

 Description of Area	Area in Acre	From	To
Area bounded by Recreational in the North-West, MCD's Staff Housing in the North-East, Rajpur Road in the South-East and MCD staff housing in the South-West.	4.4	4	"Public & Semi-Public Facilities (Military Law Institute)" with a maximum FAR of 75, Ground Coverage 25% and Height 11 Mtr."

[No, K-13011/16/2005-DDIB]
P. K. SANTRA, Under Sec.



MODIFICATION:

2 acres (0.8 Ha) in Rouse Avenue, DDU Marg, New Delhi In Zone-D bounded by Pocket 9 (Government Use) in the West, Road (20 m R/W) in the East, Deen Dayal Upadhaya Marg (36.58 m R/W) in the South and Kotla Road (30.48 m N/N) in the North from 'Government Office' to 'Public & Semi-Public Facilities"."

The Plan indicating the proposed modification is available for inspection at the office of Joint Director (MP), 6th Floor, Vikas Minar, I.P. Estate, Delhi Development Authority, New Delhi, on all working days during the period, referred above.


No. F.20(7)2007/MP

V. M. Bansal Pr. Commr.-cum-Secy.

ALIM OF ELEMONAL wniluence the out If Indian batsme shows that the modern Iraqi state is a product of arbitrary boundaries drawn by France and Britain in 1016 alrismo

# अनुसूची


 तज्ब	ज़िला	तहसीत	इलाका	स्पारक का नाम	खसरा संख्या	क्षेत्रफल	स्वामित्व	सीमाएँ
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9) 
दिल्ली	दिल्ली	कालकाजी	बदरपुर (ग्राम कोटला माहीगिरिम)	कोसमीनार	197/1	78.50 च.मी.	सरकार उत्त डी.डी.ए प्	पार्क
					·,			क्षिण ही.डी.ए पार्क श्चम ही.ही.ए पार्क



# अनुसूची

				स्मारक	 खसरा	क्षेत्रफल	स्वामित्व 🤭	<sub>ार</sub> सीमाऐं जन्म
राज्य	ज़िला	तहसील ;	इताका	का नाम	संख्या			(9)
		(3)	(4)	(5)	(6)	(7) <sub>.</sub>	(8) 	
(1)  दिल्ली	(2)  दिल्ली <sub>,</sub>	कालकाजी	बदरपुर (ग्राम ताजपुल)	कोसमीनार	46/1	25 व.मी.	सरकार पी.डी.डी.	उत्तर पार्क पूर्व पार्क दक्षिण पार्क पश्चिम मार्ग


a.'



# अनुसूची

 राज्य	ज़िला !	तहसील	इलाका	स्मारक का नाम	खसरा संख्या	क्षेत्रफल	स्वामित्व	T 3	तिमाऍ
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)		(9)
दित्त्ती	दिस्ती	कालकाजी	बदरपुर	कोसमीनार	27// 12/1/1	55.08 ਬ.ਸੀ. ਂ	सरकार भू व भ.	उत्तर पूर्व दक्षिण पश्चिम	निर्मित संरचना
				•				Ų	J:

---



# (दिल्ली राजपत्र भाग - 4 असाधारण में प्रकाशनार्थ) राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार (पुरातत्व विभाग )

दारा शिकोह लाइब्रेरी बिल्डिंग, गु. गो. सिं. इंद्रप्रस्थ विश्वविद्यालय परिसर. कश्मीरी गेट, दिल्ली -110006

दिनांक 01-11-2007

# अधिसूचना

सं.फा.3(25)/2006/मोनू (ii)/ 1231 – जबिक राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार ने अधिसूचना सं.फा.3(25)/2006-मोनू (ii)/ 2367 दिनांक 5 सितम्बर, 2006 द्वारा दिल्ली पुरातन एवं ऐतिहासिक स्मारक तथा पुरातन्त्रीय स्थल और अवशेष अधिनियम, 2004 (2005 का दिल्ली अधिनियम 9) की धारा 4 की उप-धारा (1) के अधीन सौंपी गई शक्तियों का प्रयोग करते हुए उक्त अधिसूचना के साथ संलग्न स्थल मानचित्रों तथा अनुसूचियों में विनिर्दिष्ट संस्मारकों को संरक्षित करने के अपने आशय की अधिसूचना दी थी और उक्त अधिसूचना की प्रतिलिपियाँ उक्त संस्मारकों पर एवं इनके निकट सहज दृश्य स्थानों पर चिपका दी गई थी तथा उक्त संस्मारकों में रूचि लेने वाले उक्त संस्मारकों से इनको संरक्षित घोषित करने से संवधित आपित्तयाँ एवं सुझाव, राजकीय राजपत्र में इस अधिसूचना को जारी किए जाने की तारीख से दो महीने की अविध के भीतर आमंत्रित की गई थीं ;

और जबिक उक्त राजपत्र अधिसूचना की प्रतिलिपियाँ 5 सितम्बर, 2006 को जनता को उपलब्ध करा दी गई थी;

और जबकि इस सरकार द्वारा उक्त प्रस्ताव के लिये जनता से कोई आपित एवं सुझाव प्राप्त नहीं हुये ;

अत: अब, राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार दिल्ली पुरातन एवं ऐतिहासिक स्मारक तथा पुरातत्वीय स्थल और अवशेष अधिनियम, 2004 (2005 का दिल्ली अधिनियम 9) की धारा 4 की उप-धारा (3) द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुए एतद्वारा इसके साथ संलग्न उक्त स्थल मानचित्रों तथा अनुसूचियों में विनिर्दिष्ट संस्मारकों को संरक्षित घोषित करती है।


राष्ट्रीय राजधानी क्षेत्र दिल्ली के उपराज्यपाल के आदेश तथा नाम पर.

( आर. एम. पिली )

अतिरिक्त सचिव (कला, संस्कृति एवं भाषा)


### **SCHEDULE**

		~						
State	District	Tehsil	Locality	Name of the		Area	Ownership	Boundaries
(1)	[2]	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Delhi	Delhi k	Calkaji	Village Kotla Mahigirim (near Apollo	Kos Minar	197/1	78.50 Sq.mt,	Govt: DDA	North: DDA Park East: DDA Park South: DDA Park
<del></del>	15		Hospital)	\				West: DDA Park




### SCHEDULE

State	Distric	l Tchsil	Locality	Name of the monument	Khasra No.	Агеа	Ownership	Boundaries
(1)	(2)	· (3)	(4)	(5)	(6)	(7)	(8)	(9)
Delhi	Delhi	Kalkaji	Badarpur Border (Village Tajpul)		46/1	25 Sq.mt.	Govt. P.D.D:	North: Park East: Park South: Park West: Road



### SCHEDULE

*	<u> </u>	<u>5C</u>	UEDOUE			
State District Tehsil	Locality	Name of t	he Khasra No.	Arca	Ownership	- 4401001102
(1) (2) (3)	(4)	(5)	(6)	(7)	(8)	(9)
Delhi Delhi Kalkaji	Badarpur	Kos Minar	27 // 12/1/1	55.08 Sq.mt.	Govt. L & B	North: DDA Park East: DDA Park South: Road, Built up structures West: Open area.
13						Temp. Sheds
				<del></del>		-4



(TO BE PUBLISHED IN PART - IV OF THE DELHI GAZETTE - EXTRA ORDINARY)

GOVERNMENT OF THE NATIONAL CAPITAL TERRITORY OF DELHI (DEPARTMENT OF ARCHAEOLOGY) DARA SHIKOH LIBRARY BUILDING, G.G.S. INDRAPRASTHA UNIVERSITY CAMPUS, KASHMERE GATE, DELHI-110006.

Dated 01-11-2007

No.F.3 (25)/2006/Monu.(ii)/ 12-31 - Whereas the Government of the National Capital Territory of Delhi vide notification No. F.3(25)/2006/Monu.(ii)/2367 dated the 5<sup>th</sup> September 2006 issued under sub-section (1) of section 4 of the Delhi Ancient and Historical Monuments and Archaeological Sites and Remains Act, 2004 (Delhi Act 9 of 2005) notified its intention to declare the monuments' specified in the Schedules and the Site Plans annexed thereto, to be protected monuments and the copies of aforesaid notification were affixed in a conspicuous place on and near the said monuments, inviting objections and suggestions from all persons likely to be interested in any such monuments, within a period of two months from the date on which the copies of the Gazette pertaining to the said notification were made available to

And whereas the copies of the said Gazette were made available to the public on the 5th September 2006;

And whereas no objection and suggestion has been received from the public to the said proposal by this Government;

Now, therefore, in exercise of the powers conferred by sub-section (3) of section 4 of the Delhi Ancient and Historical Monuments and Archaeological Sites and Remains Act, 2004 (Delhi Act 9 of 2005), the Government of the National Capital Territory of Delhi hereby declares the monuments specified in the Schedules and Site Plans annexed hereto, to be the protected monuments for the purpose of said Act.

> By order and in the name of the Lt. Governor of the National Capital Territory of Delhi,

Additional Secretary (Art, Culture & Language)

MOST IMMEDIATE File No.3(25)/2006-Monu/12-31 GOVERNMENT OF NCT OF DELHI (DEPARTMENT OF ARCHAEOLOGY) Dara Shikoh Library Building, G.G.S. Indraprastha University Campus, Kashmere Gate, Delhi-110 006. 

> The Joint Secretary(GAD), General Administrative Department, 2<sup>nd</sup> Level, A-Wing, Delhi Secretariat, New Delhi-110002.

Gazette Notification for the protection of the three Kos Minars situated in and around

I am enclosing herewith two copies of the above notification (English and Hindi version) & for Publishing in the Delhi Gazette (Part-IV) extraordinary today itself. It is requested that at lo least 10 copies of the same may be sent to this department as soon as it is received from the

Yours faithfully,

Addl. Secretary(Art, Culture & Language)

Encls.: As above.

File No.3(25)/2006-Monu.//257

Dated the \$1.72.7

Copy forwarded for information to:

The Additional Secretary to Lt. Governor, Raj Niwas, Delhi. 1.

The Secretary to Chief Minister, Govt. of Delhi, Delhi Secretariat, New Delhi. 2.

- The Secretary to Delhi Legislative Assembly, Old Secretariat, Delhi with 70 copies for circulation among the M.L.As., Delhi Legislative Assembly, Delhi.
- The Vice Chairman, DDA, INA, Vikas Sadan, New Delhi.
- The Secretary(law), Deptt. of Law, Justice and Legislative Affairs), Delhi Sectt., N.D.
- The Principal Secretary (Home), Department of Home, Delhi Secretariat, New Delhi.
- The Secretary (Art, Culture & Language), Old Secretariat, New Delhi. 7.
- The Secretary, Delhi Urban Arts Commission, India Habitat Centre, Core 6 A, 1st Floor, Lodhi Estate, New Delhi.
- Director (Monuments), Archaeological Survey of India, Janpath, New Delhi. Divisional Commissioner, Govt. of NCT of Delhi, 5, Sham Nath Marg, Delhi. 10.
- Commissioner, MCD, Ambedkar Bhavan, New Delhi. 11.
- Commissioner (LM), DDA, INA, Vikas Sadan, New Delhi. 12.
- Chief Town Planner, MCD, Nigam Bhavan, Kashmere Gate, Delhi. 13.
- Dy. Commissioner of Police (South), Hauz Khas, New Delhi. 14. Asstt. Commissioner of Police, Sarita Vihar, New Delhi. 15.
- Dy. Commissioner (South), Govt. of NCT of Delhi, M.B. Road, New Delhi.
- Dy. Commissioner (Central), M.C.D., Lajpat Nagar, New Delhi. 17.
- OSD to Chief Secretary, Delhi Secretariat, New Delhi. 18.
- The Secretary, INTACH, 71, Lodhi Estate, New Delhi. 19.
- Superintending Archaeologist, ASI, Delhi Circle, Red Fort, Delhi. 20.
- S.D.M.(Kalkaji), Tuglakabad Institutional Area, New Delhi.

SHO, Badarpur Police Station, Badarpur, Delhi.


Addl. Secretary(Art, Culture & Language)

# अनुसूची

 राज्य	 ज़िला	 तहसील	 इलाका	स्पारक का नाम	खसरा • संख्या	क्षेत्रफल	खामि	त्व	सीमाएँ
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)		(9) 
दिल्लो	दित्ती	कालकाजी	<b>बदरपुर</b>	दक्षिणीद्वार एवं चारदीवारी अवशेष	47(ਬਾਫ) 48(ਢਾਫ) 49(ਢਾਫ)	328.50 ग्राम सभा व.मी. (गेर-मुमकि आबादी) सरकार	<b>न</b>	उत्तर पूर्व दक्षिण पश्चिम	मार्ग एंव खुला स्थल निर्मित संरचना मार्ग एंव व्यापारिक खोखे निर्मित
		;			43(G-6)	दोलतमदा	र <del>-</del>		संस्थना

i v

.



THINDS IN YOU IN IN OCC


# अनुसूची

राज्य	ज़िला	तहस्रोत	इलाका	स्पारक का नाम	खसरा संख्या		क्षेत्रफत	स्वामित्व	 सोमाएँ
(1)	(2)	(3)	(4)	(5)	(6)		(7)	(8)	(9)
दिल्ली	दिल्ली	कालकाजी	बदरपुर	मध्यद्वार	47(खण्ड)	164	प्राम सभा	 उत्तर	 मार्ग
					48(खण्ड)	व.मी.		पूर्व	नाग निर्मित संरचना
	÷				49(खण्ड)		सरकार दौलतमदार	दक्षिण पश्चिम	मार्ग निर्मित संरचना
· 	*****	Ş <i>Ū</i>	~~~~					G	<sup>भरचना</sup> )

زلا

. - . - .

.



MINDOWN KON 1711 CACC

1

# अनुसूची

48(खण्ड) आबादी) संरच दक्षिण मार्ग 49(खण्ड) सरकार पश्चिम निर्मित	राज्य	ज़िला	तहसील .	इलाका	स्पारक का नाम	खसरा संख्या	क्षे	प्रफल	स्वामित्व :	सीमाऐं
व.भी. (गेर-मुमिकन पूर्व निर्मित 48(खण्ड) आबादी) संरच- दक्षिण मार्ग 49(खण्ड) सरकार पश्चिम निर्मित	(1)	(2)	(3)	(4)	(5)	(6)	(	7)	(8)	(9)
दक्षिण मार्ग 49(खण्ड) सरकार पश्चिम निर्मित	दिल्ली	दिल्ली	कालकाजी	बदरपुर	उत्तरीद्वार			(गेर-मुमकिन		निर्मित
						48(खण्ड)		•	दक्षिण	संरचना मार्ग
						49(खण्ड)				ि निर्मित संरचना १

• .

Site Plan of Southern Gateway, Badarpur  The state of the
--

TOTALISMENT YOU ISIN OCC

\*\*

### <u>SCHEDULE</u>

State	District	Tehsil	. Locality	Name of the	Khasra No.	Area	Ownership	Boundaries
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Delhi	Delhi 	Kalkaji	Badarpur	Gateway	47(part) 48(part) 49(part)	328.50 Sq.mt.	Gram Sabha (Gair-Mumkin Abadi) Sarkar Daulatmadar (Government)	East: Built-up structures South: Road &

**4**;

لاهمر

(दिल्ली राजपत्र भाग - 4 असाधारण में प्रकाशनार्थ) राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार (पुरातत्व विभाग)

दारा शिकोह लाइब्रेरी बिल्डिंग, गु. गो. सिं. इंद्रप्रस्थ विश्वविद्यालय परिसर, कश्मीरी गेट, दिल्ली -110006

दिनांक था।।। 2007

# अधिसूचना

सं.फा.3(25)/2006/मोनू (i)/ 1230 – जबिक राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार ने अधिसूचना सं.फा.3(25)/2006-मोनू (i)/ 2366 दिनांक 5 सितम्बर, 2006 हारा दिल्ली पुरातन एवं ऐतिहासिक स्मारक तथा पुरातत्वीय स्थल और अवशेष अधिनियम, 2004 (2005 का दिल्ली अधिनियम 9) की धारा 4 की उप-धारा (1) के अधीन सौंपी गई शिक्तयों का प्रयोग करते हुए उक्त अधिसूचना के साथ संलग्न स्थल मानचित्रों तथा अनुसूचियों में विनिर्दिष्ट संस्मारकों को संरक्षित करने के अपने आशय की अधिसूचना दी थी और उक्त अधिसूचना की प्रतिलिपियाँ उक्त संस्मारकों पर एवं इनके निकट सहज दृश्य स्थानों पर चिपका दी गई थी तथा उक्त संस्मारकों में रूचि लेने वाले सभी व्यक्तियों से इनको संरक्षित घोषित करने से संबंधित आपित्तयाँ एवं सुझाव, राजकीय राजपत्र में इस अधिसूचना को जारी किए जाने की तारीख से दो महीने की अविध के भीतर आमंत्रित की गई थीं ;

और जबकि उक्त राजपत्र अधिसूचना की प्रतिलिपियाँ 5 सितम्बर, 2006 को जनता को उपलब्ध करा दी गई थी;

और जबकि उक्त प्रस्ताव के लिये जनता से प्राप्त आपत्तियों एवं सुझावों पर इस सरकार द्वारा विचार किया गया ;


अत: अब, राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार दिल्ली पुरातन एवं ऐतिहासिक स्मारक तथा पुरातत्वीय स्थल और अवशेष अधिनियम, 2004 (2005 का दिल्ली अधिनियम 9) की धारा 4 की उप-धारा (3) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए एतद्द्वारा इसके साथ संलग्न उक्त स्थल मानचित्रों तथा अनुसूचियों में विनिर्दिष्ट संस्मारकों को संरक्षित घोषित करती है ।

राष्ट्रीय राजधानी क्षेत्र दिल्ली के उपराज्यपाल के आदेश तथा नाम पर,

3112: 47.14

( आर. एम. पिल्ले ५५ १५ ००) अतिरिक्त सचिव (कला, संस्कृति एवं भाषा)


1411 OCC



Typody va 1911 of

# SCHEDULE

State	District	Tehsil	Locality	Name of t	he Khasra t No.	Arca	Ownership	Boundaries
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8) ·	(9)
Delhi	Delhi	Kalkaji	Badarpur	Central Gateway	47(part) 48(part) 49(part)	164 Sq.mt.	Gram Sabha (Gair-Mumkin Abadi) Sarkar Daulatmadar (Government)	North: Road East: Built-up structures South: Road West: Built-up structures




اللا من المناسبة

### SCHEDULE

State	District	Tchsil	Locality	Name of t	t No.	Arca	Ownership	Boundaries
(1)	(2).	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Delhi	Delhi	Kalkaji	Badarpur	Northern Gateway	47(part) 48(part) 49(part)	164 Sq.mt.	Gram Sabha (Gair-Mumkin Abadi) Sarkar Daulatmadar (Government)	North: Road East: Built-up structures South: Road West: Built-up structures

11/



(TO BE PUBLISHED IN PART - IV OF THE DELHI GAZETTE - EXTRA ORDINARY)

### GOVERNMENT OF THE NATIONAL CAPITAL TERRITORY OF DELHI (DEPARTMENT OF ARCHAEOLOGY)

DARA SHIKOH LIBRARY BUILDING, G.G.S. INDRAPRASTHA UNIVERSITY CAMPUS, KASHMERE GATE, DELHI-110006.

Dated 01-11-2007

### NOTIFICATION

No.F.3 (25)/2006/Monu.(i)/ 1230 - Whereas the Government of the National Capital Territory of Delhi vide notification No. F.3(25)/2006/Monu.(i)/2366 dated the 5<sup>th</sup> September 2006 issued under sub-section (1) of section 4 of the Delhi Ancient and Historical Monuments and Archaeological Sites and Remains Act, 2004 (Delhi Act 9 of 2005) notified its intention to declare the monuments specified in the Schedules and the Site Plans annexed thereto, to be protected monuments' and the copies of aforesaid notification were affixed in a conspicuous place on and near the said monuments, inviting objections and suggestions from all persons likely to be interested in any such monuments, within a period of two months from the date on which the copies of the Gazette pertaining to the said notification were made available to the public;

And whereas the copies of the said Gazette were made available to the public on the 5<sup>th</sup> September 2006;

And whereas objections and suggestions received from the public to the said proposal have been considered by this Government;

Now, therefore, in exercise of the powers conferred by sub-section (3) of section 4 of the Delhi Ancient and Historical Monuments and Archaeological Sites and Remains Act, 2004 (Delhi Act 9 of 2005), the Government of the National Capital Territory of Delhi hereby declares the monuments specified in the Schedules and Site Plans annexed hereto, to be the protected monuments for the purpose of said Act.

By order and in the name of the Lt. Governor of the National Capital Territory of Delhi,

Rhadhavan Peller

Additional Secretary (Art, Culture & Language)

क कथा, है, है, गा, sealing Cell, D.D.A. यही से Ally No. 42, 23 ( All O. 42) ste. 14 1/1 o 4 (D. 98)

MOST IMMEDIATE
OUT-TODA

File No.3(25)/2006-Monu.//23b GOVERNMENT OF NCT OF DELHI (DEPARTMENT OF ARCHAEOLOGY)

Dara Shikoh Library Building, G.G.S. Indraprastha University Campus, Kashmere Gate, Delhi-110 006.

The Joint Secretary(GAD),
General Administrative Department,
2<sup>nd</sup> Level, A-Wing, Delhi Secretariat,
New Delhi-110002.

Sub.: Gazette Notification for the protection of the Northern Gateway, Central Gateway and Southern Gateway at Badarpur.

Sir.

I am enclosing herewith two copies of the above notification (English and Hindi version) for publishing in the Delhi Gazette (Part-IV) extraordinary today itself. It is requested that at Fleast 10 copies of the same may be sent to this department as soon as it is received from the Poress.

(Caparatt Sopies)

Yours faithfully,

(R.M. Pillai)

Addl. Secretary(Art, Culture & Language)

Encls.: As above.

File No.3(25)/2006-Monu.//235

Copy forwarded for information to:

Dated the かんこん ロークテ

1. The Additional Secretary to Lt. Governor, Raj Niwas, Delhi.

The Secretary to Chief Minister, Govt. of Delhi, Delhi Secretariat, New Delhi.

3. The Secretary to Delhi Legislative Assembly, Old Secretariat, Delhi with 70 copies for circulation among the M.L.As., Delhi Legislative Assembly, Delhi.

4. The Vice Chairman, DDA, INA, Vikas Sadan, New Delhi.

5. The Secretary(law), Deptt. of Law, Justice and Legislative Affairs), Delhi Sectt., N.D.

The Principal Secretary (Home), Department of Home, Delhi Secretariat, New Delhi.

7. The Secretary (Art, Culture & Language), Old Secretariat, New Delhi.

3. The Secretary, Delhi Urban Arts Commission, India Habitat Centre, Core 6 A, 1st Floor, Lodhi Estate, New Delhi.

9. Director (Monuments), Archaeological Survey of India, Janpath, New Delhi.

10. Divisional Commissioner, Govt. of NCT of Delhi, 5, Sham Nath Marg, Delhi.

11. Commissioner, MCD, Ambedkar Bhavan, New Delhi.

12. Commissioner (LM), DDA, INA, Vikas Sadan, New Delhi.

13. Chief Town Planner, MCD, Nigam Bhavan, Kashmere Gate, Delhi.

14. Dy Commissioner of Police (South) Hauz Khas, Navy Delhi.

14. Dy. Commissioner of Police (South), Hauz Khas, New Delhi.

15. Asstt. Commissioner of Police, Sarita Vihar, New Delhi.

16. Dy. Commissioner (South), Govt. of NCT of Delhi, M.B. Road, New Delhi.

Dy. Commissioner (Central), M.C.D., Lajpat Nagar, New Delhi.
OSD to Chief Secretary, Delhi Secretariat, New Delhi.

19. The Secretary, INTACH, 71, Lodhi Estate, New Delhi.

0. Superintending Archaeologist, ASI, Delhi Circle, Red Fort, Delhi.

21. S.D.M.(Kalkaji), Tuglakabad Institutional Area, New Delhi.

22. SHO, Badarpur Police Station, Badarpur, Delhi.

nc.) uspend CPCHOS), DOVE (

(R.M. Pillai)

Addl. Secretary(Art, Culture & Language)

de

tip ASSIT IN THIS DED

a 13/11

. E. 1

100

बैठक कक्ष, दि.वि.प्रा. Meeting Cell, D D A. डायशी चं Diary No. दिगांक Date. Subject:

No. K-13011/12/2007- DDIB Government of India Ministry of Urban Development Delhi Division

> Nirman Bhavan, New Delhi Dated the 13 November 2007

Extraordinary Gazette Notification - circulation of Notification S.O. No. 1907(E) dated 12.11.2007 regarding Land Use Change.

A copy of Notification dated 12th November, 2007, published in the Gazette of, India Extraordinary Pari-II-Section 3-Sub-section (ii) is sent herewith for information and necessary action.

Under Secretary to the Government of India Telefax.: 23061681

Vice Chairman, DDA, Vikas Sadan, New Delhi

Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi

The Commissioner (Planning), DDA, Vikas Minar, New Delhi

The Commissioner (LD), DDA, Vikas Sadan, New Delhi The Commissioner (LM), DDA, Vikas Sadan, New Delhi

The Principal Secretary (UD), GNCTD, Delhi.

The Chief Planner, TCPO, IP Estate, New Delhi.

The L&DO, Nirman Bhawan, New Delhi.

The Secretary, NDMC, Palika Kendra, New Delhi.

The Commissioner, MCD, Town Hall, Delhi.

The Scaretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road,

New Folhi

Copy to :-

PS to UDM / PS to N-S (UD) / Sr. PPS to Secy.(UD) / PS to JS (D&L)

# The Gazette of India

EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ii) PART II - Section 3 - Suin-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

ਜ਼. 1386]

No. 1386]

नई दिल्ली, सोमवार, नवम्बर 12, 2007/कार्तिक 21, 1929 NEW DELHI, MONDAY, NOVEMBER 12, 2007/KARTIKA 21, 1929

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना

नई दिल्ली, 12 नवम्बर, 2007

का.आ. 1907(अ). यतः, यहां नीचे उल्लिखित क्षेत्र के संबंध में दिल्ली के मास्टर प्लान-2021 में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खण्ड-44 के प्रावधानों के अनुसार दिनांक 8 अक्तूबर, 2007 की सं. का.आ. 1721(अ) की सार्वजनिक सूचना द्वारा भारत के राजपत्र, असाधारण में प्रकाशित किया गया जिसमें उनत नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (3) द्वारा यथा अपेक्षित आपित्तयां/सुझाव

- 2. यतः, प्रस्तावित संशोधन के संबंध में प्राप्त आपश्चियो/सुझालों पर सक्षम प्राधिकारी द्वारा यथोचित विचार किया गया तथा यतः, केन्द्र सरकार ने मामले के सभी पहलुओं पर व्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान-2021 में संशोधन करने का निर्णय लिया है।
- 3. अतः, अब, उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार, भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती है :--

जोन "डी" में राउज एवेन्यू, द्वीनदयाल उपाध्याय मार्ग, नई दिल्ली पर 2 एकड़ (0.8 हेक्टे) माप वाले निम्नलिखित क्षेत्र के भू-उपयोग को निम्नलिखित विवरण अनुसार परिवर्तित किया जाए :—

	स्थिति	क्षेत्र (	भू-उपयोग एम पी डी-2021)	परिवर्तित भू-उपयोग		सीमाएं
राउ दीन	ज एवेन्यू, दयाल उपाध्याय मार्ग	0.8 हेवडे (2 एकड़)	् सरकारी कार्यालय	सरकारी और अर्ध- सरकारी सुविधाएं	पूर्व पश्चिम	: सड़क (20 मीटर मार्गाधिकार) : पॉकेंट 9 (सरकारी उपयोग)
-		Š.			उत्तर	कोटला रोड (30.48 मीटर मार्गाधिकार) चीनदयाल उपाध्याय मार्ग (36.58 मीटर मार्गाधिकार)
4585	GI/2007			(1)	[सं. के-	13011/12/2007-डी डी आई बी] पी. के. सांतरा, अवर सचिव

### MINISTRY OF URBAN DEVELOPMENT

### (Delhi Division)

### NOTIFICATION

New Delhi, the 12th November, 2007

- S.O. 1907(E).—Whereas, certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2021 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 1721(E) dated 3th October, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.
- 2. Whereas, objections/suggestions received with regard to the proposed modification were duly considered by the competent authority and whereas the Central Government, after carefully considering all aspects of the matter, have decided to modify the Master Plan for Delhi-2021.
- 3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi- 2021 with effect from the date of Publication of this Notification in the Gazette of India:—

### Modification:

The land use of the following area measuring 2 acres (0.8 ha.) at Rouse Avenue, DDU Marg, New Delhi in Zone "D" be changed as per description listed below:

Location	Area	 Land Use (MPD-2021)		Land Use Changed	 Boundaries
Rouse Avenue, DDU Marg	0.8 ha. (2 acres)	Government Office		Public and Semi- Public Facilities	: Road (20 m R/W) : Pocket 9 (Govt. Use) : Kotla Road (30.48 m R/W)
			٠.		: Deen Dayal Upadhaya Marg (36.58 m R/W)

[No. K-13011/12/2007-DDIB]

P. K. SANTRA, Under Secy.

No. K-13011/12/2007- DDIB Government of India Ministry of Urban Development Delhi Division 非非非非非非

Nirman Bhavan, New Delhi Dated the 13 November 2007

:Subject کے

Extraordinary Gazette Notification - circulation of Notification S.O. No. 1907(E) dated 12.11.2007 regarding Land Use Change.

A copy of Notification dated 12th November, 2007 published in the Gazette of India Extraordinary Part-II-Section 3-Sub-section (ii) is sent herewith for information and necessary action.

रोठक कहा, दि.वि.प्रा. Meeting Cell, D.D.A. स्त्रवरी सं Diary No....

Under Secretary to the Government of India Telefax.: 23061681

Vice Chairman, DDA, Vikas Sadan, New Delhi

Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi

The Commissioner (Planning), DDA, Vikas Minar, New Delhi

The Commissioner (LD), DDA, Vikas Sadan, New Delhi

The Commissioner (LM), DDA, Vikas Sadan, New Delhi

The Erracipal Secretary (UD), GNCTD, Delhi.

6. The Chaef Planner, TCPO, IP Estate, New Delhi.

7. The L&DO, Nirman Bhawan, New Delhi.

8. The Secretary, NDMC, Palika Kendra, New Delhi.

9, The Commissioner, MCD. Town Hall, Delhi.

The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, 10. 11. New Dalhi

Copy to :-

PS to UDM / PS to MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS (D&L)



धाग II —खण्ड 3 — उप-खण्ड (ii) PART II — Section 3 — Sub-section (ii) प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

vi. 1386] No. 1386]

नई दिल्ली, सोमबार, नवम्बर 12, 2007/कार्तिक 21, 1929

NEW DELHI, MONDAY, NOVEMBER 12, 2007/KARTIKA 21, 1929

शहरी विकास मन्नालय

(दिल्ली प्रभाग)

अधिसृद्यना

नई दिल्ली, 12 नवम्बर, 2007

का.आ. 1907(अ).—यत:, यहां नीचे उल्लिखित क्षेत्र के संबंध में दिल्ली के मास्टर प्लान-2021 में कोड़ सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली िकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खण्ड--44 के प्रावधानों के अनुसार दिनांक 8 अक्तूबर, 2007 की ने का.आ. 1721(अ) की सार्वजनिक सूचना द्वारा धारत के राजपत्र, असाधारण में प्रकाशित किया गया जिसमें उक्त नीटिस की तारीख़ से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उपं-खण्ड (3) द्वारा यथा अपेक्षित आपित्तयां/सुझाव आमंत्रित किए गए।

- यत: प्रस्तावित संशोधन के संबंध में प्राप्त आपत्तियों/सुझावों पर सक्षम प्राधिकारी द्वारा यथोजित विचार किया गया तथा यत:, कोन्द्र सरकार ने मामले के सभी पहलुओं पर प्र्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान-2021 में संशोधन करने का निर्णय लिया है ।
- 3. अतः, अब, उवत अधिनियम के खण्ड 11-ए के उप-खण्ड (2) द्वारा प्रदत्त शिवतयों का प्रयोग करते हुए, केन्द्र सरकार, भारत के सजपन्न में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उवत मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती है :-- संशोधन :

जोन "डी" में राउज एवेन्यू, होनदयाल उपाध्याय मार्ग, नई दिल्ली पर 2 एकड़ (0.8 हेक्टे) भाप वाले निम्नलिखित क्षेत्र को भू-उपयोग को निम्नलिखित विवरण अनुसार परिवर्षित किया जाए :—

स्थिति .	क्षेत्र	भू-उपयोग (एम पी डी-2021)	परिवर्तित भू-उपयोग	सीमाएं
राउज एथेन्यू, दोनदयाल उपाध्याय मार्ग	0.8 हेस: (2 एकड़)	ं सरकारी कार्यालय	सरकारी और अर्ध- सरकारी सुविधाएं	पृत्रं : सड्क (२० मीटर मार्गाधिकार) पश्चिम : पॉकेट १ (सरकारी उपयोग) उत्तर : कोटला रोड (३०.४८ मीटर मार्गाधिकार) दक्षिण : दीनदयाल उपाध्याय मार्ग (३6.58 मीटर मार्गाधिकार)
	• .•			[सं. के-13011/12/2007-डी डी आई बी

4535 Gir2007

्रमी. के. सांतरा, अवर सचिव

(1)

# MINISTRY OF URBAN DEVELOPMENT

### (Delhi Division)

### NOTIFICATION

New Delhi, the 12th November, 2007

- S.O. 1907(E).—Whereas, cartain modifications which the Central Government proposed to make in the Master Plan for Delhi-2021 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 1721(E) dated 8th October, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.
- 2. Whereas, objections/suggestions received with regard to the proposed modification were duly considered by the competent authority and whereas the Central Government, after carefully considering all aspects of the matter, have decided to modify the Master Plan for Delhi-2021.
- 3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following, modification in the said Master Plan for Delhi- 2021 with effect from the date of Publication of this Notification in the Gazette of India:---

### Medification:

The land use of the following area measuring 2 acres (0.8 ha.) at Rouse Avenue, DDU Marg, New Delhi in Zone "D" be changed as per description listed below:

ation Area	Land Use (MPD-2021)	Land Use Changed	Boundaries
se Àveane, 0.8 ha. J Marg (2 acre	Government Office	Public and Semi- Public Facilities	East: Road (20 m R/W) West: Pocket 9 (Govt. Use) North: Kotla Road (30.48 m R/W) South: Deen Dayal Upadhaya Marg (36.58 m R/W)
			South: Deen Dayal

P. K. SANTRA, Under Secy.

No. K-12016/6/2003- DDIB Government of India Ministry of Urban Development (Delhi Division)

Nirman Bhavan, New Delhi Dated the December 5, 2007

Extraordinary Gazette Notification-circulation Subject: 1964(A) of Notification S.O. No. Constitution regarding 20.11.2007 Heritage Conservation Committee (HCC).

A copy of Notification dated 20th November, 2007 published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

(P.K. Santra) Under Secretary Telefax.: 23061681/ 23061006 /23061478 .

To

Vice Chairman, DDA, Vikas Sadan, New Delhi

Principal Commissioner-cum-Secretary, DDA, 2. Sadan, New Delhi

The Commissioner (Planning), DDA, Vikas Minar, New

The Commissioner (LD), DDA, Vikas Sadan, New Delhi 4.

The Commissioner (LM), DDA, Vikas Sadan, New Delhi The Principal Secretary (UD), GNCTD, Delhi. 5.

The Chief Planner, TCPO, IP Estate, New Delhi.

The L&DO, Nirman Bhawan, New Delhi. 7.

The Secretary, NDMC, Palika Kendra, New Delhi. 8.

9.

The Commissioner, MCD, Town Hall, Delhi. The Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi

Copy to ::

PS to UDM / PS to MoS (UD) / Sr. PPt to Secy.(UD) / PS to JS



EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 1242]

नई दिल्ली, शुक्रवार, अक्तूबर 12, 2007/आश्विन 20, 1929

NEW DELHI, FRIDAY, OCTOBER 12, 2007/ASVINA 20, 1929

शहरी विकास मंत्रालय (दिल्ली प्रभाग) अधिसूचना

नई दिल्ली, 12 अवतूर्वर, 2007

का,आ, 1748(अ).--यतः, यहां रोचे उल्लिखित क्षेत्र के संबंध में दिल्ली के मास्टर प्लान में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खंड-44 के प्रावधानों के अनुसार दिल्ली विकास प्राधिकरण द्वारा दिनांक 26 सितम्बर, 2006 की सं. का.आ. 2151(अ) की सार्वजनिक सूचना द्वारा भारत के असाधारण राजपत्र में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खंड 11-ए के उप-खंड (3) द्वारा यथा अपेक्षित आपत्तियां/सुझाव आमंत्रित किए गए।

. 2. यतः, प्रस्तावित संशोधन के संबंध में सक्षम प्राधिकारी ने आपत्तियों/सुझावों पर ध्यानपूर्वक विचार किया तथा यतः केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली कं मास्टर प्लान-2021 में र गोधन करने का निर्णय लिया है।

3. अतः, अब उक्त अधिनियम के खंड 11-ए के उप-खंड (2) द्वारा प्रदत्त शवितयों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उनत मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती 計

''जोन 'ओ' बुलन्द मस्जिद क्षेत्र (शास्त्री पार्क एवसटेंशन) के 1.70 हैक्टेयर कें क्षेत्रफल के निम्नलिखित मृ-उपयोग में निम्नलिखित विवरण के अनुसार परिवर्तन किया जाता है :--

भू-उपयोग सीमाएं क्षेत्रफल . भू-उपयोग जिसमें (एमपोडी-.परिवर्तित 2021) की गई (5) (4) (3) (1) सार्वजनिक उत्तरः 'कृषि एवं यमुना नदी 1.70 आ,ग्रं.ब.अ. व अर्द जलाशय' तल जोन हैक्टेयर तथा जी.टी. रोड सार्वजनिक 'ओ' में को जोड़ने वाली सुविधाएं जुलंद मस्जिद नई सड़क क्षेत्र (शास्त्री दक्षिण : ्पार्क एक्सटेशन) अनाधकत में निर्मित कालोनी पूर्व : अनधिकृत निर्मित कालोनी/ 9 मी. चौड़ी प्रस्तावित सड्क पश्चिम : डीएमआरसी भृमि, एचटी ्लाइन/13.5 भी. चौड़ी प्रस्तावित -संड्क

[स. के-13011/3/2006-डीडीआई-जी] पी. के. सांतरा, अवर सृचिव

4183 GI/2007

# MINISTRY OF URBAN DEVELOPMENT (DELHI DIVISION)

## NOTIFICATION

New Delhi, the 12th October, 2007

S.O. 1748(II). — Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2021 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 2151(E), dated 26th December, 2006 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.

2. Whereas objections/suggestions received with regard to the proposed modification were duly considered by the competent authority and whereas the Central Government, after carefully considering all aspects of the matter, have decided to modify the Master Plan for Delhi -2021.

3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi-2021 with effect from the date of Publication of this Notification in the Gazette of India.

### Modification:

The land use of an area measuring 1.70 ha, of land in Buland Masjid area (Shastri Park Extension) in Zone 'O' is changed as per description listed below:-

changed as ber			Roundaries
(1) (2) Buland. 1.70 Masjid ha. area (Shastri Park: Extension) in River Yamuna	Land use (MPD- 2021)	Land use changed to (4)  c Public and semi-public facilities	linking ISBT and G.T. Road South: Built up unauthorised colony unauthorised
Yamuna Bed Zone 'O'			colony/9M wide proposed Road West: DMRC land, HT Line/ 13.5M wide proposed Road

[No. K-13011/3/2006-DDIB]

P. K. SANTRA, Under Secy.

No. K-12016/2/2006- DDIB Government of India Ministry of Urban Development (Delhi Division).

बैठक कक्ष, दि.वि.प्रा.

Meeting Cell, D.D.A.

Nirman Bhavan, New Delhi Dated the December 7, 2007

Subject: The National Capital Territory of Delhi Laws (Sps ial Provisions) Act 2007 (43 of 2007) dated

A copy of above Act published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

(P.K. Santra) Under Secretary Telefax.: 23061681/ 23061006 /23061478

To

- Vice Chairrian, DDA, Vikas Sadan, New Delhi Principal ( )mmissioner-cum-Secretary, DDA, Vikas Sadan, 3.
- Commissio er (Planning), DDA, Vikas Minar, New Delhi Commissio er (LD), DDA, Vikas Sadan, New Delhi 4.
- Commissio er (LM), DDA, Vikas Sadan, New Delhi 5.
- Principal Secretary (UD), GNCTD, Delhi. 6.
- Chief Planr r, TCPO, IP Estate, New Delhi. 7. 8.
- L&DO, Nirr an Bhawan, New Delhi.
- Secretary, DMC, Palika Kendra, New Delhi. Commissio er, MCD, Town Hall, Delhi. 10.
- Secretary, VUAC, India Habitat Centre, Zone-6, Core-F, Lodhi

Copy to :-

PS to UDM / PS o MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS



असाधारप

**EXTRAORDINARY** 

भाग II — खण्ड 1

PART II - Section 1

प्राधिकार से प्रकाशित

PUBLISHED BY AUTHORITY

सं॰ 52] नई दिल्ली, गुरूबार, दिसम्बर 6, 2007 / अग्रहायण 15, 1929 No. 52] NEW DELHI, THURSDAY, DECEMBER 6, 2007 /AGRAHAYANA 15, 1929

इस भाग में भिन्न पृष्ठ संख्या दी जाती है जिससे कि यह अलग संकलन के रूप में रखा जा सके। Separate paging is given to this Part in order that it may be filed as a separate compilation.

### MINISTRY OF LAW AND JUSTICE

(Legislative Department)

New Delhi, the 6th December, 2007/Agrahayana 15, 1929 (Saka)

The following Act of Parliament received the assent of the President on the 5th December, 2007, and is hereby published for general information:—

# THE NATIONAL CAPITAL TERRITORY OF DELHI LAWS (SPECIAL PROVISIONS) ACT, 2007

No. 43 of 2007

[5th December, 2007]

An Act to make special provisions for the National Capital Territory of Delhi for a further period up to 31st December, 2008 and for matters connected therewith or incidental thereto.

Whereas there had been phenomenal increase in the population of the National Capital Territory of Delhi owing to migration and other factors resulting in tremendous pressure on land and infrastructure leading to encroachment or unauthorised developments which are not in consonance with the concept of planned development as provided in the Master Plan of Delhi, 2001 and the relevant Acts and building bye-laws made thereunder;

And whereas the Master Plan of Delhi, 2001 has been extensively modified and notified by the Central Government on 7th February, 2007 with the perspective for the year 2021 keeping in view the emerging new dimensions in urban development vis-a-vis the social,

5268GI

שיוערוויג

14/12

ok M.

financial and other ground realities;

AND WHEREAS the Master Plan of Delhi with the perspective for the year 2021 specifically provides for strategies for housing for urban poor as well as to deal with the informal sector;

AND WHEREAS a revised policy for relocation and rehabilitation of slum dwellers in the National Capital Territory of Delhi is also under consideration of the Central Government;

And whereas a strategy and a scheme has been prepared by the local authorities in the National Capital Territory of Delhi for regulation of urban street vendors in accordance with the National Policy for Urban Street Vendors and the Master Plan for Delhi, 2021;

AND WHEREAS some time is required for making orderly arrangements in accordance with the revised policy for relocation and rehabilitation of slum dwellers of Delhi as well as for putting in place the scheme for regulation of urban street vendors in terms of the Master Plan of Delhi, 2021 and also the national policy in this regard;

AND WHEREAS the Central Government has considered and finalised a policy regarding regularisation of unauthorised colonies, village abadi area and its extension, as existed on the 31st day of March, 2002 for which the guidelines are being framed;

And whereas the Central Government require time to take a considered view on the policy regarding existing farm houses involving construction beyond permissible building limits and regarding schools, dispensaries, religious institutions and cultural institutions, storages, warehouses and godowns used for agricultural inputs or produce (including dairy and poultry) in rural areas built on agricultural land, inter alia, in the light of recommendations of the Expert Committees constituted by the Central Government in the year 2006;

AND WHEREAS the National Capital Territory of Delhi Laws (Special Provisions) Ordinance, 2007 for making special provisions for the areas of the National Capital Territory of Delhi for a further period of one year promulgated on 4th July, 2007 will cease to operate from the 21st day of September, 2007;

Ord. 6 of 2007.

And whereas the National Capital Territory of Delhi Laws (Special Provisions) Bill, 2007 introduced in Parliament to replace the National Capital Territory of Delhi Laws (Special Provisions) Ordinance, 2007 could not be taken up for consideration and passing since Ord. 6 of 2007. Parliament adjourned sine die;

AND WHEREAS it is expedient to have a law in terms of the Master Plan of Delhi, 2021, in continuation of the said Act for a period up to 31st December, 2008 to provide temporary relief and to minimise avoidable hardships and irreparable loss to the people of the National Capital Territory of Delhi against any action by the concerned agency in respect of persons covered by the policies referred to above which are expected to be finalised within the period so extended;

Be it enacted by Parliament in the Fifty-eighth Year of the Republic of India as follows:—

- 1. (1) This Act may be called the National Capital Territory of Delhi Laws (Special Provisions) Act, 2007.
  - (2) It extends to the National Capital Territory of Delhi.
  - (3) It shall be deemed to have come into force on the 19th day of May, 2007.
- (4) It shall cease to have effect on the 31st day of December, 2008 except as respects things done or omitted to be done before such cesser, and upon such cesser section 6 of the General Clauses Act, 1897, shall apply as if this Act had then been repealed by a Central Act.

10 of 1897.

Definitions.

Short title,

commencement and

extent,

duration.

- 2. (1) In this Act, unless the context otherwise requires,—
- (a) "building bye-laws" means bye-laws made under section 481 of the Delhi Municipal Corporation Act, 1957 or the bye-laws made under section 188, sub-section 61 of 1957.

Punjab Act 3 of 1911.
61 of 1957.

(3) of section 189 and sub-section (1) of section 190 of the Punjab Municipal Act, 1911, as in force in New Delhi or the regulations made under sub-section (1) of section 57 of the Delhi Development Act, 1957, relating to buildings;

66 of 1957

(b) "Delhi" means the entire area of the National Capital Territory of Delhi except the Delhi Cantonment as defined in clause (11) of section 2 of the Delhi Municipal Corporation Act, 1957;

66 of 1957. 44 of 1994.

61 of 1957.

(c) "encroachment" means unauthorised occupation of Government land or public land by way of putting temporary, semi-permanent or permanent structure for residential use or commercial use or any other use;

(d) "local authority" means the Delhi Municipal Corporation established under the Delhi Municipal Corporation Act 1967, and the Delhi Municipal Corporation and the Delhi Municipal Cor

the Delhi Municipal Corporation Act, 1957, or the New Delhi Municipal Council established under the New Delhi Municipal Council Act, 1994, or the Delhi Development Authority established under the Delhi Development Act, 1957, legally entitled to exercise control in respect of the areas under their respective jurisdiction;

61 of 1957.

(e) "Master Plan" means the Master Plan for Delhi with the perspective for the year 2021 notified, vide the notification number S.O.141(E), dated 7th February, 2007 under the Delhi Development Act, 1957;

(f) "notification" means a notification published in the Official Gazette;

(g) "punitive action" means action taken by a local authority under the relevant law against unauthorised development and shall include demolition, sealing of premises and displacement of persons or their business establishment from their existing location, whether in pursuance of court orders or otherwise;

(h) "relevant law" means in case of-

61 of 1957.

(i) the Delhi Development Authority, the Delhi Development Act, 1957;

66 of 1957.

(ii) the Municipal Corporation of Delhi, the Delhi Municipal Corporation Act, 1957; and

44 of 1994.

(iii) the New Delhi Municipal Council, the New Delhi Municipal Council Act, 1994;

(i) "unauthorised development" means use of land or use of building or construction of building or development of colonies, village abadi area and its extension, carried out in contravention of the sanctioned plans or without obtaining the sanction of plans, or in contravention of the land use as permitted under the Master Plan or Zonal Plan or layout plan, as the case may be, and includes any encroachment.

61 of 1957. 66 of 1957. 44 of 1994. (2) The words and expressions used but not defined herein shall have the meanings respectively assigned to them in the Delhi Development Act, 1957, the Delhi Municipal Corporation Act, 1957 and the New Delhi Municipal Council Act, 1994.

3. (1) Notwithstanding anything contained in any relevant law or any rules, regulations or bye-laws made thereunder, the Central Government shall before the expiry of this Act, take all possible measures to finalise norms, policy guidelines and feasible strategies to deal with the problem of encroachment or unauthorised development in the form of encroachment by slum dwellers and Jhuggi-Jhompri clusters, hawkers and urban street vendors, unauthorised colonies, village abadi area and its extension, existing farm houses involving construction beyond permissible building limits and schools, dispensaries, religious institutions, cultural institutions, storages, warehouses and godowns used for agricultural inputs or produce (including dairy and poultry) in rural areas built on agricultural land, as mentioned below:

Enforcement to be kept in abeyance.

111/11/

---

(a) policy for relocation and rehabilitation of slum dwellers and *Jhuggi-Jhompri* clusters in accordance with provisions of the Master Plan of Delhi, 2021 to ensure development of Delhi in a sustainable, planned and humane manner;

- (b) strategy for regulation of urban street vendors in consonance with the national policy for urban street vendors and hawkers as provided in the Master Plan of Delhi, 2021;
- (c) scheme containing guidelines for regularisation of unauthorised colonies, village *abadi* area and its extension, as existed on the 31st day of March, 2002, and where construction took place even beyond that date and up to the 8th day of February, 2007.
- (d) policy regarding existing farm houses involving construction beyond permissible building limits; and
- (e) policy regarding schools, dispensaries, religious institutions, cultural institutions, storages, warehouses and godowns used for agricultural inputs or produce (including dairy and poultry) in rural areas built on agricultural land.
- (2) Subject to the provisions contained in sub-section (1) and notwithstanding any judgment, decree or order of any court, status quo
  - (i) as on the 1st day of January, 2006 in respect of encroachment or unauthorised development; and
  - (ii) in respect of unauthorised colonies, village *abadi* area and its extension, which existed on the 31st day of March, 2002 and where construction took place even beyond that date and up to the 8th day of February, 2007, mentioned in subsection (1),

### shall be maintained.

- (3) All notices issued by any local authority for initiating action against encroachment or unauthorised development referred to in sub-section (1), shall be deemed to have been suspended and no punitive action shall be taken till the 31st day of December, 2008.
- (4) Notwithstanding any other provision contained in this Act, the Central Government may, at any time before the 31st day of December, 2008, withdraw the exemption by notification in respect of encroachment or unauthorised development mentioned in sub-section (2) or sub-section (3), as the case may be.

Provisions of this Act not to apply in certain cases.

- 4. During the period of operation of this Act, no relief shall be available under the provisions of section 3 in respect of the following encroachment or unauthorised development, namely:—
  - (a) encroachment on public land except in those cases which are covered under clauses (a), (b) and (c) of sub-section (1) of section 3;
  - (b) removal of slums and Jhuggi-Jhompri dwellers, hawkers and urban street vendors, unauthorised colonies or part thereof, village abadi area and its extension, in accordance with the relevant policies approved by the Central Government for clearance of land required for specific public projects.

Power of Central Government to give directions.

Repeal and savings.

- 5. The Central Government may, from time to time, issue such directions to the local authorities as it may deem fit, for giving effect to the provisions of this Act and it shall be the duty of the local authorities to comply with such directions.
- 6. (1) The National Capital Territory of Delhi Laws (Special Provisions) Second Ordinance, 2007 is hereby repealed.

Ord.7 of 2007.

Ord, 7 of 2007.

10

(2) Notwithstanding such repeal, anything done or any action taken under the National Capital Territory of Delhi Laws (Special Provisions) Second Ordinance, 2007, shall be deemed to have been done or taken under the corresponding provisions of this Act.

K.N. CHATURVEDI, Secy. to the Govt. of India

PRINTED BY THE MANAGER, GOVT. OF INDIA PRESS MINTO ROAD, NEW DELHIAND PUBLISHED BY THE CONTROLLER OF PUBLICATIONS, DELHI—2007.

MGIPMRND-5268UD(GI)(S-1)-06-12-2007.

01/1/2 UN 1/12 16 107/2

DD(P&c)(Mc)/consu-OC () Stone



No. K-20014/2/2007-DDIIA
Government of India
Ministry of Urban Development
(Delhi Division)

Nirman Bhawan, New Delhi-110 011 Dated the 09th January, 2008

То

The Vice-Chairman,
Delhi Development Authority,
Vikas Sadan,
INA Colony,
New Delhi-110 023

[Attention: Shri Prahlad Singh, Director (LC)]F

Sub:

Cost Benefit Analysis (CBA) of Narela and determination of predetermined rates for various land uses in Narela project for the year 2007-2008.

Sir,

I am directed to refer to your letter No. F.4(23)06/AO(P)/DDA/47 dated 11.7.2007, on the subject noted above, and to enclose a copy of the Notification regarding pre-determined rates for various land uses in Narela for information and further necessary action.

Encl.: As above

Yours faithfully,

(S.N. GUPTA)
Under Secretary to the Govt. of India

2 # 2306 1478

Copy along with a copy of Notification to the DDA [Member (Finance)/Principal Commissioner-cum-Secretary/Commissioner (LD)], Vikas Sadan, INA Colony, New Delhi for information and necessary action.

Under Secretary to the Govt. of India

DD/R 10/

Y-celif Ass T

1071/m

27-10 8 24-10-10 8 27-10-10 8

TOLLOS

# (भारत के राजपत्र के भाग-।। खण्ड 3 उपखण्ड(i)में प्रकाशनार्थ)

सं0 20014/2/2007-डीडी।।ए भारत सरकार शहरी विकास मंत्रालय

निर्माण भवन, नई दिल्ली-110011, दिनांकः ०१ ०। २००८

# अधिसूचना

जी.एस.आर.सं....... दिल्ली विकास प्राधिकरण (नज़ूल भूमि विकास का निपटान) नियम, 1981, के नियम 2(1) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार विभिन्न प्रयोगों के लिए पूर्व निर्धारित प्रभार योग्य दरों को एतद्द्वारा अधिसूचित करती है।

1. 2.	भूमि की श्रेणी सीजीएचएस के लिए भूमि वैकल्पिक भूखंड	2007-2008 के लिए नरेला के लिए अनुमोदित पूर्व निर्धारित दरें (प्रति वर्ग मी0) 7602.00 6108.00 रु0 (आंतरिक विकास की लागत एवं प्रयोग और अधिभोग प्रभार शामिल हैं )
3. (ক) (ख) (ম) (ঘ)	डीडीए आवासीय स्कीम एसएफएस एमआईजी एलआईजी ईडब्ल्यूएस	7602.00 रू0 6335.00 रू0 3801.00 रू0 2534.00 रू0 (फ्लैटों की बिक्री लागत निकालते समय आंतरिक विकास लागत भी जोड़ी जाय)
4.	जे0जे0 स्क्वेटर्स (पुनर्वास)	22.90 लाख रू0 प्रति एकड़ (आंतरिक विकास के दरों को छोड़कर जो एमसीडी के स्लम विभाग द्वारा निर्धारित किया जाना है)

ये दरें वित्तीय वर्ष 2007-08 के लिए प्रभावी है ।

(एस०एन० गुप्ता) अवर सचिव, भारत सरकार

सेवा में,

प्रवंधक, भारत सरकार मुद्रणालय, रिंग रोड, मायापुरी, नई दिल्ली ।



[To be published in Gazette of India, Part II-Section 3-sub-Section (i)]

No.K-20014/2/2007-DD IIA Government of India Ministry of Urban Development

> Nirman Bhawan, New Delhi Dated the 09th January, 2008

### **Notification**

G.S.R. No. \_\_\_\_\_ In exercise of powers conferred by Rule 2(I) of the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981, the Central Government hereby notify the pre-determined rates chargeable for different uses as under :-

Category of Land

pre-determined Approved rates for Narela for 2007-2008 (per sq. mtr.)

Land for CGHS 1.

Rs.7602.00

Alternative Plots

Rs.6108.00 (inclusive of cost of internal development and use and occupation charges)

**DDA Housing Schemes** 

(a) SFS

(c) LIG

(b) MIG

(d) EWS

Rs. 7602.00

Rs. 6335.00 Rs. 3801.00

Rs. 2534.00

(cost of internal development to be added while working out the disposal cost of flats)

J.J. Squatters (Resettlement)

Rs. 22.90 lakh per acre (excluding rates of internal development which is to be carried out by the Slum Deptt. of MCD)

These rates are effective for the financial year 2007-2008.

(S.N. Gupta)

Under Secretary to the Govt. of India

То

The Manager, Government of India Press Mayapuri, New Delhi-110064



### [To be published in Gazette of India -Part II-Section 3-Sub-section (i)]

No.K-20014/3/2007-DD IIA Government of India Ministry of Urban Development

> Nirman Bhawan, New Delhi Dated 09th January, 2008

### **NOTIFICATION**

\_\_\_ In exercise of powers conferred by Rule 2(I) of the Delhi G.S.R. No. \_ Development Authority (Disposal of Developed Nazul Land) Rules, 1981, the Central Government hereby notify the pre-determined rates chargeable for different uses as under: -Category of Land Approved pre-determined rates for Rohini Phase IV & V for 2007-2008 (per sq. mtr.) 1. Rohini Plots EWS 26 sqm. Rs. 4905.00 (b) Rs. 6193.00 LIG 32 sqm. (c) MIG 60 sqm. Rs. 10058.00 (inclusive of cost of internal development and use and occupation charges) Housing Scheme **EWS** (a) Rs. 2577.00 (b) LIG Rs. 3865.00 (c) MIG Rs. 6441.00 (d) SFS Rs. 7730.00 (cost of internal development to be added while working out the disposal cost of flats) 3. Alternative Plots Rs. 6193.00 (inclusive of cost of internal development and use and occupation charges) Land for CGHS Rs. 7730.00 J.J. Squatters (Resettlement) Rs. 22.90 lakh per acre (excluding rates of internal development which is to be carried out by the Slum Deptt. of MCD)

These rates are effective for the financial year 2007-2008.

(S.N. Gupta) Under Secretary to the Govt. of India

То

The Manager, Government of India Press Mayapuri, New Delhi-110064



### No. K-20014/3/2007-DDIIA Government of India Ministry of Urban Development (Delhi Division)

Nirman Bhawan, New Delhi-110 011 Dated the 09th January, 2008

То

The Vice-Chairman, Delhi Development Authority, Vikas Sadan, INA Colony, New Delhi-110 023

[Attention: Shri Prahlad Singh, Director(LC)]

Sub:

Cost Benefit Analysis of Rohini Phase IV & V and determination of pre-determined rates for various land uses in Rohini Phase IV & V project for the year 2006-2007.

Meeting Cell, D.C.

I am directed to refer to your letter No. F.4(25)06/AO(P)/DDA/49, dated the 11.7.2007, on the subject noted above, and to enclose a copy of the Notification regarding pre-determined rates for various land uses in Rohini Phase IV & V for information and further necessary action.

Encl.: As above

Yours faithfully,

(S.N. GUPTA) Under Secretary to the Govt. of India **2** # 2306 1478

Copy along with a copy of Notification to the DDA [Member (Finance)/Principal Commissioner-cum-Secretary/Commissioner (LD)], Vikas Sadan, INA Colony, New Delhi for information and necessary action.

Under Secretary to the Govt. of India

# (भारत के राजपत्र के भाग-।। खण्ड 3 उपखण्ड(i)में प्रकाशनाधी

सं० २००१४/३/२००७-डीडी।।ए भारत सरकार शहरी विकास मंत्रालय 80000

निर्माण भवन, नई दिल्ली-110011, दिनांक: 09.01.2008

# अधिसूचना

जी.एस.आर.सं...... दिल्ली विकास प्राधिकरण (नज़ूल भूमि विकास का निपटान) नियम, 1981, के नियम 2(1) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार विभिन्न प्रयोगों के लिए पूर्व निर्धारित प्रभार

4116	विश्व का एतद्द्वारा अधिसूचित करती है ।	पूर्व निधारित प्रभार		
भूमि	की श्रेणी	2007-2008 के लिए रोहिणी फेज-IV एवं V के वि		
1.	रोहिणी प्लाट	(प्रति वर्ग मी0)		
(ক) (ख) (ম)	ईडब्ल्यूएस 26 व0मी0 एलआईजी 32 व0मी0 एमआईजी 60 व0मी0	4905.00 रू० 6193.00 रू० 10058.00 रू० (आंतरिक विकास की लागत एवं प्रयोग और अधिभोग प्रभार शामिल)		
3.	आवासीय स्कीम			
	(क) ईडब्ल्यूएस (ख) एलआईजी (ग) एमआईजी (घ) एसएफएस	2577.00 रु0 3865.00 रु0 6441.00 रु0 7730.00 रु0 (फ्लैटों के बिक्री लागत पूरा करने के दौरान आंतरिक विकास के लागत को जोड़ा जाय)		
3.	वैकल्पिक प्लाट	6193.00 रु० (आंतरिक विकास की लागत एवं प्रयोग और अधिभोग प्रभार शामिल)		

सीजीएचएस के लिए भूमि 4.

7730.00 ২০

प्रभार शामिल)

5. जे०जे० स्क्वेटर्स (पुनर्वास)

22.90 लाख रू० प्रति एकड़ (आंतरिक विकास के दरों को छोड़कर जो एमसीडी के स्लम विभाग द्वारा निर्धारित किया जाना है)

ये दरें वित्तीय वर्ष 2007-08 के लिए प्रभावी है ।

(एस०एन० गुप्ता) अवर सचिव, भारत सरकार

सेवा में,

प्रबंधक, भारत सरकार मुद्रणालय, रिंग रोड, मायापुरी, नई दिल्ली।

No. N-11013/19/2006-DDIB No. K-13011/3/2004-DDIB Government of India Ministry of Urban Development (Delhi Division 1B)

> Nirman Bhawan, New Delhi Dated 7<sup>th</sup> January, 2008

Subject:

Notification Gazette -Extraordinary circulation of Notification (i) S.O. No. 2178(E) dated 28.12.2007 and (ii) S.O. No. 141(E) dated 1.1.2008.

चैठक कक्ष, दि.हि.प्रा Meeting Cell, D.D.A.

A copy each of Notification/Corrigendum dated 27.12.2007 and 1.1.2008 referred to above and published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

(P.K. Śańtra) **Under Secretary** Telefax.: 23061681

To

Vice Chairman, DDA, Vikas Sadan, New Delhi

2. Principal Commissioner-cum-Secretary, DDA, Sadan, New Delhi

3. Commissioner (Planning), DDA, Vikas Minar, New Delhi 4. Commissioner (LD), DDA, Vikas Sadan, New Delhi

5. Commissioner (LM), DDA, Vikas Sadan, New Delhi

6. Principal Secretary (UD), GNCTD, Delhi. 7. Chief Planner, TCPO, IP Estate, New Delhi.

8. The L&DO, Nirman Bhawan, New Delhi.

9. Secretary, NDMC, Palika Kendra, New Delhi.

10. Commissioner, MCD, Town Hall, Delhi.

11. Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Ledhi Road, New Delhi

Copy to :-. PS to UDM / PS to MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS

रजिस्ट्री सं॰ डी॰ एल॰-33004/99

REGD. NO. D. L.-33004/99



असाधारण EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 1595] No. 1595] नई दिल्ली, बृहस्पतिवार, दिसम्बर 27, 2007/पौष 6, 1929 NEW DELHI, THURSDAY, DECEMBER 27, 2007/PAUSA 6, 1929

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना

नई दिल्ली, 27 दिसम्बर, 2007

का.आ. 2187(अ).— यतः यहां नीचे उल्लिखित क्षेत्र के संबंध में दिल्ली मास्टर प्लान- 2021 में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 ( 1957 का 61) के खण्ड-44 के प्रावधानों के अनुसार दिनांक 1 अक्टूबर, 2007 की का.आ.सं.1690(ई) की सार्वजनिक सूचना द्वारा भारत के असाधारण राजपत्र में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उप खण्ड (3) द्वारा यथा अपेक्षित आपित्तयां/सुझाव आमंत्रित किए गए।

- 2. यतः प्रस्तावित संशोधन के संबंध में प्राप्त आपत्तियों /सुझावों पर सक्षम प्राधिकारी द्वारा यथोचित विचार किया गया तथा यतः केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान- 2021 में संशोधन करने का निर्णय लिया है ।
- 3. अतः, अब उक्त अधिनियम के खण्ड ।।-ए के उपखण्ड-2 द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वारा निम्निलिखत संशोधन करती है ।

(1)

5094 G1/2007

जोन "डी" में रेस कोर्स रोड(45 मीटर मार्गाधिकार) के 19668 वर्ग मीटर माप वाले निम्नलिखित क्षेत्र के संशोधन: भू-उपयोग को निम्नलिखित विवरण अनुसार परिवर्तित किया जाए :-

•	सू-उपजान कर र		į.	·	0.00
	स्थिति जोन "डी" में 45 मीटर मार्गाधिकार वाले रेस कोर्स रोड	<b>क्षेत्रफल</b> 19668 वर्ग मीटर	भू-उपयोग (एमपीडी-2021) सर्कुलेशन/रोड	परिवर्तित भू-उपयोग आवासीय ( प्रधान मंत्री के सरकारी आवास)	सीमाएं  पूर्व- मनोरंजनात्मक(जिम खाना कलब) पश्चिम- आवासीय (7 रेस कोर्स रोड कॉम्पलैक्स) उत्तर/पश्चिम- अकबर रोड और तीन मूर्ति मार्ग का चौराहा - दक्षिण- कलब रोड(36.57 मीटर मार्गाधिकार)
	1	1			

[फा.सं. के-13011/3/2004-डी डी I बी] पी. के. सांतरा, अवर सचिव

# MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

# NOTIFICATION

New Delhi, the 27th December, 2007

- S.O. 2187(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2021 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide S.O. 1690 (E) dated Ist October 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi. Development Act, 1957 (61 of 1957) inviting objections/ suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.
- 2. Whereas objections/suggestions received with regard to the proposed modification were duly considered by the competent authority and whereas the Central Government, after carefully considering all aspects of the matter, have decided to modify the .Master Plan for Delhi 2021.
- Now, therefore, in exercise of the powers conferred by subsection (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi- 2021 with effect from the date of Publication of this Notification in the Gazette of India.

# Modification:

The land use of an area measuring 19668 sqm of Race Course Road (45 m R/W) in Zone-D is changed as per description listed below:-

Location	Area	Land use (MPD- 2021)	Land Use changed to	Boundaries
1	2	3	4	5
Race Course Road 45m R/W in Zone-D	19668 sqm	Circulation/ Road	Residential (Official Residence of the Prime Minister)	East - Recreational (Gymkhana Club) West - Residential (7 Race Course Road Complex) North/West - Junction of Akbar Road and Teen Murti Marg South- Club Road 36.57m R/W

[F. No. K-13011/3/2004-DDIB]
P.K. SANTRA, Under Secy.

रजिस्ट्री सं॰ डी॰ एल॰-33004/99

REGD. NO. D. L.-33004/99

# HRA AN UNIVERSITE OF India

EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii)

PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित

PUBLISHED BY AUTHORITY

सं. 6] No. 6]

नई दिल्ली, मंगलवार, जनवरी 1, 2008/पौष 11, 1929

Ì

NEW DELHI, TUESDAY, JANUARY 1, 2008/PAUSA 11, 1929

## MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

# CORRIGENDUM

New Delhi, the 1st January, 2008

S.O. 6(E).—Reference is invited to Ministry of Urban Development's Extraordinary Gazette Notification No. S.O. 141(E) dated 7-2-2007 (issued from F. No. K-12011/1/2005-DDIB). In the English version of the said Notification, in note (i), under the column 'other controls' against Sl. Nos. (c) Hotel, below table 5.4:—Development Controls—Commercial Centres, for the numerics "5 10%", read "10%".

[No. N-11013/19/2006-DDIB]

P. K. SANTRA, Under Secy.

> Nirman Bhawan, New Delhi Dated 7<sup>th</sup> January, 2008

Subject:

Extraordinary Gazette Notification – circulation of Notification (i) S.O. No. 2178(E) dated 28.12.2007 and (ii) S.O. No. 141(E) dated 1.1.2008.

26/108

चैठक कथा, विविद्या Meeting Coll, DDA. A copy each of Notification/Corrigendum dated 27.12.2007 and 1.1.2008 referred to above and published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

(P.K. Śantra) Under Secretary Telefax.: 23061681

To

1. Vice Chairman, DDA, Vikas Sadan, New Delhi 2. Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi

3. Commissioner (Planning), DDA, Vikas Minar, New Delhi

4. Commissioner (LD), DDA, Vikas Sadan, New Delhi

5. Commissioner (LM), DDA, Vikas Sadan, New Delhi

6. Principal Secretary (UD), GNCTD, Delhi.

7. Chief Planner, TCPO, IP Estate, New Delhi.

8. The L&DO, Nirman Bhawan, New Delhi.

9. Secretary, NDMC, Palika Kendra, New Delhi.

10. Commissioner, MCD, Town Hall, Delhi.


11. Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi

Copy to :

PS to UDM / PS to MoS (UD) / Sr. PPS to Secy.(UD) / PS to JS (D&L)

patme DD (291)

10/1/200



रजिस्ट्री सं॰ डी॰ एल॰–33004/99

REGD. NO. D. L.-33004/99

# Heche Sazette of India

असाधारण EXTRAORDINARY

भाग II —खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 1595]

No. 1595

नई दिल्ली, बृहस्पतिवार, दिसम्बर 27, 2007/पौष 6, 1929 NEW DELHI, THURSDAY, DECEMBER 27, 2007/PAUSA 6, 1929

शहरी विकास मंत्रालय

( दिल्ली प्रभाग )

अधिसूचना

नई दिल्ली, 27 दिसम्बर, 2007

का,आ. 2187(२),— यतः यहां नीचे उत्लिखित क्षेत्र के संबंध में दिल्ली मास्टर प्लान- 2021 में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खण्ड-44 के प्रावधानों के अनुसार दिनांक 1 अक्टूबर, 2007 की का.आ.सं.1690(ई) की सार्वजनिक सूचना द्वारा भारत के असाधारण राजपत्र में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उप खण्ड (3) द्वारा यथा अपेक्षित आपत्तियां/सुझाव आमंत्रित किए गए।

- 2. यतः प्रस्तावित संशोधन के संबंध में प्राप्त आपत्तियों /सुझावों पर सक्षम प्राधिकारी द्वारा यथोचित विचार किया गया तथा यतः केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान- 2021 में संशोधन करने का निर्णय लिया है ।
- 3. अतः, अब उक्त अधिनियम के खण्डं ।।-ए के उपखण्ड-2 द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती है।

5094 GI/2007

(1)

संशोधन:

जोन "डी" में रेस कोर्स रोड(45 मीटर मार्गाधिकार) के 19668 वर्ग मीटर माप वाले निम्नलिखित क्षेत्र के भू-उपयोग को निम्नलिखित विवरण अनुसार परिवर्तित किया जाए :-

स्थिति	क्षेत्रफल	भू-उपयोग (एमपीडी-2021)	परिवर्तित भू-उपयोग	सीमाए
जोन "डी" में 45 मीटर मार्गाधिकार वाले रेस कोर्स रोड	19668 वर्ग मीटर	सर्कुलेशन/रोड	आवासीय ( प्रधान मंत्री के सरकारी आवास)	पूर्व- मनोरंजनात्मक (जिम खाना क्लब) पश्चिम- आवासीय (7 रेस कोर्स रोड कॉम्पलैक्स) उत्तर/पश्चिम- अकबर रोड और तीन मूर्ति मार्ग का चौराहा दक्षिण- क्लब रोड (36.57 मीटर मार्गाधिकार)

[फा.सं. के-13011/3/2004-डी डी I बी] पी. के. सांतरा, अवर सचिव

### MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

### **NOTIFICATION**

New Delhi, the 27th December, 2007

S.O. 2187(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi-2021 regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide S.O. 1690 (E) dated Ist October 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.

- 2. Whereas objections/suggestions received with regard to the proposed modification were duly considered by the competent authority and whereas the Central Government, after carefully considering all aspects of the matter, have decided to modify the Master Plan for Delhi 2021.
- 3. Now, therefore, in exercise of the powers conferred by subsection (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi- 2021 with effect from the date of Publication of this Notification in the Gazette of India.

# Modification:

The land use of an area measuring 19668 sqm of Race Course Road (45 m R/W) in Zone-D is changed as per description listed below:-

		_		description listed
Location 1	Area 2	Land use (MPD- 2021)	Land Use changed to	Boundaries
Race Course Road 45m R/W in Zone-D	19668 sqm		,	(Gymkhana Club)  West - Residential

[F. No. K-13011/3/2004-DDIB] P.K. SANTRA, Under Secy.

# **Modification:**

The land use of an area measuring 19668 sqm of Race Course Road (45 m R/W) in Zone-D is changed as per description listed below:-

Location 1	2	Land use (MPD- 2021)	Land Use changed to	Boundaries
Race Course Road 45m R/W in Zone-D	19668 sqm	Circulation/ Road		5  East - Recreational (Gymkhana Club)  West - Residential (7 Race Course Road Complex)  North/West - Junction of Akbar Road and Teen Murti Marg  South- Club Road 36.57m R/W

[F. No. K-13011/3/2004-DDIB] P.K. SANTRA, Under Secy.

रजिस्ट्री सं॰ डी॰ एल॰-33004/99

REGD. NO. D. L.-33004/99

# The Gazette of India

EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii)

PART II—Section 3—Sub-section (ii) प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं.: 6] No. 6]

नई दिल्ली, मंगलवार, जनवरी 1, 2008/पौष 11, 1929 NEW DELHI, TUESDAY, JANUARY 1, 2008/PAUSA 11, 1929

# MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

# CORRIGENDUM

New Delhi, the 1st January, 2008

S.O. 6(E).—Reference is invited to Ministry of Urban Development's Extraordinary Gazette Notification No. S.O. 141(E) dated 7-2-2007 (issued from F. No. K-12011/1/2005-DDIB). In the English version of the said Notification, in note (i), under the column 'other controls' against Sl. Nos. (c) Hotel, below table 5.4:—Development Controls—Commercial Centres, for the numerics "5 10%", read "10%".

[No. N-11013/19/2006-DDIB] P. K. SANTRA, Under Secy.



## No. K-20014/2/2007-DDIIA Government of India Ministry of Urban Development (Delhi Division)

Nirman Bhawan, New Delhi-110 011 Dated the 09th January, 2008

To

The Vice-Chairman, Delhi Development Authority, Vlkas Sadan, INA Colony, New Delhi-110 023

[Attention: Shri Prahlad Singh, Director (LC)]F

Cost Benefit Analysis (CBA) of Narola and determination of predetermined rates for various land uses in Narela project for the

yoar 2007-2008.

I am directed to refer to your letter No. F.4(23)06/AO(P)/DDA/47dated 11.7.2007, on the subject noted above, and to enclose a copy of the Notification regarding pre-determined rates for various land uses in Narela for information and further necessary action.

TOB Encl.: As above

Sir,

Yours falthfully,

(S.N. GUPTA)

Under Secretary to the Govt. of India **#** # 2306 1478

नैजना अन्य, विजीआ Date 11 08

Miching Cell, D.D.A. (Finance)/Principal Commissioner-cum-Secretary/Commissioner (LD)], Vikas Sadan, INA Colony, New Delhi for information and necessary action.

Under Secretary to the Govt. of India

Medup Assit

# (भारत के राजपत्र के भाग-।। खण्ड ३ उपखण्ड(i)में प्रकाणनार्थ)

RIO 20014/2/2007=원위10 भारत सरकार शहरी विकास मंत्रालय

िर्माण भवन, नई दिल्ली-110011, Rain: 09. 01.2008

# अधिसूचना

जी.एस.आर.सं...... दिल्ली विकास प्राधिकरण (नजूल भूमि विकास का निपदान) नियम, 1981, के नियम 2(1) हारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र शरकार विभिन्न प्रयोगी के लिए पूर्व निर्धारित प्रभार योग्य दरों को एतद्द्वारा अधिसूचित करती है ।

2007-2008 के लिए चरेला के लिए अनुमोदित पूर्व भूमिकी श्रेणी िर्धारित दरें (प्रति वर्ष भी०) 7602.00 सीजीएसएस के लिए भूमि ١. 0100.00 ₹0 तैकल्विक भूखंड (आंतरिक विकास की लागत एवं प्रयोग और अधिभोग 2. प्रभार शामिल है ) होटीए आवासीय रकीम 7002.00 ₹0 Burnh (<del>क</del>) 0335.0n 70 एमअपर्दशी (स्प) 3801,00 ₹0 एलआईजी (H)2534.00 ₹70 (फ्लैटों की विकी लागत निकालते समय आंतरिक ्रहरूयूएरा (u) विकास लागत भी जोड़ी जाय) जे०जे० स्ववेटर्स 22.00 लाख राठ प्रति एकद (आंतरिक विकास के तरों को छोड़कर जो एपसीदी के (पुनर्वास)

वे दर विद्याचि वर्ष 2007-08 वेड शिए प्रभावी है

*Elistam* <u>उत्ता</u> (एरा०ए १० गुप्ता)

अवर राचिय, भारत रारकार

रोवा में,

प्रवंधक, भारत सरकार मुद्रणालयः रिंग रोह, मायापुरी, नई दिल्ली ।

रलम विभाग द्वारा निर्धारित किया आना है)



[To be published in Gazette of India, Part II-Section 3-sub-Section (i)]

No.K-20014/2/2007-DD IIA Government of India Ministry of Urban Dovolopment

Nirman Bhawan, New Delhi Dated the 00th January, 2008

## Notification

O.S.R. No. \_\_\_\_\_\_ In exercise of powers conferred by Rule 2(I) of the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981, the Central Government hereby notify the pro-determined rates chargeable for different uses as under :-

Catogory of Land

pro-determined Approved rates for Narola for 2007-2008 (por eq. mtr.)

Land for CGHS

Rtt.7002.00

Alternative Piota 2.

Ru,0108.00 (inclusive of cost of internal development and use and occupation charges)

**DDA Housing Schemes** 3.

(a) SFS

(b) MIG

(c) LIG (d) EWS Rs. 7802.00

Rs. 6335.00

Rs. 3801.00 Rs. 2534.00

(cost of internal development to be added while working out the disposal cost of flats)

J.J. Squallors (Rosalllomoni)

Rs, 22,90 lakh per acre (excluding rates of internal development which is to be carried out by the Slum Deptt. o(MCD)

These rates are effective for the financial year 2007-2008.

(S.N. Gupta)

Under Secretary to the Govt. of India

The Manager, Government of India Press Mayapuri, Now Dolhl-110004



No. K-20014/3/2007-DDIIA
Government of India
Ministry of Urban Dovelopment
(Delhi Division)

Nirman Bhawan, New Delhi-110 011 Dated the 09th January, 2008

To

The Vicq-Chairman,
Delhi Development Authority,
Vikas Sadan,
INA Colony,
New Delhi-110 023

[Attention: Shrl Prahlad Singh, Director(LC)]

Sub

Gost Benefit Analysis of Rohini Phase IV & V and determination of pre-determined rates for various land uses in Rohini Phase IV & V project for the year 2006-2007.

Sir,

I am directed to refer to your letter No. F.4(25)06/AO(P)/DDA/49, dated the 11.7.2007, on the subject noted above, and to enclose a copy of the Notification regarding pre-determined rates for various land uses in Rohini Phase IV & V for information and further necessary action.

Encl.: As above

Yours faithfully,

**#** # 2306 1478

•

(S.N. GUPTA) Under Secretary to the Govt, of India

वैदक कहा, दिक्षिणा. Meeling Cell, D.D.A.

maki ni Deny No AA-

Copy along with a copy of Notification to the DDA [Momber (Finance)/Principal Commissioner-cum-Secretary/Commissioner (LD)], Vikas Sadan, INA Colony, New Delhi for information and necessary action.

Under Secretary to the Govt. of India

Rolling ?

DD Ope

Meetup 1881

Taplas

# (भारत के राजायत्र के भाग-11 खण्ड 3 उपखण्ड(1)में प्रकाशनार्थ)

अहरी विकास मंत्रालय भारत सरकार सहस्र विकास मंत्रालय

िन्याण भारत, नई विल्ली-110011, दिनोक्तः ०१.०। २००८

# अधिसूचना

जी.एस.आर.सं...... दिल्ली विकास प्राधिकरण (नजूल भूमि विकास का निपटान) नियम, 1081, के नियम 2(1) प्रारा प्रदत्ता शवितयों का प्रयोग करते हुए, केन्द्र सरकार विभिन्न प्रयोग के लिए पूर्व निर्धारित प्रभार योग्य दशें को एतद्वारा अधिसूचित करती हैं।

भूमि की श्रेणी

2007-2008 के लिए शेहिणी केज-IV एवं V के लिए अनुमोदित पूर्व निर्धारित वर (प्रति वर्ष मी०)

0/10b 02 гууразу (т)

00% 00,2004 00% 00,2010

अगियह २६ विद्याधिकात्र (१४)

10060.00 रण (आंतरिक विकास की लागत एवं प्रयोग और अधिमोग

रोगार भागाल)

3. आवासीय रकीम

(क) ६६८ (क) (क) एकआईजी 075 00,778S. 075 00,208C

(म) एलगाईगी (च) एलगाईगी

077 00.11418 077 00.0077

(घ) एराएकएस

(पलेटों के विकी लागत पूरा करने के धौरान आसरिक विकास के लागत को जीहा आय)

3. वैक्रिकिक प्लाट

0103.00 राठ (जांतरिक विकास की लागत एवं प्रयोग और अधियोग प्रभार शामिल)

4. शीजीपराएरा के लिए भूगि

7730.00 350

जे0जे**० स्वतं**टर्स (पुनर्वास)

ं 22,90 लाख राठ प्रति एकड् (आंतरिक विकास के बरों को छोड़कर जो एमसीही के रलग विभाग द्वारा निर्धारित किया जाना है)

ये वरें विस्तीय वर्ष 2007-08 के लिए प्रभावी है।

(एस०एन० गुप्सा) अवर राविव, भारत रारकार

रोवा में,

प्रवंधक, भारत संरकार मुत्रणालय, रिंग रोष्ठ, गांधापुरी, नई विल्ली।



### [To be published in Gazette of India -Part II-Section 3-Sub-section (I)]

No.K-20014/3/2007-DD IIA Government of India Ministry of Urban Dovolopment

> Nirman Bhawan, New Delhl Dated 09th January, 2008

### NOTIFICATION

G.S.R. No. \_\_\_\_\_ In exercise of powers conferred by Rule 2(I) of the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981, the Central

Government hereby notify the pre-determined rates chargeable for different uses as under: -Approved pre-determined rates for Category of Land Robbil Phono IV & V for 2007-2008 (per aq. mtr.) Robini Plots Ra. 4905.00 EWS 26 agm. Rs. 6193.00 LIG 32 sqm. Ra. 10058.00 MIG 60 agm. (inclusive of cost of internal development and use and occupation charges) Housing Schome Rn. 2577.00 **EWS** Rs. 3865.00 LIG Rs. 6441,00 MIG Rs. 7730.00 SFS (cost of internal development to be added while working out the disposal cost of flats) Ru, 6463,00 Alternative Plots (inclusive of cont of internal dovelopment and use and occupation charges) Ra. 7730.00 Land for CGHS

J.J. Squatters (Resettlément)

Rs. 22.90 lakh per acre (excluding rates of internal development which is to be carried out by the Slum Deptt. of MCD)

These ratio are effective for the financial year 2007-2008.

(S.N. Gupta) Under Secretary to the Govt. of India

The Manager, Government of India Press Mayapuri, Now Doll:110004



### No. K-20014/3/2007-DD IIA Government of India Sinistry of Urban Development

Ministry of Urban Development (Delhi Division)

Niman Bhawan, New Dolhl Dated the 09th January, 2008

ĵο

The Managor, Govt, of India Press, Mayapuri, Now Delhi.

Sub:-Publication of Pre-determined rates for Rohini Phase IV & V for 2007-08 in Part II Section — 3 Sub-section (I) in the Gazette of India.

Coty

I am directed to send herewith a copy each of the notifications (Hindl & English versions) (duly signed in ink) in respect of prodetermined rates of Robini Phase IV & V for the year 2007-08 for being published in the Gazette of India.

4. It is requested that the same may be published immediately and one sol each of the Gazette Notifications may be sent to this office for official use.

5. This may be treated as MOST IMMEDIATE. This issues with the approval of Hon'ble Urban Development Minister.

100 8 July 10 8

Yours fallhfully.

(S.N. Gupta)

में क्षेत्र पद्मा, विक्रिया, Managar

Meeting Cell, D.D.A. Encl.: - As above.

Under Secretary to the Govt, of India Tel.: 2306 1478

Duny Line A

-- Gopy to:

The Vice Chairman, DDA, Vikas Sadan, I.N.A, Now Dolhi,

2:" The Socretary to E.G. Dolhi.

3. Socretary (L & B), GNCTD, Dolhi.

4. Financo Mombor, DDA, Vikas Sadan, I.N.A, New Dolhi.

Commissioner (ED), DDA, Vikas Sadan, I.N.A, New Delhi.

M Maril

Million Di Dec 101

Under Secretary to the Govt, of India

# (भारत के राजायत्र के भाग-11 फान्ड 3 उपखण्ड(i)में प्रकाशनार्थ)

र्सं० २००१४/३/२००४ न्हीती ।।ए भारत सरकार एहरी विकास मंत्रालय

> निर्माण भगन, नई दिल्ली-110011, विगांकः ०१.०१.२००८

# अधिसूचना

जी.एस.आर.सं...... दिल्ली विकास प्राधिकरण (नज़ूल भूमि विकास का निपटान) नियम, 1081, के नियम 2(1) हारा प्रदत्त शवित्तयों का प्रयोग करते हुए, केन्द्र रास्कार विभिन्न प्रयोगों के लिए पूर्व निर्धारित प्रभार योग्य दर्श को एतव्हारा अधिसूचित कंरती है ।

भूति की श्रेणी

9007-2008 के लिए रीहिजी फिजा-IV एवं V के लिए अनुमोवित पूर्व निर्मारित वर

(प्रति वर्ग गी०)

रोहिणी प्लाट

ईवल्यूएस २० व०गी०

4005,00 700

एताविजी ३२ व्यवित (44)

0103.00 70

एगआईजी ७० क्लंगी०

10088.00 90

(अतिरिक विकास की लागत एवं प्रयोग और अधिओग प्रभार शामिल)

आवासीय स्कीम 3.

2577.00 350

**१, हरूल्यू ए**रा एलआईजी

3805,00 3080

एमआईजी

एराएफएरा

0441.00 ੴ

7730,00 300 (पलैटों के बिकी लागत पूरा करने के दौरान आंतरिक विकास के लागत को जीहा जाय)

वैक्रियक प्लाट Э,

OF 00.0010

(अविरिक विकास की लाग्त एवं प्रयोग और अधिमोग

प्रभार शामिल)

सीजीएराएस के लिए भूमि 4.

7730.00 370

ो०३० रक्वेटर्स (पुनर्वास)

22.90 लाख ७० प्रति एकद् र्थ ब्रिशिए कि एकार्स के वें के के कि वाकी करीताल रलम विभाग द्वारा निर्धारित किया जाना है)

ये वरें विकीय वर्ष 2007-08 के लिए प्रभावी है।

(एरा०एन० गुप्ता) अवर रावियं, भारत रारकार

रोवा में,

प्रबंधक, भारत सरकार मुक्रणालय, िरंग रोष्ठ, मायापुरी, नई विल्ली ।



(To be published in Gazette of India -Part II-Section 3-Sub-section (i)]

> No K-20014/3/2007-DD IIA Government of India Ministry of Urban Development

> > Nirman Bhawan, New Dolhi Dated 09<sup>th</sup> January, 2008

### NOTIFICATION

G.S.R. No. In exercise of powers conferred by Rule 2(I) of the Delhi Development Authority (Disposal of Developed Nazul Land) -Rules, 1981, the Central Government hereby notify the pre-determined rates chargeable for different uses as under: -

Category of Land

Approved pre-determined rates for Robini Phane IV & V for 2007-2008 (por eq. mtr.)

- Robini Plots
  - EWS 26 sqm.
- Rs. 4905.00 Rs. 6193.00

LIG 32 ngm.

Rs. 10058.00

- MIG '60 agm:

(inclusive of cost of Internal development and use and occupation charges)

- Housing Scheme 2.
  - **EWS** 
    - LIG
  - MIG
  - SES

- Rn. 2577.00 Rs. 3805,00
- Rs. 6441.00
- Ro. 7730.00

(cost of internal development to be added while working out the disposal cost of flats)

Alternative Plots

(inclusive of cont of Internal development and use and occupation charges)

Rn. 6193.00

Land for CGHS

Rs. 7730.00

- J.J. Squalters (Rosottlement)
- Ra. 22,00 lakh per acre (excluding rates of internal development which is to be carried out by the Slum Deptt.

Under Secretary to the Govt. of India

of MCD).

These rates are effective for the lineacial year 2007-2008.

(S.N. Gupta)

The Manager, Government of India Press Mayapuri, Now Dolhi-110064



# No. K-20014/2/2007-DD IIA Government of Indla Ministry of Urban Development (Dolhi Division)

Nirman Bhawan, Now Delhi Dated the 09th January, 2008

10

The Manager, Govl. of India Pross, Mayapuri, New Delhi.

Sub:- Publication of Pre-determined rates for Narela for 2007-08 in Part Il Section – 3 Sub-section (I) in the Gazette of India.

I am directed to send herewith a copy each of the notifications (Hindi & English vorsions) (duly signed in ink) in respect of prodetermined rates of Narola for the year 2007-08 for being published in the Gazette of India.

It is requested that the same may be published immediately and one set each of the Gazette Notifications may be sont to this office for official uso.

This may be treated as MOST IMMEDIATE. This issues with the approval of Hon'ble Urban Development Minister.

' (S.N. Gupta)

वैतेक कथा, वि.वि.धाः Meeting Cell, D.D.A.

Encl.: As above.

Under Secretary to the Govt. of India Tel.: 2306 1478

Copy lo:

The Vice Chairman, DDA, Vikas Sadan, I.N.A, New Delhi,

The Socretary to L.G. Dolhi.

Secretary (L. & B), GNCID, Delhi: 3.

Finance Member, DDA, Vikas Sadan, I.N.A, New Delhi.

Commissioner (LD), DDA, Vikás Sadan, I.N.A, New Dolhi.

Under Secretary to the Govt, of India

# (भारत के पाजायत्र के भाग-।। प्राण्ड ३ अवकाष(।) में प्रतावानाथी)

(io 20014/2/2007-취취 III भारत शरकार सहरी विकास मेत्रालय

िर्माण भवन, नए विल्ली-110011, Parim: 09. 01.2008

# अधिसूचना

जी.एस.आर.सं...... दिल्ली विकास प्राधिकरण (नजूल भूमि विकास का निपटान) नियम, 1981, के ियम 2(1) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र रारकार विभिन्न प्रयोगों के लिए पूर्व निर्धारित प्रभार योग्य दशें को एतद्वारा अधिसूचित करती है ।

2007-२००८ के लिए नरेला के लिए अनुमोबित पूर्व . मूमिकी श्रेणी निधारित वरें 🙄 (प्रति वर्ग मी०) शीजीएचएस के लिए भूमि 7002,00 1. 07 00.8010 वैक्वरिपक भूखंड 2, (आंतरिक विकास की लागत एवं प्रयोग और अधिगोग प्रभार कामिल है ) दीहीए आवासीय रकीम J. 7002.00 ₹0 (15) एसएकएस एमआईजी 6335.00 ₹0 (W) 3801.00 ₹50 एलआईजी 2634.00 ₹50 *६६व*स्यूएस (फ्लैटो की विक्री लागत निकासते समय आंतरिक विकास सामत भी ओड़ी जाय) जे०जे० स्क्वेटर्स 22.00 लाख २०० प्रति एकड्

ये दरें वित्तीय वर्ष 2007-08 के लिए प्रभावी है

(एरा०एन० गुप्सा)

अंधर राजिव, भारत रारकार


(आंतरिक विकास के दर्श को छोड़कर जो धारीबी के


रलम विभाग द्वारा निर्धारित किया जाना है)

रोवा में,

(पुनर्वास)

प्रशंधका, भारत रारकार मुद्रणालयं, रिंग रोढ, मावापुरी, नई दिल्ली ।







[To be published in Gazette of India, Part II:Section 3-sub-Section (I)]

No K-20014/2/2007-DD IIA Government of India Ministry of Urban Development

Nirman Bhawan, New Dolhi Dated the 09<sup>th</sup> January, 2008

#### Notification

G.S.R. No. \_\_\_\_\_\_ In exercise of powers conferred by Rule 2(I) of the Delhi Development Authority (Disposal of Developed Nazul Land) Rules, 1981, the Central Government hereby notify the pre-determined rates chargeable for different uses as under :-

Catogory of Land

Approved pro-determined rates for Narela for 2007-2008 (per sq. mtr.)

Lind for CGHS

Rs.7602.00

2. Alternative Plots

Rs.6106.00
(inclusive of cost of internal development and use and occupation charges)

- 3. DDA Housing Schemes .
  - (a) SFS
  - (b) MIG
  - (c) LIG (d) EWS

- Rs. 7602.00 Rs. 6335.00
  - Ro. 3801.00
- Rs. 2534.00

(cost of internal development to be added while working out the disposal cost of firsts)

J.J. Squattors (Resottlement)

Ru. 22.90 lakh per acro (excluding rates of internal development which is to be carried out by the Slum Deptt. of MCD)

These rates are effective for the financial year 2007-2008.

(S.N. Gupta)
Under Secretary to the Govt. of India

То

The Manager, Government of India Pres Mayapurt, New Dolhi-110064 No. K-12016/2/2006- DDIB Government of India Ministry of Urban Development Delhi Division

> Nirman Bhavan, New Delhi Dated the 31<sup>st</sup> January, 2008

PC-Secr.

Subject:

Notification dated 30.1.2008 regarding issue of directions to the local authorities in the Extraordinary Gazette of India.

P C

A copy of above Notification published in the Gazette of India Extraordinary is sent herewith for information and necessary

acusm.

011/2005

(P.K. Santra) Under Secretary Telefax.: 23061681/ 23061006 /23061478

वैठक कक्ष, विविद्या १ - ज्यानिक Viceling Cell, D. ए. य. ....... २१८० होयरी सं

Vice Chairman, DDA, Vikas Sadan, New Delhi Principal: Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi:

Commissioner (Planning), DDA, Vikas Minar, New Delhi Commissioner (LD), DDA, Vikas Sadan, New Delhi

Commissioner (LM), DDA, Vikas Sadan, New Delhi Principal Secretary (UD), GNCTD, Delhi.

Chief Planner, TCPO, IP Estate, New Delhi.

L&DO, Nirman Bhawan, New Delhi.
Secretary, NDMC, Palika Kendra, New Delhi.

10. Commissioner, MCD, Town Hall, Delhi

Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi

in forci

Copy to :-

7.

Millip ASENT

PS to UDM / PS to MoS (UD) / Sr. PRS to Secy.(UD) / PS to JS (D&L)/ Director (DD).

# Ele Gazette of India

असाधारण EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. [27]

Γ

नई दिल्ली, बुधवार, जनवरी 30, 2008/माघ 10, 1929

NEW DELHI, WEDNESDAY, JANUARY 30, 2008/MAGHA 10, 1929

No. 127]

#### शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

#### अधिसूचना

नई दिल्ली, 30 जनवरी, 2008

का आ. 213(अ).—यतः दिल्ली विधि (विशेष उपबंध) अधिनियम, 2007 (2007 का 43) (यहाँ इसके बाद उक्त अधिनियम के रूप में उल्लिखित) की धारा 3 के निवन्धनों के अनुसार अतिक्रमण अथवा अप्राधिकृत विकास की श्रेणियों के संबंध में स्थानीय प्राधिकरणों द्वारा जारी सभी नोटिस, दिसम्बर, 2008 के 31वें दिन तक के लिए निलम्बित माने जाएंगे;

और यत: उवत अधिनियम की धारा 3 की उप-धारा (3) के उपवंशों के निबन्धनों के अनुसार अधिनियम की धारा 3 की उप-धारा (1) में उल्लिखित अतिक्रमण अथवा अप्राधिकृत विकास के खिलाफ दाण्डिक कार्रवाई दिसम्बर, 2008 के 31वें दिन तक के लिए निलम्बित रखी जाएगी;

अतः, अब, दिल्ली विधि (विशेष उपबंध) अधिनियम, 2007 (2007 का 43) की धारा 5 द्वारा प्रदत्त शिवतयों का प्रयोग करते हुए केन्द्र सरकार उवत अधिनियम के उपबंधों को प्रवृत्त करने के लिए स्थानीय प्राधिकरणों को एतद्द्वारा निम्नलिखित निर्देश देती है: निर्देश

 (i) उक्त अधिनियम की धारा 3 में उल्लिखित अतिक्रमण या अनिधकृत विकास के संबंध में अनिधकृत कालोनियों, गांव आबादी क्षेत्र तथा इसके विस्तार क्षेत्र को छोड़कर, न्यायालय के किसी निर्णय, डिक्री या आदेश के होते हुए भी, स्थानीय प्राधिकरण द्वारा सीलिंग कार्य बंद करने सहित जनवरी, 2006 के पहले दिन की यथास्थित बनाए रखने के लिए कार्यवाही की जाएगी।

- (ii) न्यायालय के किसी निर्णय, डिक्री या आरेश के होते हुए भी सीलिंग कार्य बन्द करने सहित अनिधकृत कालोनियों, गांव आबादी क्षेत्र तथा इसके विस्तार क्षेत्र जो 31 मार्च, 2002 को 8 फरवरी, 2007 की स्थिति के अनुसार मौजूद थे, की स्थानीय प्राधिकरण द्वारा यशास्थिति बनाई रखी जाएगी।
- 2. अधिनियम के खण्ड 3 में उल्लिखित अतिक्रमण या अप्राधिकृत विकास के विरुद्ध प्रारंभिक कार्रवाई के लिए किसी भी स्थानीय प्राधिकारी द्वारा जारी सभी सूचनाएं निलंबित होंगी और 31 दिसम्बर, 2008 तक कोई भी दांडिक कार्रवाई नहीं की जाएगी।
- 3. दिसम्बर, 2007 के 5वें दिन से 31 दिसम्बर, 2008 तक की अवधि के दौरान उक्त अधिनियम की धारा 4 में यथानिर्दिष्ट अप्रधिकृत विकास की श्रेणियों के संबंध में स्थानीय प्राधिकरणों द्वारा संगत विधियों के अनुसार कार्रवाई जारी रहेगी और की गई कार्रगाई की मासिक रिपोर्ट आगामी माह के प्रथम सप्ताह के अंत तक राचिव, शहरी विकास मंत्रालय, नई दिल्ली को भेजी जाएगी।

[फा. सं. के-12016/2/2006-डीडीआईबी]

पी. के. सांतरा, अवर सचिव

#### MINISTRY OF URBAN DEVELOPMENT

(DELHI DIVISION)

### NOTIFICATION

New Delhi, the 30th January, 2008

S.O. 213(E).—Whereas in terms of Section 3 of The National Capital Territory of Delhi Laws (Special Provisions) Act, 2007 (43 of 2007) (hereafter referred to as

312 GI/2008

(1

THE GAZETTE OF INDIA: EXTRAORDINARY

the said Act), all notices issued by the local authorities in respect of the categories of encroachment or unauthorized development mentioned therein shall be deemed to have been suspended till the 31st day of December, 2008;

And whereas in terms of the provisions of subsection (3) of Section 3 of the said Act, punitive action, against encroachment or unauthorized development referred to in sub-section (1) of Section 3 of the Act shall be suspended till the 31st day of December, 2008;

Now, therefore, in exercise of powers conferred by Section 5 of the National Capital Territory of Delhi Laws (Special Provisions) Act, 2007 (43 of 2007), the Central Government hereby issues the following directions to the local authorities to give effect to the provisions of the said Act, namely:

#### DIRECTIONS

(1) (i) Notwithstanding any judgement, decree, or order of Court, steps shall be taken by the local authority, including descaling, to maintain status quo as on 1st day of January, 2006 in respect of encroachment or unauthorized development referred to in Section 3 of the said Act except in respect of unauthorized colonies, village abadi area and its extension.

- (ii) Notwithstanding any judgement, decree, or order of Court, steps shall be taken by the local authority, including descaling, to maintain status quo, in the unauthorized colonies, village abadiarca, and its extension, which existed in the 31st day of March, 2002, as on the 8th day of February, 2007.
- (2) All notices issued by any local authority for initiating action against encroachment or unauthorised development referred to in Section 3 of the Act shall be suspended and no punitive action shall be taken till the 31st day of December, 2008.
- (3) During the period up to 31st December, 2008 w.e.f. 5th day of December, 2007, action as per relevant laws shall continue to be taken by the local authorities in respect of the categories of encroachment or unauthorized development, as specified in Section 4 of the said Act and a monthly report of the action taken shall be sent to the Secretary, Ministry of Urban Development, New Delhi by the end of the first week of the succeeding month.

\*\*\* 30: \$1:51.51

grand des en en dien een. Van dees een 20 kaar 1995

्राच्याच्या (११६ वर्षः स्टब्स्) प्राप्तम् स्थिति । यो स्टब्स्ट स्टब्स् स्टब्स् स्टब्स् स्टब्स्स्य स्टब्स् १९ - द्यार्टी वर्षे वर्षे स्टब्स्ट स्टब्स्स्य स्टब्स्ट १९ - द्यारस्ट स्टब्स्ट स्टब्स्ट स्टब्स्ट स्टब्स्ट

ित्र विभिन्ने विकास के प्रियम् कार्या के विश्व विश विश्व वि विश्व वि

ি ক্রিক ক্রিটিটি, কর্ণির ক্রিটের **স্কল**ের আ প্রতিষ্ঠিত ক্রিটার ক্রেটির ক্রিটের স্কলে ক্রিটিটি প্রতিষ্ঠিত ক্রিটিটি ক্রিটিটির ক্রিটিটির ক্রিটিটির ক্রিটিটির

[F. No. K-12016/2/2006-DDIB]

प्रदेशको विश्वार्थ P. K. SANTRA, Under Secy.

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054

#### No. K-20013/17/2006- DDVA/IB Government of India Ministry of Urban Development Delhi Division

Nirman Bhavan, New Delhi Dated the 12<sup>th</sup> February, 2008

Subject:

Extraordinary Gazette Notification – No.S.O. 272(E) dated 7.2.2008 regarding change of land use.

A copy of above Notification published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

A After the termon frame.

वैदक कक्ष, दि.वि.प्रा. Meeting Cell, D.D.A. डायरी पं 10 6 Diary No. 10 6

(P.K. Santra) Under Secretary Telefax.: 23061681

Vice Chairman, DDA, Vikas Sadan, New Delhi

- Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, New Delhi
- 3. Commissioner (Planning), DDA, Vikas Minar, New Delhi
- 4. Commissioner (LD), DDA, Vikas Sadan, New Delhi
- 5. Commissioner (LM), DDA, Vikas Sadan, New Delhi
- 6. Principal Secretary (UD), GNCTD, Delhi.
- 7. Chief Planner, TCPO, IP Estate, New Delhi.
- 8. L&DO, Nirman Bhawan, New Delhi.
- 9. Secretary, NDMC, Palika Kendra, New Delhi.
- 10. Commissioner, MCD, Town Hall, Delhi. . . . . .
- 11. Secretary, DUAC, India Habitat Centre, Zone-6, Core-F, Lodhi Road, New Delhi.
- 12. Dy. Registrar (AG), Supreme Court of India.

Copy to :-

Computer Cell, M/o UD for display the above Notification on the website of the Ministry.

D 8/2 12/2 1/3/2/08 ROLAS

Meetry ASSM 13ppros



असाधारण EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii) प्राधिकार से प्रकाशित

PUBLISHED BY AUTHORITY

सं. - 176] No. 176] नई दिल्ली, बृहस्पतिवार, फरवरी 7, 2008/माघ 18, 1929 NEW DELHI, THURSDAY, FEBRUARY 7, 2008/MAGHA 18, 1929

शहरी विकास मंत्रालय

(दिल्ली प्रभाग)

अधिसूचना

नई दिल्ली, 7 फरवरी, 2008

का,आ. 272(अ).—यतः यहां नीचे उल्लिखित क्षेत्र के संबंध में दिल्ली मास्टर प्लान में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव था, उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खण्ड-44 के प्रावधानों के अनुसार दिनांक 16 मई, 2007 की सं. का.आ. 767(अ) की सार्वजनिक सूचना द्वारा भारत के असाधारण राजपत्र में प्रकाशित किया गया जिसमें उक्त नोटिस की तारीख से तीस दिन के अंदर उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (3) द्वारा यथाअपेक्षित आपत्तियां/सुझाव आमंत्रित किए गए।

2. यतः प्रस्तावित संशोधन के संबंध में प्राप्त आपित्तयों/सुझावों पर सक्षम प्राधिकारी द्वारा यथोचित विचार किया गया तथा यतः केन्द्र सरकार ने मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के बाद दिल्ली के मास्टर प्लान-2021 में संशोधन करने का निर्णय लिया है ।

3. अत: अब उक्त अधिनियम के खण्ड 11-ए के उप-खण्ड (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार भारत के राजपत्र में इस अधिसूचना के प्रकाशित होने की तारीख से दिल्ली के उक्त मास्टर प्लान-2021 में एतद्द्वारा निम्नलिखित संशोधन करती है। संशोधन :

जोन ''डी'' में 12.19 एकड़ माप वाले निम्नलिखित क्षेत्र के भू-उपयोग को निम्नलिखित विवरण अनुसार परिवर्तित किया गया है :--

• • •						
क्षेत्रफल	भू-उपयोग (एमपीडी-2021)	परिवर्तित भू-उपयोग	सीमाएं			
2	3	4 19 19 19 19 19 19 19 19 19 19 19 19 19	5			
12.19 एकड	मनोरंजनात्मक	सरकारी कार्यालय	उत्तर-रेलवे लाईन/मेट्रो लाईन पूर्व और दक्षिण-प्रगति मैदान काम्पलैक्स पश्चिम-मथुरा रोड			
	2	(एमपीडी-2021) 2 3	(एमपीडी-2021) भू-उपयोग 2 3 4 12.19 एकड़ मनोरंजनात्मक सरकारी कार्यालय			

ं[फा. सं. के-20013/17/2006-डी डी V ए/ाबी]

पी. के. सांतरा, अवर सचिव

422 GI/2008

(1

#### MINISTRY OF URBAN DEVELOPMENT

#### (Delhi Division)

#### NOTIFICATION

New Delhi, the 7th February, 2008

- S.O. 272(E).—Whereas certain modifications which the Central Government proposed to make in the Master Plan for Delhi regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 767(E) dated 16th May, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11-A of the said Act, within thirty days from the date of the said notice.
- 2. Whereas a number of objections/suggestions were received with regard to the proposed modification and whereas the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master Plan for Delhi-2021.
- 3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11-A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi-2021 with effect from the date of publication of this notification in the Gazette of India.

#### Modification:

The land use of the following area measuring 12.19 acreas of land in Zone D is changed as per description listed below:—

Location	Area	Land use (MPD-2021)	Land Use changed to	Boundaries	-
1	2	3	4	. 5	
ITPO, Pragati Maidan in Zone-D	12.19 acre	'Recretional'	Government office	North: Railway line/Metro station East and South: Pragati Maidan Com West: Mathura Road	plex

[F. No. K-20013/17/2006-DDVA/IB] P. K. SANTRA, Under Secy. (To be published in Part I, Section 2 of the Gazette of India)

No. K-11011/42/2006-DDIA Government of India Ministry of Urban Development (Delhi Division)

Nirman Bhawan, New Delhi-110 108 Dated: April 2, 2008

थैठक कक्ष, दि.वि.प्रा. Meeting Cell, D.D.A.

Diary No. 20 C

दिनाक

NOTIFICATION

The President is pleased to appoint Ms. Veena Ish, IAS (AP:85) as Principal Commissioner (Commonwealth Games) in the Delhi Development Authority at the level of Joint Secretary in the pay scale of Rs. 18400-22400 for a period of five years from the date of assumption of charge of the post or till the term of the Commonwealth Games or until further orders, whichever is the earliest.

(N.T. Joseph) Under Secretary (DD 1A) Tel: 23061478

To

The Manager, Govt. of India Press, (with Hindi version) FARIDABAD (Haryana)

# Copy forwarded to:

- 1. The Secretary to the Lt. Governor, Raj Niwas, Delhi.
- 2. Vice-Chairman, DDA, Vikas Sadan, INA, New Delhi.
- 3. Department of Personnel & Training (Shri A.K. Singhal, Director) w.r.t O.M. No. 26/1/2007-EO (SM.I) dated 20.3.2008.
- 4. Chief Secretary, Govt. of Andhra Pradesh, Secretariat, Hyderabad.
- 5. Ms. Veena Ish, IAS (AP:85) through Chief Secretary, Govt. of Andhra
- 6. Principal Commissioner-cum-Secretary, DDA, Vikas Sadan, INA, New Delhi. 7. Commissioner (Personnel), DDA, Vikas Sadan, INA, New Delhi.

Copy also forwarded for information to:-

PS to UDM / Sr. PPS to Secretary (UD) / PS to SS (UD) / PS to JS(DL)/PS to JS &FA/PS to JS(UD).

Oozr.

(N.T. Joseph) Under Secretary (DD 1A)

Tel: 23061478

#### No. K- 12016/6/2003-DDIB

Government of India Ministry of Urban Development Delhi Division

> Nirman Bhavan, New Delhi Dated the 21st April, 2008

Subject: Modification Composition of Heritage Conservation Committee-- forwarding of copy of Extraordinary Gazette Notification issued on 4.4.2008.

A copy of Notification No.817 (E) dated 4th April, 2008 published in the Gazette of India Extraordinary is sent herewith for information and necessary action.

> (P.K.Santra) **Under Secretary** Tel.No.23061681

#### Copy to:

- 1. Special Secretary, MoUD and Chairman of the Heritage Conservation Committee, Nirman Bhavan, New Delhi-
- 2. Member Secretary, DUAC,
- 3. Director General, Archeological Survey of India, Janpath, New Delhi
- 4. Vice Chairman, DDA, Vikas Sadan, INA, New Delhi
- 5. Chairperson, NDMC, Palika Kendra, New Delhi
- 6. Commissioner (MCD), Town Hall, Delhi
- 7. Director General (Works), CPWD, Nirman Bhavan, New Delhi



EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii) PART II—Section 3—Sub-section (ii) प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 452] No. 4521

नई दिल्ली, शुक्रवार, अप्रैल 4, 2008/चैत्र 15, 1930 NEW DELHI, FRIDAY, APRIL 4, 2008/CHAITRA 15, 1930

शहरी विकास मंत्राल (दिल्ली प्रभाग) अधिसूचना

नई दिल्ली, 4 अप्रैल, 2008

का.आ. 817(अ).—केन्द्र सरकार, दिल्ली विकास अधिनियम, 1957 की धारा 11-ए की उप-धारा (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, दिल्ली भवन निर्माण उप-नियमों में एतद्द्वारा राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से निम्नलिखित संशोधन करती है :-

#### संशोधन :

- 1. धारा 23.16 में हेरीटेज संरक्षण समिति के गठन में क्र.सं.
- (i) को संशोधित करके इस प्रकार पढ़ा जाए :-अध्यक्ष" "1. विशेष सचिव/अपर सचिव

शहरी विकास मंत्रालय

2. दिनांक 20 नवम्बर, 2007 की अधिसूचना सं. का. आ. 1964(अ) की ओर भी ध्यान आकर्षित किया जाता है। उक्त अधिसूचना में निम्नलिखित संशोधन किए जाएं :-

#### संशोधन

- 1. हेरीटेज संरक्षण समिति के गठन में क्र.सं. 1 को संशोधित करके इस प्रकार पढ़ा जाए :-
  - "1. विशेष सचिव/अपर सचिव शहरी विकास मंत्रालय
  - 2. पैरा 2 को इस प्रकार संशोधित किया जाए :-
  - "2. समिति का कार्यकाल दिनाक 9-2-2007 से लेकर 3 वर्ष तक का होगा"।

[सं. के 12016/6/2003-डीडीआईबी] पी. के. सांत्रा, अवर सचिव

# MINISTRY OF URBAN DEVELOPMENT

(Delhi Division)

NOTIFICATION

New Delhi, the 4th April, 2008

S.O. 817(E).—In exercise of the powers conferred by sub-section (2) of Section 11-A of the Delhi Development Act, 1957, the Central Government hereby makes the following modifications in the Delhi Building Bye Laws with effect from the date of publication of this Notification in the Gazette of India.

#### Modification:

Sl.No. (i) in the composition of the Heritage Conservation Committee in Clause 23.16 shall be modified to read as under :--Chairman"

."(i) Special Secretary/Additional Secretary, Ministry of Urban

Development 2. Attention is also invited to Notification No. S.O.1964(E) dated 20th November, 2007. The following

## modifications shall be made in the said Notification :-Modifications

- 1. In the composition of the Heritage Conservation Committee, SI.No.1 shall be modified to read as under:-
- "I. Special Secretary/Additional Chairman" Secretary, Ministry of Urban Development
- 2. Para 2 shall be modified as under:
  - "2. The tenure of the Committee shall be 3 years with effect from 9-2-2007.".

[No. K-12016/6/2003-DDIB] P. K. SANTRA, Under Secy.

1270 GI/2008

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054.



EXTRAORDINARY

भाग II — खण्ड 3 — उप-खण्ड (ii)

PART II—Section 3!—Sub-section (ii) प्राधिकार से प्रकाशित

PUBLISHED BY AUTHORITY

No. 6741

नई दिल्ली, शुक्रवार, मई 16, 2008/वैशाख 26, 1930 NEW DELHI, FRIDAY, MAY 16, 2008/VAISAKHA 26, 1930

बैठक कक्षा, वि.वि.प्रा. Meeting Cell, D.D.A. डायरी रां Diany No.

शहरी विकास मंत्रालय (दिल्ली प्रभाग) अधिसूचना नई दिल्ली, 16 मई, 2008

का.आ:"!169(अ):--यतः, नीचे विल्लाखित क्षेत्र के बारे में दिल्ली मास्टर प्लान में केन्द्र सरकार का जिन कुछ संशोधनों का प्रस्ताव है, उन्हें दिल्ली विकास प्राधिकरण द्वारा दिल्ली विकास अधिनियम, 1957 (1957 का 61) के खण्ड 44 के प्रावधानों के अनुसार 14 नवम्बर, 2007 की सं. का.आ. 1933(अ) की सार्वजनिक सूचना के रूप में भारत का राजपत्र, असाधारण में प्रकाशित किया गया था जिसमें उक्त अधिनियम के खण्ड 11ए के उप-खण्ड (3) द्वारा यथाअपेक्षित उक्त नोटिस की तारीख के तीस दिन के भीतर आपतियां/सुझाव आमंत्रित किए गए थे।

2. यतः, केन्द्र सरकार ने, मामले के सभी पहलुओं पर ध्यानपूर्वक विचार करने के पश्चात् दिल्ली मास्टर प्लान, 2021 को संशोधित करने का निर्णय लिया है।

3. अतः, अद, टब्त अधिनियम् के खण्ड 11ए के उप-खण्ड (2) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केन्द्र सरकार, भारत के राजपत्र में इस अधिसूचना के प्रकाशन की तारीख से उक्त दिल्ली मास्टर प्लान, 2021 में निम्नलिखित संशोधन करती है, वशतें कि मौजूरा अनिधकृत कालोनी के साथ-साथ डिफेंस अपनी भूमि पर टिवत सड्क मुहैया कराए। संशोधन :

जोन-जे (दक्षिण दिल्ली-II) में 12.15 हेक्टे. (29.968 एकड़) के निम्न क्षेत्र का भू-उपयोग नीचे सूचीबद्ध वर्णन के आधार पर वदला जाता है :--

					,	
स्थान	- क्षेत्रफ <u>र</u> ू	•	भू-उपयोग (एमपीडी-2021)	भू-उपयोग परिवर्तित .	,	सीमा
(4) mm	(2),		(3)	(4)		(5)
जोन-जें (दक्षिण दिल्ली-!!) रंगपुरी (वसंतक्षुंज)	12.15 हेक्टे. (29.968 एकड़)	:	कृषि और जलाराव "ग्रामीण"	"सरकारी भूमि		म — कृषि और जलाशय(ग्रामीण)
			, ;	(अनिश्चित उपयोग)"	उत्तर	और क्षेत्रीय पार्क — महारौली-महिपालपुर रोड
<u> </u>			:		বৃদ্ধিত	और सुल्तानगढ़ी मकबरा — नांगल देवात बेदखल स्कीम

[फा. सं. के-13011/4/2007-डो डी आई वी] पी. के. सांतरा, अवर सचिव

1321 GV2008

(1)

# MINISTRY OF URBAN DEVELOPMENT (DELHI DIVISION)

#### NOTIFICATION

#### New Delhi, the 16th May, 2008

Plan for Dollai regarding the area mentioned hereunder were published in the Gazette of India, Extraordinary, as Public Notice vide No. S.O. 1933(E) dated the 14th November, 2007 by the Delhi Development Authority in accordance with the provisions of Section 44 of the Delhi Development Act, 1957 (61 of 1957) inviting objections/suggestions as required by sub-section (3) of Section 11A of the said Act, within thirty days from the date of the said notice.

Whereas, the Central Government have, after carefully considering all aspects of the matter, decided to modify the Master Plan for Delhi, 2021

3. Now, therefore, in exercise of the powers conferred by sub-section (2) of Section 11A of the said Act, the Central Government hereby makes the following modification in the said Master Plan for Delhi, 2021 with effect from the date of publication of this Notification in the Gazette of India. Subject to the condition that proper road would be provided by Defence on their land along the existing unauthorized colony.

#### Modification:

The land use of the following area measuring 12.15 Ha. (29.968 acres) of land falling in Zone-J (South Delhi-II) is changed as per description listed below:—

		1					
Location	Area	Land use (MPD-2021)	Land use changed to	•	Boundaries		
(1)	(2)	(3)	(4)	٧	(5)		
Rangpuri (Vasant Kunj) in Zone-J (South Delhi-II)	(29.968 Acres)	Agricultural and Water Body 'Rural'	'Government Land (use undetermined)' for defence purpose.	East — West —			
	y Karangang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palangganggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palanggang Palangg		A Section of the second	North-	- Mehrauli Mahipalpur Road and Sultan Garhi Tomb		
				South-	- Nangal Dewat Evictees Scheme		
		1					

[F. No. K-13011/4/2007-DDIB]
P. K. SANTRA, Under Secy.

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054.

# The Gazette of India

#### असाधारण EXTRAORDINARY

भाग.H — खण्ड ३ — उप-खण्ड (ii) PART II — Section 3 — Sub-section (ii)

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 389]

नई दिल्ली, सोमवार, मार्च 24, 2008/चैत्र 4, 1930

No. 389]

NEW DELHI, MONDAY, MARCH 24, 2008/CHAITRA 4, 1930

#### दिल्ली विकास प्राधिकरण

#### अधिसूचना

नई दिल्ली, 24 मार्च, 2008

दिल्ती में अनिधकृत कॉलोनियों के नियमन के विनियम (दिल्ली विकास अधिनियम, 1957 की धारा 57 के अंतर्गत)

का.आ. 683( अ ).—िरिल्ली विकास अधिनियम, 1957 (1957 का 61) की धारा 57 द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए दिल्ली विकास प्राधिकरण केन्द्र सरकार के पूर्व अनुमोदन से एतद्द्वारा निम्निलिखित विनियम बनाता है :

- ]. प्रस्तावना
- 2. परिभाषाएं
- 3. अनिधकृत कॉलोनियों के नियमन के मानदण्ड
  - 3.1 निर्धारक तिथि
  - 3.2 नियमन के लिए पात्र वस्ती
  - 3.3 नियमन के लिए विचार नहीं की जाने वाली कॉलोनियों की प्रकृति
  - 3.4 गैर-आवासीय उद्देश्यों के लिए प्रयोग में लाए जाने वाले आवासीय भवन
  - 3.5 अनिधकृत निर्माण के विरुद्ध कार्रवाई
  - 3.6 विनियम जो संभ्रांत कॉलोनियों से संबद्ध नहीं हैं
- 4. नियमन की पद्धति
  - 4.1 रेजीडेंट सोसायटी का पंजीकरण

- 4.2 रेजीडेंट सोसायटी के कार्य
- 4.3 ले-आउट प्लान तैयार करना
- 4.4 ले-आउट प्लान में संशोधन करना
- 4.5 ले-आउट प्लान प्रस्तुत करने की अपेक्षाएं
- 4.5.1 प्रस्तुत किए जाने वाले दस्तावेज
- 4.5.2 वर्तमान/प्रस्तावित ले-आउट प्लान के संबंध में सूचना
- 4.5.3 वचनबंध-पत्र
- 5. नियमन के लिए स्थानीय निकाय/दि.वि.प्रा./रा.रा.क्षे. दिल्ली सरकार द्वारा की जाने वाली कार्रवाई/पद्धति
  - 5.1 एक पृथक कक्ष (सेल) का सृजन
  - 5.2 तें-आउट प्लान की जांच
  - 5.3 सीमाओं को अंतिम रूप देना
  - 5.4 स्थानीय निकायों को ले-आउट प्लान अग्रेषित करना
  - 5.5 ले-आउट प्लान का अनुमोदन
  - 5.6 भूमि उपयोग परिवर्तन
  - 5.7 आदेश जारी करना
  - 5.8 भृमि को लागत
  - 5.9 ' जुर्माना
  - 5.10 विकास कार्य प्रारंभ करना

1075 GI/2008

(1)

- 5.11 समय अनुसूची
- नियमन के मानदण्ड/आधीर
  - 6.1 भूमि का इक
  - 6.2 योजना मानदण्ड
  - 6.3 मिश्रित उपयोग
  - 6.4 लागत/विकास प्रभार की वसूली
- 7. विविध
  - 7.1 संस्वीकृति देना या दुकराना
  - 7.2 दिशानिदंशों के साथ पठित विनियम
  - 7.3 समन्वय आदि रा.रा.क्षेत्र दिल्ली सरकार द्वारा

#### . <sub>1.</sub> प्रस्तावना

शहरी विकास मंत्रालय ने दिनांक 05-10-2007 के पत्र द्वारा दिल्ली में अनिधकृत कॉलोनियों के नियमन हेतु संशोधित मार्गनिर्देश 2007 की सूचना दी है, जिसे 1994 की रिट याचिका सं. 725 में उच्चतम न्यायालय के दिनांक 14-02-2006 के आदेशों और 1993 की सिवित रिट याचिका सं. 4771 में दिल्लो उच्च न्यायालय के दिनांक 27-2-2001 के आदेशों के संदर्भ में भी देखा जा सकता है। उच्च न्यायालय के आदेशों में मार्गनिर्देशों के अनुसार नियमित की जाने वाली कॉलोनियों की अधिसूचना और नियमों को वैयार करने की माँग की गई है।

#### 2. परिभाषाएँ

- (क) ''वास्तुकाएनगर योजनाकार'' ऐसा वास्तुकार जो वास्तुकला परिपद् में पंजीकृत हो और जिसके पास नगर योजना में ऐसी योग्यता हो जो नगर योजनाकार संस्थान, भारत की सदस्यता के लिए नान्य हो;
- (ख) ''संबंधित एजेंसी'' से अभिग्राय ऐसे स्थानीय निकाय/दिल्ली विकास प्राधिकरण (दि.वि.प्रा.)/ राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार (रा.रा.क्षे.दिल्ली सरकार) अथवा किसी अन्य एजेन्सी से है, जो योजनाओं के नियमन/तैयार करने, क्रियान्वयन की प्रक्रिया और अपने संबंधित क्षेत्राधिकार में आने वाली अनिधकृत कॉलानियों के नियमन के कार्य में सम्मिलित हो।
  - (ग) "वरती" शब्द से अभिप्राय संशोधित मार्गनिर्देश 2007/विनियमों में यथा निर्दिष्ट नियमन के उद्देश्य के लिए उन बस्तियों से है जो 31-3-2002 को विद्यमान थी तथा जो गाँव की आवादी के विस्तार के रूप में बनी हैं और जो गाँव की आवादी के लाल डोरा विस्तार के रूप में अधिसृचित नहीं हैं;
  - (घ) ''आधारिक संरचना'' से अभिप्राय उस आधारिक संरचना से है, जो 'सामाजिक आधारिक संरचना' जैसे जल आपूर्ति, डूनेज, सीवरेज, विजली और कूड़ा निपटान, जिसका उल्लेख दिल्ली मुख्य योजना (एम.पी.डो.)-2021 के अध्याय-14 (भौतिक आधारिक संरचना) में हुआ है, से भिन्न है;
  - (इ) ''ले-आउट प्लान'' से अभिप्राय: उस नक्से में है जिसमें सभी विद्यमान (प्रसावित भी, यदि कोई हो) सड़को की उनकी चौड़ाई सहित अवस्थिति, विल्डिंग लाइन्स सहित प्लाटों की

दिशाओं, नालों और सार्वजनिक सुविधाओं, यदि के हो, की अवस्थिति, सड़कों के स्थल के कुल क्षेत्रफल को दर्शाने वाला विवरण और यदि उपलब्ध हो, तो पाकों के लिए खुले स्थलों, खेल-मैदानों, मनोरंजनात्मक स्थलों और सार्वजनिक स्थलों को दर्शाया गया हो;

- (च) ''रेजीडेंट्स सोसायटी'' से अभिप्राय एक पंजीकृत रेजीडेट सोसायटी से है, जिसमें अनिधकृत कॉलोनी/आवास के सदस्य शामिल हैं, जो समन्वय, ले-आउट प्लान तैयार करने और नियमन की प्रक्रिया से संबंधित विभिन्न मृद्दों के संबंध में संबंधित एजेंसी से सम्मर्क करने के लिए उत्तरदायी होगी।
- (छ) ''सर्विस रोड''-ऐसी रोड/लेन जिसकी व्यवस्था सर्विस उद्देश्यों के लिए प्लाट के पीछे या एक तरफ की गई है;
- (ज) ''साइट या प्लॉट''-ऐसा भूखण्ड जिसकी सीमाएँ निर्धारित हैं;
- (झ) ''सामाजिक आधारिक संरचना'' से अभिप्राय उन सामाजिक आधारिक संरचना संबंधी सुविधाओं से है, जो स्वास्थ्य, शिक्षा, खेल सुविधाओं एवं सामाजिक-सांस्कृतिक कार्यकलापों और धार्मिक कार्यकलापों से संबंधित हैं;
  - (ज) "स्ट्रीट" में कोई भी मार्ग, रोड, लेन, स्कवेयर, कोर्ट, गली, नाली, रास्ता चाहे वह आम रास्ता हो या न हो और चाहे यह बना हुआ हो या न हो, जिसके ऊपर आम जनता को चलने का अधिकार हो और चाहे वह किसी पुल या पक्के नदी पथ पर बना रोड वे या पैदल रास्ता हो, शामिल है;
  - (ट) "अनिधकृत कॉलोनी" से अभिप्राय ऐसी कॉलोनी/ समीपस्थ विकास क्षेत्र से है, जहाँ ले-आउट प्लान, और/अथवा बिल्डिंग प्लान के अनुमोदन के लिए संबंधित एजेंसी से कोई अनुमित प्राप्त न की गई हो;
    - 3. अनिधकृत कॉलोनियों और बस्तियों के नियमन हेतु पानदण्ड
  - 3.1 नियमन की निर्धारक (कट ऑफ) तिथि 31-3-2002 है।
  - 3.2 ऐसे आवास जो गाँव की आवादी के विस्तार के रूप में बने है और जो गाँव के लाल डोरे से बाहर स्थित हैं, वे नियमन के लिए अनिधकृत कॉलोनियों की पद्धति के समान आधार पर नियमन के लिए पात्र होंगे।
  - 3.3 निम्नलिखित प्रकार की कॉलोनियों अथवा उनके भाग पर नियमन हेतु विचार नहीं किया जाएगा :
  - (क) ऐसी अनिधकृत कॉलोनियाँ/कॉलोनियों के भाग/बस्तियां, जो अधिसूचित या आरक्षित वन क्षेत्रों के अंतर्गत आती हैं।
  - (ख) अनिधकृत/कॉलोनियां/कॉलोनियों के भाग/बस्तियां जो आधारिक-संरचना सुविधाओं की व्यवस्था में बाधा.

उत्तेत्न करती हैं, अयस निष्यमान/प्रस्तानित रेतने नाडमें; भुख्य योजना सङ्गों और बड़ी/मुख्य जलपूर्त और सीयरेज लाइमों के मार्गाधिकार (आर ओ डब्ल्यूं) के क्षेत्र में आती हैं।

- (ग) अनिधिकृत कॉलोनियां/यिस्तियां, जिनमें निोपन योजना की औपचारिक घोषणा की तिथि को 50 प्रांहप्त से अधिक प्लाटों पर निर्माण कार्य नहीं हुआ है। तपाषि, उपर्युक्त कॉलोनियों में 31-3-2002 के बाद और नियमन योजना की औपचारिक घोषणा की तिथि तक यने प्लाटों को कॉलोनी की नियमन की पात्रता निर्धारित करने के लिए ध्यान में रखा जाएगा।
- (घ) अनिधकृत कॉलोनियां/कॉलोनियों के भाग/वस्तिया—जो प्राचीन स्भारक और पुरातत्वीय स्थल और अवशेष अधिनियम, 1956 की व्यवस्थाओं का उल्लंघन करती हैं।
- 3.4 समय-समय पर यथा संशोधित, दि.मु.यो. -2021 में निहित मिश्रित भूमि उपयोग विनियमों के अंतर्गत शामिल होने वाले आवासीय भवनों को छोड़कर, गैर-आवासीय उद्देश्यों के लिए प्रयोग किए जा रहे आवासीय भवनों के संबंध में कोई नियमन नहीं किया जाएगा। इन कॉलोनियों के संबंध में दि.मु.यो. -2021 के खण्ड 15.3.4 में यथा-निर्धारित मिश्रित उपयोग सड़कों की अधिसूचना के लिए सर्वेक्षण करने के लिए 90 दिनों की समय-सीमा, रा.रा.क्षे. दिल्ली रास्कार द्वारा कॉलोनी को नियमित कॉलोनी माने जाने की अधिसूचना की तिथि से अथवा उस तिथि-जिससे कॉलोनी नियमन के लिए योग्य मानी जाएगी, से आरंभ होगी।
- 3.5 अनिधकृत कॉलीनियां/कालोनियों के भाग/बस्तियां जा नियमन की शर्ते पूरी नहीं करती हैं, में अनिधकृत निर्माण के बिरुद्ध कार्रवाई संबंधित स्थानीय निकाय/दि.बि.प्रा. द्वारा पैरा 16.2.3 में दी गई व्यवस्थाओं सहित दिल्ली मुख्य योजना में दी गई व्यवस्थाओं के अनुसार की जाएगी।
- 3.6 ये विनियम सार्वजनिक और निजी भूमि पर संभ्रांत वर्गों द्वारा बसायी गयी विस्तयों/अनिधकृत कॉलोनियों पर लागू नहीं होते।
- नियमन के लिए प्रक्रिया
  नियमन के लिए निम्नलिखित कदमों को अपनाया जाएगा:-
- 4.1 रेजीडेण्टस् सोसायटी का पंजीकरण
  प्रत्येक अनिधकृत कॉलोनी/वस्ती के निवासी एक पंजीकृत
  रेजीडेण्ट्स सोसायटी (जिसे आगे रेजीडेण्ट सोसायटी कहा
  जाएगा) का गठन करेंगे। नियमन के मामले में विचार के
  लिए यह एक पूर्व-शर्त होगी। एक कॉलोनी में कई
  एसोसिएशनों के होने पर कोई आपित नहीं होगी, परंतु इन
  एसोसिएशनों को संयुक्त रूप से एक पंजीकृत रेजीडेण्टस्
  सोसायटी बनानी होगी। स्थानीय निकाय केवल ऐसी
  रेजीडेण्ट्स सोसायटियों को मान्यता देगा और उनसे बातचीत
  करेगा, जिसमें उस कॉलोनी के कम-से-कम 75 प्रतिशत

- 4.2 रेजीडेण्ट्स सोसायटी निम्नलिखित कार्य करेगी:-
- 4.2.1.1 नियमन प्रक्रिया से संबंधित विभिन्न मामलों में संबंधित अभिकरण के साथ सम्पर्क स्थापित करना।
- 4.2.1.2 वारतुकां/नगर योजनाकार के माध्यम से कॉलोनी का विद्यमान तं-आउट प्लान तैयार करना। तथापि, रेजीडेन्ट सोसायटी अपनी कॉलोनी के संबंध में संशोधित ले-आउट प्लान स्वैच्छिक रूप से भी जमा करा सकती है।
- 4.2.1.3 इस प्रकार तैयार किया गया ले-आउट प्लान रेजीडेण्ट. सोसायटी द्वारा संबंधित स्थानीय निकाय/दि.वि.प्रा. को प्रस्तुत किया जाएगा और इसके साथ ही साथ रेजीडेण्ट सोसायटी रा.रा.क्षे. दिल्ली सरकार को भी ले-आउट प्लान की एक प्रति जमा कराएगी।
- 4.2.2 रेजीडेण्ट सोसायटी द्वारा ले-आउट प्लान के साथ पूर्ण विवरण जैसे प्लाट नं. और कॉलोनी के क्षेत्रफल सहित महस्यों की पूर्ण सूची स्थानीय निकाय को जमा कराना होगा। रेजीडेण्ट्स सोसायटी का यह दायित्व होगा कि वह सामाजिक आधारिक संरचना की व्यवस्था करने हेतु कार्य करने के लिए संबंधित अभिकरण को जहां संभव हो, भूमि उपलब्ध कराए । जिन कॉलोनियों में सोसायटी द्वारा सामाजिक आधारिक संरचना के लिए भूमि उपलब्ध नहीं करायी जा सकती, उन कॉलोनियों को ऐसी आधारिक-संरचना की व्यवस्था के बिना अपना काम चलाना होगा।
- 4.2.3 स्थानीय निकाय/दि.वि.प्रा./रा.रा.के. दिल्ली सरकार/भारत संघ के लिए कोई बाध्यता नहीं होगी कि वे उन निवासियों को वैक्लियक स्थलों/फ्लैटों का आवंटन करें, जिन्हें खण्ड 3.3 में यथावर्णित नियमित नहीं हुई कॉलोनियों में नागरिक सुविधाओं/आधारिक-संरचना की व्यवस्था के लिए भूमि, उपलब्ध कराने के लिए विस्थापित किया गया हो।
- 4.2.4 रा.रा.क्षे. दिल्ली सरकार रेजिडेंट सोसायटियों/व्यक्तियों से वसूल किए जाने वाले विकास प्रभारो/कार्यवाही शुल्क, यदि कोई हो, का निर्धारण करेगी।
- 4.3 रेजिडेंट सोसायटी को ले-आउट प्लान और संशोधित ले-आउट प्लान का प्रस्ताव, यदि कोई हो, प्रस्तुत करना होगा। यह उस विधि से और उतनी संख्या में प्रस्तुत करना होगा जिस रूप में रा.रा.क्षेत्र दिल्ली सरकार द्वारा उचित समझा जाए।
- 4.4 ले-आउट प्लान एक बार संस्वीकृत हो जाने पर रेजिडेंट सोसायटी उसकी मुद्रित प्रमाणित प्रति सोसायटी के सभी सदस्यों को उपलब्ध कराएगी। संस्वीकृत ले-आउट प्लान में कोई भी अंतर एवं संशोधन संबंधित स्थानिय निकाय/दि. वि.प्रा. के अनुमोदन के अधीन होगा।
- 4.5 ले-आउट प्लान को प्रस्तुत करने के लिए अपेक्षित दस्तावेज
- 4.5.1 प्रस्तुत िकए जाने वाले दस्तावेज : अनिधकृत कालोनियों के नियमन हेतु आवेदन-पत्र के साथ निम्नलिखित दस्तावेज प्रस्तुत करने होंगे :

- (i) खरास संख्या सिंदत भूमि यत ब्योस जिसके साथ स्थल नक्शा लगा हो जिसमें स्थल का चास्तविक विवरण दिया गया हो।
- (ii) प्रमाण पत्रों पर रेजिडेंट सोसायटी के प्राधिकृत हस्ताक्षरकर्ता/स्वामी और वास्तुकार/नगर योजनाकार के विधिवत् हस्ताक्षर होने चाहिए।
- (iii) विनियमन हेतु आवेदन-पत्र के साथ प्रस्तुत किया गया ले-आउट प्लान 1:1000 या बड़े पैमाने पर तैयार किया हुआ होना चाहिए और उसमें आगे के पैराग्राफ में दिया गया विवरण दर्शाया हुआ होना चाहिए।
- 4.5.2 विद्यमान/प्रस्तावित ले-आउट प्लान पर प्रस्तुत की जाने वाली अपेक्षित जानकारी :
  - (i) स्वामित्व संवधी स्थिति सहित स्थल की चारदीवारी और उससे सटी हुई भूमि;
  - (ii) समीपवर्ती क्षेत्र/सड़कों के संबंध में इस स्थल की स्थिति:
  - (iii) उन मार्गों के नाम जिनमें प्लॉट प्रस्तावित/विद्यमान
  - (iv) भूमि के उप विभाजन (सब डिवीजन)सिंहत उस पर प्लॉटों का उपयोग एवं स्थिति;
  - (v) पहुंच मार्ग/रोड स्ट्रीट और उनकी चीड़ाई ;
  - (vi) नॉर्थ प्वाइंट ;
  - (vii) अन्य विद्यमान भौतिक विशेषताएं जैसे कुंए, नाले, वृक्ष आदि;
  - (viii) प्लान रेजिडेंट सोसायटी के प्राधिकृत हस्ताक्षरकर्ता और वास्तुकार/नगर योजनाकार द्वारा अधिप्रमाणित होना चाहिए।

#### 4.5.3 वचनबंध-पत्र

रेजिडेंट्स सोसायटी को ले-आउट प्लान प्रस्तुत करते समय निम्नलिखित वचनवथ-पत्र प्रस्तुत करने होंगे :

- (i) वे शर्तो सहित अथवा शर्तो के बिना यथा अनुमादित ले-आउट प्लानों का पालन वारेंगे।
- (ii) वे सामाजिक-आधारिक संरचना के लिए उपलब्ध भूमि, यदि कोई हो, का हस्तांतरण दि.वि.प्रा. या दि. न.नि./नई दिल्ली नगर पालिका परिषद् के नाम में, नि:्शुल्क रूप से, ऐसी सामाजिक आधारिक संरचना उपलब्ध कराने के लिए करेंगे।
- 5. नियमन के लिए स्थानीय निकाय/दि. वि.प्रा./ रा.रा.क्षेत्र दिल्ली सरकार द्वारा अपनाए जाने वाले उपाय/कार्य-पद्धति :
- 5.1 स्थानीय निकायों/दि.वि.प्रा./रा.स.सेत्र दिल्ली सरकार में, उनके क्षेत्राधिकार के अंतर्गत आने वाली अनिधकृत कालोनियों के नियमन से संबंधित कार्य को करने के लिए एक पृथक

- कक्ष बनाया जाएगा। रेजीडेट सोक्षायटी द्वारा तैयार किया गया ले-अडट प्लान इस कक्ष को प्रस्तुत किया जाएगा।
- 5.2 रेजिडेंट सोसायटी द्वारा प्रस्तुत किए गए ले-आउट प्लान को प्राप्त होने पर स्थानीय निकाय अथवा दि.वि.प्रा. जैसी भी स्थिति हो, दो माह के अन्दर ले-आउट प्लान की जांच पूरी करेगा।
- 5.3 इसके साथ-साथ, रा.रा.क्षे. दिल्ली सरकार सैटेलाइट/एरियल सर्वेक्षण चित्रों का प्रयोग करते हुए ले-आउट प्लान प्रस्तुत करने की अंतिम तिथि से तीन माह के अन्दर प्रत्येक निर्धारित कालोनी की सीमाओं को अंतिम रूप देगी।
- 5.4 संबंधित स्थानीय निकाय द्वारा जांच किए गए ले-आउट प्लान पर सीमाएं निर्धारित किए जाने के बाद रा.रा.क्षे. दिल्ली सरकार, औपचारिक रूप से ले-आउट प्लान को अनुमोदन के लिए स्थानीय निकाय की भेजेगी।
- 5.5 रा.रा.क्षे. दिल्ली सरकार द्वारा चारदीवारियों के निर्धारण के पश्चात् ले-आउट प्लान की प्राप्त के एक माह के अन्दर संबंधित स्थानीय निकाय में सक्षम प्राधिकारी द्वारा ले-आउट प्लान अनुमोदित किया जाएगा।
- 5.6 साथ ही साथ, स्थानीय निकाय मामले को नियमन के लिए रा.रा.क्षे. दिल्ली सरकार को और भूमि उपयोग परिवर्तन के लिए दि.वि.प्रा. को भेजेगा।
- 5.7 भूमि उपयोग परिवर्तन और सभी अपेक्षित प्रभारों के भुगतान सिंहत सभी औपचारिकताओं को पूरा करने के पश्चात् ही रा.रा.क्षे. दिल्ली सरकार द्वारा औपचारिक आदेश अधवा नियमन जारी किया जाएगा।
- 5.8 सरकारी भूमि पर कॉलोनियों के संबंध में भूमि की लागत भूमि स्वामी एजेंसी की ओर से स्थानीय निकाय/दि.वि.प्रा. द्वारा एकत्रित की जाएगी। प्राप्त की गई राशि को संबंधित भूमि स्वामी एजेंसी के खाते में जमा किया जाएगा।
- 5.9 इसी तरह, स्थानीय निकाय/दि.वि.प्रा. द्वारा एकत्रित की जाने वाली जुर्माना राशि एक अलग फंड में जमा की जाएगी।
- 5.10 यदि यह संतुष्टि होती है कि कॉलोनियां अथवा उनके भाग-संशोधित दिशानिर्देश 2007 में निहित सामान्य सिद्धान्तों की पूर्ति करते हैं तो ले-आउट प्लान की प्राप्ति के तुरन्त वाद रा.रा.क्षे. दिल्ली सरकार सार्वजनिक हित में कालोनियों में विकास कार्य और आधारिक सुविधाओं के संबर्धन को प्रारम्भ कर सकती है।
- 5.11 रा.रा.क्षे. दिल्ली सरकार इस बात को सुनिश्चित करने के लिए सभी अपेक्षित कदम उठाएगी कि भूमि उपयोग में परिवर्तन के अतिरिक्त नियमन की संपूर्ण-प्रक्रिया 6 माह के अन्दर पूरी होगी और रेजिडेंट सोसायटी द्वारा ले-आउट प्लान प्रस्तुत करने के 9 माह के अन्दर भूमि उपयोग में प्रभावी परिवर्तन के बाद औपचारिक नियमन हो जाएगा। रा.रा.थे. दिल्ली सरकार के विशिष्ट अनुराध पर उपराज्यपाल, दिल्ली पृथक कॉलोनियों के संबंध में समय-सीमा में छूट दे सकते हैं।

					_
6				THE	G
9. 3	अनेधिकृत	। कॉलोनी	कय से	अस्तित्व ।	ने है
		1/आस-पा ्रवं, पश्चि			,
11.	विकास १	तेत्र गं			
	दि.न.नि./	न.दि.न.पा	./केंट घोर	ई क्षेत्र/	
•	क्या यह	अधिसृचि	त स्लम	क्षेत्र में पर	इंता
12.	अन्धिकृ	त कॉलोनी	का कु	न क्षेत्र	
13.	पृपि की	स्थिति (र	हेट्स)		
14.	न्यायात्र	र मृतहर्स्स	, यदि को	ाई हो	
	(कृपया	, विदरण	संलग्न क	रॅ)	•
(15.	.क्या भूषि	म अभ्रिहण	ा हेतु आ	धसूचित ।	<b>}</b> ?
16.	रेजिडेंट्र	व सोसायव यों∕गृइ-स्व	ी के सद	स्य के रू	
17.		प्लॉटों की			
	(i)	100 वर्ग	मीटर तक	<u>,                                    </u>	
	· (ii)	100 ਵਾਂ 250 ਵਾਂ			a
•	(iii)	250 वर्ग	मीटर से	अधिक	
18	खाली	प्लॉटों की	संख्या		
	(i)	100 मर्ग	भीटर तर	17	
	(ii)	100 वर्ग	मीटर से	250 वर्ग	मीर
٠.		250 বর্গ			
					_

# DELHI DEVELOPMENT AUTHORITY

#### NOTIFICATION

New Delhi, the 24th March, 2008

Regulations for Regularisation of Unauthorised Colonies in Delhi

#### (under Section 57 of DD Act, 1957)

S.O. 683(E).—In exercise of powers conferred by Section 57 of the Delhi Development Act, 1957 (61 of 1957), the Deihi Development Authority with the previous approval of the Central Government, hereby makes the following regulations:-

- Introduction
- Definitions
- Criteria for Regularization of Unauthorized Colonies
  - 3.1 Cut off date
  - 3.2 Habitation eligible for regularization
  - 3.3 Types of colonies NOT to be considered for regularization
  - 3.4 Residential buildings used for non-residential.
  - 3.5 Action against unauthorized construction
  - 3.6 Regulations not relate to affluent colonies
  - Procedure for Regularization
    - 4.1 Registration of Resident Society
    - ,4.2 Functions of Resident Society
    - 4.3 Submission of Layout Plan
    - 4.4 Modification in the Layout Plan
    - 4.5 Requisites for submission of Layout Plan
    - 4.5.1 Documents to be submitted . . .:
    - 4.5.2 Information regarding existing/proposed Layout Plan
    - 4.5.3 Undertakings
  - 5: Steps/procedure to be followed by Local Body/. DDA/GNCTD for regularization
    - 5.1 Creation of a separate Cell
    - 5.2 Scrutiny of Layout Plan
    - 5.3 Finalization of boundaries
    - 5.4 Forwarding of Layout Plan to Local Body
    - 5.5 Approval of Layout Plan
    - 5.6 Change of Land Use
    - 5.7 Issue of Orders"
    - 5.8 Cost of land
    - 5.9 Penalties
    - 5.10 Commencement of developmental works

#### <sub>(-पास</sub> के स्थान (उत्तर, श्चिम की ओर)

- न.पा./कोंट बोर्ड क्षेत्र/
- सृचित स्लम क्षेत्र में पड़ता है? लांनी का कुल क्षेत्र
- ते (स्टेट्स)
- द्रमा, यदि कोई हो रण संलान करें)
- भ्रहण हेतु अधिसूचित है?
- अयटी के सदस्य के रूप में -स्वामियों का प्रतिशत
- की संख्या
  - वर्ग मीटर तक
  - वर्ग मीटर से अधिक एवं वर्ग मीटर तक
  - वर्ग मीटर से अधिक
- की संख्या
  - चर्म भीटर तगर
  - वर्ग मीटर से 250 वर्ग मीटर
  - वर्ग मीटर से बड़े
  - सुविधाओं की स्थिति
    - विकास-चरण संख्या/क्षेत्र/ चोड़ाई/लंबाई
    - पार्क/परिवहन लॉट्स/ सामान्य खुला स्थल
    - स्कूल
    - समाज सदन
    - सामान्य पार्किंग क्षेत्र
    - डिसोंसरी/स्वास्थ्य केन्द्र
    - पार्मिक संरचना
    - पुलिस पोस्ट/फायर पोस्ट

#### संलग्नक:

- (क) सदस्यों/स्वामियों/अधिभोगियों की सूची
- (ख) रेजिडेंट्स सोसायटी का पंजीकरण/संकल्प
- (ग) नियमितीकरण प्तान्स/ले-आउट प्लान
- (घ) वचन बंधपत्र
- (ङ) प्रमाणित पूर्वि स्वामित्व दस्तावेज/खसरा गिल्दावरी
- (च) भुगतानों की रसीद

अधिकृत हस्ताक्षरकर्ता के हस्ताक्षर रेजिडेंट्स सोसायटी

6. नियमन के लिए मानदण्ड/आधार

6.1 भूमि का हक

भूमि का हक देने के लिए, समुचित संशोधित दिशानिर्देश, 2007 तैयार करने के लिए रा.रा.क्षे. दिल्ली सरकार दि.वि.प्रा. के प्रतिनिधियों के साथ वरीयत: 2 माह की समय-सीमा के अन्दर एक कमेटी का गठन करेगी।

्र 6.2 योजना मानदण्ड दि. मु.यो.—2021 के पैरा 4.2.2.2 (बी) में यथा निहित संबंधित प्रावधान लागू होंगे।

6,3 मिश्रित उपयोग

दि.मु. यो.—2021 के संगत प्रावधान संबंधित स्थानीय निकाय द्वारा मिश्रित उपयोग सड़कों (स्ट्रीट्स)/स्थानीय व्यावसायिक स्ट्रीट की घोषणा के आधार पर लागू होंगे।

6.4 भूमि की लागत और विकास प्रभारों की वसूली
यूनिट एरिया विधि के आधार पर सम्मित्त कर की वसूली
हेतु कॉलोनियों के वर्गीकरण के लिए दिल्ली नगर निगम
द्वारा अपनाए गए मानदण्ड के आधार पर नियमितीकरण
उद्देश्य हेतु, कॉलोनियों को मुख्यत: तीन समूहों के अंतर्गत
वर्गीकृत किया जाता है, जो कि निकटवर्ती नियोजित कॉलोनी
की अपेक्षा दो स्तर कम से मानक पर आधारित है।

समृह I : श्रेणी सी एवं डी में अनिधकृत कॉलोनियां। समृह II : श्रेणी ई एवं एफ में अनिधकृत कॉलोनियां। समृह III: श्रेणी जी में अनिधकृत कॉलोनियां।

संस्कारी भृमि की लागत निम्नानुसार बस्रुल की जाएगी :--

(क) अविकसित सार्वजनिक/सरकारी भृमि हेतु :

संमूह-। की कालोनियों में :

कृषि भूमि को प्रचलित अधिग्रहण लागत (575 रुपए प्रति वर्ग मी.) + 100 वर्ग मीटर तक के प्लाट आकार हेतु 10 प्रतिशत जुर्माना राशि और 100 से 250 वर्ग मीटर तक के प्लाट साइज के लिए 25 प्रतिशत जुर्माना राशि, और 250 वर्गमीटर से बड़े प्लाट साइज के लिए 50 प्रतिशत जुर्माना राशि ।

समृह II की कालोनियों में :

कृषि भूमि की प्रचलित अधिग्रहण लागत में से 15 प्रतिशत घटाकर + 100 से 250 वर्गमीटर तक के प्लाट साइज के लिए 10 प्रतिशत जुर्माना राशि और 250 वर्ग मीटर से बड़े प्लाट साइज के लिए 25 प्रतिश जुर्माना राशि । 100 वर्ग मीटर तक के प्लाट साइज के लिए कोई जुर्माना राशि वसुल नहीं की जाएगी ।

समूह Ш की कालोनियों में :

कृषि भूमि की प्रचलित अधिग्रहण लागत में से 30 प्रतिशत घटाकर + 100 से 250 वर्ग मी. तक के प्लाट साइज के लिए 5 प्रतिशत जुर्माना राशि और 250 वर्ग मी. से बड़े प्लाट साइज के लिए 10 प्रतिशत जुर्माना राशि वसूल की जाएगी। 100 वर्ग मीटर तक के प्लाट के लिए कोई जुर्माना राशि वसूल नहीं की जाएगी। (ख) विकसित सार्वजनिक भूमि/सरकारी भूमि हेतु:
अधिसूचित भूमि-दर और जुमांना राशि (100 वर्ग मीटर
तक के प्लाट के लिए 10 प्रतिशत तथा 100 वर्ग मीटर से
यडे प्लाट के लिए 50 प्रतिशत)।

(ग) रा.रा.क्षे. दिल्ली सरकार द्वारा निजी भूमि के रूप में निर्धारित की गई भूमि पर बसी हुई अधनाब्य (नॉन-एपलूएंट) कॉलोनियों से कोई भी परिवर्तन प्रभार अथवा संघटन-शुल्क वसूल नहीं किया जाएगा। उपर्युक्त दरें समय-समय पर परिवर्तनीय रहेंगी।

7. विविध

7.1 संस्वीकृति प्रदान करना अथवा मना करना :-स्थानीय निकाय योजनाओं को अनुमोदित अथवा संशोधित
कर सकता है अथवा जैसा वह आवश्यक समझे उन्हें
संशोधनों/निर्देशों सिहत मंजूर कर सकता है तथा
विनिर्धारित रूप में नोटिस देकर संबंधित व्यक्ति को अपना
निर्णय प्रेपित करेगा। जिन मामलों में प्लान में दिशा-निर्देश,
2007 अथवा विनियमों का पर्याप्त उल्लंघन पाया जाएगा,
उन मामलों में स्थानीय निकाय प्लान को रद्द कर सकता है
अथवा 'रेजिडेंट सोसाइटी' द्वारा उन्हें संधोंधित कराने का
आदेश दे सकता है।

7.2 इन विनियमों को, संशोधित दिशा-निर्देश, 2007 के साथ पढ़ा जाए और एक तालमेल के साथ इनका प्रतिपादन किया जाए ताकि अनिधकृत कॉलोनियों के नियमितीकरण की प्रक्रिया सुविधाजनक हो सके।

7.3 नियमितीकरण की सम्पूर्ण प्रक्रिया को स.स.क्षे. दिल्ली सरकार द्वारा समन्वित और पर्यवेक्षित किया जाना है, जो संशोधित दिशा-निर्देश, 2007 और इन विनियमों को और भी अधिक प्रचार-प्रसार देगी।

[सं-फा. 3(11)2004/एम.पी./पार्ट-I] विश्व मोहन बसल, प्रधान आयुक्त एवं सचिव

अनुबंध

अन्धिकृत कॉलोनी के नियमन हेतु जांच-सूची

- 1. कॉलोनी का नाम और पता
- 2 रा.स.क्षे. दिल्ली सरकार की सूची
- रेजिडेंट्स वैलफेयर एसोसिएशन्/ आवेदक की सोसायटी का नाम
- रेजिडेंट्स वैलफेय एसोसिएशन सोसायटी की पंजीकरण संख्या
- 5. अधिकृत हस्ताक्षरकर्ताओं के नाम
- कॉलोनी की श्रेणी (दि.न.नि. सम्पत्तिकर के अनुसार)
- 7. राजस्व गांव/खसरा सं.
- जोन (दिल्ली मुख्य योजना के अनुसार)

1075 GI 08-2

- 4.5.2.5 Information required to be furnished on Existing/ Proposed Layout Plan:
  - (i) The boundaries of the site and of configuous hand with ownership status;
  - (ii) The position of the site in relation to neighbouring area/roads;
  - (iii) The name of the streets in which the plots are proposed/existing;
  - (iv). The use and position of the plots on the land including sub division;
  - (v) The means of access/roads streets and their widths;
  - (vi) The North point;
  - (vii) Any existing physical features, such as wells, drains, trees etc;
  - (viii) The plan shall be authenticated by the authorized signatory of Resident Society and Architect/Town Planner.

#### 4.5.3 Undertakings

The Residents' Society shall furnish the following undertakings at the time of submission of the layout plan:

- (i)-That they shall abide by the layout plans as may be approved with or without conditions.
- (ii) That they shall transfer the land available if any for social infrastructure in the name of the DDA or the MCD/NDMC, free of cost, in order to provide such social, infrastructure.
- 5. Steps/Procedure to be followed by Local Body/ DDA/GNCTD for regularization:
- 5.1 A separate Cell is to be created in the local bodies/
  DDA/GNCTD to carry out the work relating to regularization of unauthorized colonies within their jurisdiction. The layout plan prepared by Resident Societies would be submitted to this Cell.
- 5.2 On receipt of the layout plan submitted by the Resident Society, the Local Body or DDA, as the case may be, within two months will complete the scrutiny of the layout plan.
- 5.3 Simultaneously, GNCTD will finalize the, boundaries of each identified colony within three months from the last date of submission of layout plan by using satellite/aerial survey images.
- 5.4 After fixing the boundaries on the scrutinized layout plan by the Local Body concerned, GNCTD to formally forward the layout plan to Local Body for approval.

- 5.5 Lay-out plan to be approved by the compotent authority in the Local Body concerned within one month of receipt of LOP after fixation of boundaries by GNCTD.
- 5.6 Simultaneously, the Local Body to refer the case to GNCTD for regularization and to DDA for land use change.
- 5.7 Formal orders or regularization to be issued by GNCTD only after completing all formalities including land use change and payment of all requisite charges.
- 5.8 The cost of land shall be collected by Local Body/
  DDA on behalf of land owning agency in respect
  of colonies on public land. Amounts so recovered
  to be credited to the account of respective land
  owning agency.
- 5.9 Similarly, penalties to be collected by Local Body/ DDA and to be credited into a separate fund.
- 5.10 GNCTD may commence the development works and augmentation of infrastructure facilities in public interest in colonies soon after the receipt of layout plan if it is satisfied that the colonies or part thereof fulfil the general principles contained in the Revised Guidelines 2007.
- 5.11 GNCTD shall take all required steps to ensure that the entire process of regularization except change in land use is completed within six months and formal regularization after effecting change in land use is done within nine months of submission of LOP by Resident Society. Lt.

  Governor, Delhi may relax the time limit in respect of individual colonies on specific request of GNCID.

#### 6. Parameters/basis for regularization

- 6.1 Title of land
  - GNCTD shall constitute a Committee with representatives of DDA to evolve suitable Revised Guidelines-2007 to confer title of land preferably within a time frame of two months.
- 62 Planning norms
  Relevant provisions as contained in para 4.2.2.2(B)
  of MPD 2021 to apply.
- 6.3 Mixed Use
  - The relevant provisions of MPD-2021 shall be applicable subject to declaration of mixed use street/local Commercial Street by the concerned Local Body.
- 6.4 Recovery of cost of land and development charges
  - Based on criteria adopted by the Municipal Corporation of Delhi for categorization of colonies for recovery of property tax based on Unit Area Method, the colonies are broadly clubbed under three groups for regularization purpose based on the criteria of two stage lower than adjacent planned colony:

Group-I: Unauthorized Colonies in Category C

and D

Group-II: Unauthorized Colonies in Category

Group-III: Unauthorized Colonies in Category
G

The cost of Government land shall be recovered as under:

(a) For undeveloped public/Govt. land

#### În Group-I colonies:

Prevailing Cost of acquisition of agricultural land (Rs. 575 per sqm) + 10% penalty for plot size up to 100 sqm and 25% penalty for plot size from 100 to 250 sq. m, and 50% penalty for plot size peyond 250 sqm.

#### In Group-II colonies:

Prevailing Cost of acquisition of agricultural land minus 15% + 10% penalty for plot size from 100 to 250 sqm and 25% penalty for plot size beyond 250 sqm. No penalty is to be levied for plot size up to 100 sqm.

#### In Group-III coloities:

Prevailing Cost of acquisition of agricultural land minus 30%; +5% penalty for plot size from 100 to 250 sqm and 10% penalty for plot size beyond 250 sqm. No penalty is to be levied for plot size up to 100 sqm.

- (b) For developed public land/Govt, land

  Notified land rate and penalty (10% up to 100 sqm
  plot and 50% beyond 100 sqm plot).
- (c) No conversion charges or compounding fee for non-affluent colonies on lands identified as private land by the GNCTD shall be levied.

Above rates are subject to changes from time to time.

#### 7. Miscellaneous

- 7.1 Grant of Sanction or Refusal The Local Body may either approve or modify the plans, or may sanction them with modifications or directions as it may deem necessary and thereupon shall communicate its decision to the person giving the notice in the prescribed form. In cases where the plans are substantially violative of the guidelines-2007 or the Regulations, the Local Body may reject or cause the plans to be modified by the Resident Society.
- 7.2 These Regulations may be read together with the Revised Guidelines 2007 and may be interpreted harmoniously so as to facilitate the process of regularization of the unauthorized colonies.
- 7.3 The entire process of regularization is to be coordinated and supervised by GNCTD, which

may also give wide publicity to the Revised Guidelines 2007 and these Regulations.

[F. No. 3(11)2004-MP-pt. I] V. M. BANSAL, Pr. Commr.-cum-Secy.

Annexure

Check list for Regularization of Unauthorized Colony

- 1. Name and address of the Colony
- 2. Serial No. in the GNCTD List, if any
- -3. Name of RWA/Applicant Society
- 4. Registration no. of the RWA/Society
- 5. Name of Authorized Signatories
- 6. Category of colony (as per MCD Property Tax)
- 7. Revenue Village/khasra no.
- 8. Zone (As per Master Plan of Delhi)
- 9. Date from which unauthorized colony exists
- Location/surroundings (Towards North, South, East West)
- 11. Development Area No:

MCD/NDMC/Cantt. Board Area/Whether falls in Notified Slum Area?

- 12. Total area of Unauthorized Colony
- 13. Land Status
- 14. Court Case, if any (Please attach details)
- 15. Land whether notified for acquisition
- 16. Percentage of Residents/house owners as members of the Residents Society
- 17. No. of Built up Plots:
  - (i) Up to 100 sq.m.——
  - (ii) Above 100 sqm & upto 250 sqm.-
- (iii) Above 250 sqm.-
- 18. No. of Vacant Plots:
- (i) Upto 100 sq.m.——
- (ii) Upto 100 250 sqm.----
- (iii) Above 250 sqm.
- 19. Status of Facilities Nos./ Arca/ Stage of Width/ Length Development
- Parks / Transport lots/ Common open space;
- Schools
- Community Hall
- Common Parking Areas
- Dispensary / Health Centre
- Religious structures
- Police Post / Fire Post
  - --Enclosures:
    - (a) Lists of members/owners/occupants.
    - (b) Registration/ resolution of the Residents Society.
    - (c) Regularization Plans / Layout Plan.
  - (d) Undertakings
  - (e). Certified Land Ownership documents/ Khasra Gildawari (f) Receipt of payments.

Signature of Authorized Signatory Resident Society

Printed by the Manager, Govt. of India Press, Ring Road, Mayapuri, New Delhi-110064 and Published by the Controller of Publications, Delhi-110054.

- 6 Parameters/basis for regularization
  - 6.1- Title of land
  - 6.2 Planning norms
  - 6.3 Mixed use
  - 6.4 Recovery of cost/development charges
- 7. Miscellaneous
- 7.1 Grant of sanction or refusal
- 7.2 Regulations to be read together with Guidelines
- 7.3 GNCTD to Coordinate, etc.
- 1. Introduction

Ministry of Urban Development vide letter dated 05-10-2007 conveyed the Revised Guidelines 2007 for regularization of unauthorized colonies in Delhi which also referred to orders of Supreme Court dated 14-02-2006 in WP@ No. 725 of 1994 and orders of Delhi High Court dated 27-2-2001 in CW(P) No. 4771 of 1993. The High Court order stipulates notification of the colonies to be regularized as per the guidelines and framing of modalities.

- 2. Definitions
- (a) "Architect/Town Planner": An architect registered with the Council of Architecture and having qualification in Town Planning, recognized for the membership of Institute of Town Planners, India;
- (b) "Concerned agency" means Local Body/Delhi Development Authority (DDA)/ Government of NCT of Delhi (GNCTD) or any other agency involved in the process of regularization/ preparation, implementation of the plans and work of regularization of unauthorized colonies falling within their respective jurisdictions;
- (c) "Habitations" for the purpose of regularization as envisaged in the Revised Guidelines 2007/ Regulations means those habitations existing as on 31-3-2002 that have come up as extension to village abadi and have not been notified as Lal Dora extension to village abadi;
- (d) "Infrastructure" means infrastructure other than 'social infrastructure' such as water supply, drainage, sewerage, electricity and solid waste management, as mentioned in the Chapter 14 (Physical Infrastructure) of the Master Plan for Delhi (MPD)-2021.
- (e) "Layout Plan" means a plan that will indicate the location of all existing (also proposed, if any) roads with their widths, dimensions of plots along with building lines, location of drains and public facilities, if any, a statement indicating the total area of the site under roads, and if available, then open spaces for parks, playgrounds, recreational spaces and other public spaces;

- (f) "Residents' Society" means a registered Resident Society and comprising the members of the unauthorized colony/habitation which will be responsible for coordination, preparation of layout plans, and for liaison with the concerned agency in respect of various issues pertaining to the regularization process;
- (g) "Service Road" A road/lane provided at the rear or side of a plot for service purposes;
- (h) "Site or Plot" A parcel/piece of land enclosed by definite boundaries;
- "Social infrastructure" means social infrastructure facilities pertaining to health, education, sports facilities and socio-cultural activities and religious activities.
- (j) "Street" includes any way, road, lane, square, court, alley, gully, passage, whether a thoroughfare or not and whether built upon or not, over which the public have a right of way and also the roadway or footway over any bridge or causeway;
- (k) "Unauthorized colony" means a colony/ development comprising of contiguous area, where no permission of concerned agency has been obtained for approval of Layout Plan, and/ or building plan;
- Criteria for Regularization of Unauthorized Colonies and Habitations
  - 3.1 Cut off date for regularization is 31-3-2002.
  - 3.2 Habitations that have come up as extension to village abadi and are outside the Lal Dora of village, would be eligible for regularization on the same lines as those of unauthorized colonies.
  - 33 The following types of colonies or parts thereof would not be considered for regularization:
    - (a) Unauthorized colonies/part of colonies/ habitations falling in notified or reserved forest areas.
  - (b) Unauthorized colonies/part of colonies/ habitations which pose hindrances in the provision of infrastructure facilities or fall in the area of right of way (ROW) of existing/proposed railway lines; Master Plan roads and major/trunk water supply and sewerage lines.
  - (c) Unauthorized colonics/habitations where more than 50% plots are un-built on the date of formal announcement of regularization scheme. However, plots, which have been built up in the above mentioned colonies, even after 31-3-2002

1075 GI/08-3

- and till the date of formal announcement of regularization scheme will be taken into consideration for deciding the eligibility of the colony for regularization.
- (d) Unauthorized colonies/part of colonies/ habitations which violates the provisions of Ancient Monuments and Archeological Sites and Remains Act, 1958.
- 3.4 No regularization will be done in respect of residential buildings used for non-residential purposes except those covered under the mixed land use regulations contained in the MPD-2021 as may be amended from time to time. The time limit of 90 days for conducting survey for notification of mixed use streets as prescribed in clause 15.3.4 of the MPD-2021 in respect of these colonies will commence with effect from the date of notification of the colony as deemed regularized colony by the GNCTD or the date with effect from which the colony shall qualify for regularization.
- 3.5 Action against unauthorized constructions in unauthorized colonies/parts of colonies/habitations which do not fulfill the conditions for regularization, will be taken by concerned Local Body/DDA subject to provisions contained in Master Plan of Delhi including those in para 16.2.3.
- 3.6 These Regulations do not relate to unauthorized colonies/habitations inhabited by affluent sections on public and private land.

#### 4. Procedure for regularization

The following steps are to be followed for regularization:

- 4.1 Registration of Residents' Society
  - The residents of each unauthorized colony/ habitation shall establish a registered Residents Society (henceforth cailed as Resident Society). This shall be a pre-condition for considering the case for regularization. There would be no objection to several associations in a colony, but they would have to be federated into one recognized Residents Society. The Local Body shall only recognize and interact with such Residents Societies which have at least 75% of residents of that colony as its members.
- 4.2 The Resident Society shall perform/carry out the following functions:
- 4.2.1.1 Liaise with the concerned agency in various matters pertaining to the regularization process.
- 4.2.1.2 Prepare through an Architect/Town Planner, the existing layout plan of the colony. The Resident Society may, however, voluntarily also submit proposal for improved Layout Plan in respect of their colony.

- 4.2.1.3 The Layout Plan thus prepared shall be submitted by the Resident Society to the concerned Local Body/DDA, and simultaneously, a copy of the Layout Plan shall also be submitted to GNCTD by the Resident Society.
- Along with the layout plan, the Resident Society shall be required to submit the complete list of members with details such as plot nos. and area of the colony to the Local Body. It shall be the duty of the Resident Society to make available, wherever possible, land to the concerned agency for taking up the works for provision of social infrastructure. In such colonies where land cannot be made available by the society for social infrastructure, the colony shall have to manage without the provision of such infrastructure.
- 4.2.3 There shall be no obligation on part of the Local Body/DDA/GNCTD/Union of India to allot alternate sites/flats to residents who may be displaced on account of provision of land for civic amenities/infrastructure which are not regularized as in clause 3.3.
- 4.2.4 The GNCTD shall determine the development charges/processing fee, if any, to be charged from the Residents Societies/individuals.
- 4.3 The Resident Society shall be required to submit the layout plan and proposal for improved layout plan if any. It shall be submitted in such manner and numbers as the GNCTD may deem fit.
- Once sanctioned, a printed authenticated copy of the layout plan shall be made available by the Resident Society to all its members. Any deviation and modification in the sanctioned layout plan shall be subject to approval by the concerned Local Body/DDA.
- 4.5 Requisites for submission of Layout Plan:
- 4.5.1 Documents to be submitted

Application for regularization of unauthorized colonies shall be accompanied by the following documents:

- (i) Land details with Khasra No. accompanied by a site plan giving the physical description of the site.
- (ii) The certificates duly signed by the authorized signatory of Resident Society/owner and the Architect/Town Planner.
- (iii) The layout plan submitted with the application for regularization shall be drawn to a scale of 1: 1000 or larger and shall show details as given in the following paragraphs.

# (TO BE PUBLISHED IN THE PART IV- OF THE DELHI GAZETTE) EXTRAORDINARY

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
(HEALTH & FAMILY WELFARE DEPARTMENT)

9<sup>TH</sup> Level, A-Wing, Delhi Secretariat, New Delhi-110002

No. F.24/Misc/NH/DHS/94/PF/A-2/ Dated, the 16<sup>th</sup> May, 2008

## NOTIFICATION

No. F.24/Misc/NH/DHS/94/PF /A-2 – The following draft of Rules further to amend the Delhi Nursing Homes Registration Rules, 1953, which the Lt. Governor of the National Capital Territory of Delhi proposes to make in exercise of the powers conferred by section 16 of the Delhi Nursing Homes Registration Act, 1953 (Delhi Act 6 of 1953), is hereby published for the information of persons likely to be affected thereby, and notice is, hereby, given that the said draft will be taken into consideration after the expiry of a period of thirty days from the date on which copies of the Delhi Gazette containing this notification are made available to the public, together with any objections or suggestions, that may be received in respect thereto by the stipulated period.

The objections and suggestions in this behalf should be addressed to the Director of Health Services, Government of NCT of Delhi, F-17, Karkardooma, Shahdara Delhi-110032: -

1

#### DRAFT RULES

- Short title and commencement. (1) These rules may be called the Delhi
  Nursing Homes Registration (Amendment) Rules, 2008.
- (2) They shall come into force with immediate effect:

  Provided that the nursing homes already registered on the date on which these rules come into force shall comply with these rules within a period of ninety days from the said date.
- 2. Amendment of rule 6. In the Delhi Nursing Homes Registration Rules, 1953 (hereinafter referred to as "the principal Rules"), in rule 6, for sub-rule (1), the following sub-rule shall be substituted, namely: -
  - "(1) An application for the renewal of registration shall be made every third year, in Form 'B' in advance in the month of January and shall be accompanied by the fee prescribed in rule 7."
- 3. Substitution of new rule for rule 7. In the principal Rules, for rule 7, the following rule shall be substituted, namely:
  - " 7. Fees for registration and for renewal of registration for a period of three years. (1) The fees to be paid for registration and for renewal of registration shall be charged as under: -

#### Bed Strength

Upto ten beds

Eleven beds to thirty beds

Thirty-one beds to one hundred beds

One hundred beds onwards

#### Registration /Renewal Fees

Two thousand rupees
Three thousand rupees
Eight thousand rupees
Eight thousand rupees plus one
hundred twenty five rupees per bed
for number of beds above one
hundred beds.

(2) Where the fee for renewal is not deposited in time as required under rule 6, a late fee amounting to ten percent of the renewal fee shall be charged per month or part thereof.

. . . .

- (3) Failure to deposit the fee for renewal of registration within six months of the last date prescribed under sub-rule (1) of rule 6 shall result in refusal of the application for renewal and removal of name from the register."
- 4. Substitution of new rule for rule 11. In the principal Rules, for rule 11, the following rule shall be substituted, namely:-
  - "11. Issue of duplicate certificates. In the event of a certificate of registration being lost, mutilated or destroyed, the holder may apply to the supervising authority for a fresh certificate and the supervising authority, if it thinks fit, may issue such certificate upon payment of a fee of five hundred rupees. A certificate issued under this rule shall be marked 'DUPLICATE'."
- 5. Amendment of rule 12. In the principal Rules, in rule 12, -
  - (i) for the shoulder heading, the following shoulder heading shall be substituted, namely: -
  - "12. Records of patients admitted or children born in the nursing home. -";
  - (ii) for sub-rule (1), the following sub rule shall be substituted, namely: -
  - "(1) The keeper of a nursing home shall keep --
  - (a) in the Form "D" appended to these rules, a register of patients admitted into the nursing home as per the guidelines framed by the supervising authority from time to time;
  - (b) a correct alphabetical index of the names of the patients admitted in the nursing home in accordance with the admission register as per Form "D";

(c) record of health of every patient admitted in the nursing home containing the following information in addition to any other information, that may be required by the supervising authority and as per guidelines framed by the supervising authority from time to time:-

(1) Admission number

(2) Name -----son/daughter/wife of Shri-----

- (3) Age
- (4) Sex
- (5) Occupation
- (6) Religion
- (7) Doctor in charge of the case
- (8) Date and time of admission
- (9) Date of discharge
- (10) Admitting diagnosis
- (11) Final diagnosis
- (12) Result/out come of the case
- (13) Case summary
- (14) Record of investigations
- (15) Consent
- (16) Details of operative procedure and anesthesia, if given
- (17) Records of treatment
- (18) Records of nursing care
- (19) Special record and progress notes for patient admitted in ICU/ICCU
- (20) Diet
- (21) If medico legal case, date and time of information to police
- (22) Summary of Medico Legal case given to police;
- (d) in the Form "E" appended to these rules, a record of every maternity case admitted into the nursing home and of every child delivered;

4

(e) in the Form "F 1& F 2" appended to these rules, a record of all the miscarriages, medical termination of pregnancies and stillbirths occurring in the nursing home as per the provisions under MTP Act (F 1) and PNDT Act (F 2)."

6. Substitution of new rule for rule 13. — In the principal Rules, for rule 13, the following rule shall be substituted, namely:

"13.Intimation of death occurring in nursing home. — If any death occurs in the nursing home, the keeper of the nursing home shall, within twenty four hours from the occurrence of death, furnish the information in respect of such death to the supervising authorities in Form "G", together with any other information that may be required by it and to the Medical Officer of Health MCD/NDMC/Cantonment Board having jurisdiction over the area in which the nursing home is situated."

7. Substitution of new Schedule for the Schedule. - In the principal Rules, for the Schedule, the following Schedule shall be substituted, namely:-

#### "SCHEDULE

(See rule 14)

Requirements to be complied with by a nursing home:

1. Location and surroundings. — The nursing home shall be situated in a place having clean surroundings and shall not be adjacent to an open sewer, drain or public lavatory or to a factory emitting smoke or obnoxious odour. The nursing home shall have sufficient facilities for parking area for the visitors, as per the municipal byelaws in force from time to time/as per norms of MPD 2021.

#### 2. Buildings. -

2.1 The building used for the nursing home shall comply with the municipal byelaws as in force and such guidelines as may be framed by the Government from time to time and the use of the premises shall conform to the land use prescribed under the relevant law(s).

- 2.2 The rooms in the nursing home shall be well ventilated and lighted and shall be kept in clean and hygienic conditions. Arrangements shall be made for cooling the rooms in summer and heating them in winter.
- 2.3 The walls of the labour room and operation theatre up to a height of 1.22 metre (4 feet) from the floor shall be of such construction as to render it waterproof. The flooring shall be such as not to permit retention or accumulation of dust. There shall be no chinks or crevices in the walls or floors.
- 2.4 Aseptic conditions shall be maintained in labour room and the operation room.
- 2.5 Adequate arrangements shall be made for isolating septic and infectious cases.
- 3. Space accommodation for the patients, etc. -
- 3.1 A nursing home providing facility for a single specialty or additional specialty shall have sufficient waiting area for the patients and attendants with proper sitting arrangements and other facilities near the reception/registration counter and shall have appropriate infrastructure according to the specialty or specialties. The floor space in the general nursing home shall not be less than 7.43 square metre (80 square feet) for one bed and additional minimum 5.57 square metre (60 square feet) for every additional bed in the room and the area shall not include the area for toilet for the patient.
  - 3.2 A nursing home having facility for intensive care shall, in the main areas, have a space of 18.59 square meter (200 square feet) per bed. There shall be sufficient storage space for medicines and equipments (for ventilators, special beds, suction machine, transport equipment, wheel chair carts, monitors, etc.). The intensive care units shall have sturdy large shelves, wide room access with touch less door openers and outlets for battery charging. The space for doctors/staff on duty shall be in addition to the intensive care unit bed space. The supportive service rooms (changing rooms, duty rooms, attendant room) shall be near the intensive care unit. There shall be space for readily accessible storage (one for 2/4 bedded pod;

3-4 for 10 bedded ICU), crash cart alcoves (with electrical outlets), medication station, refrigerator, lockable cabinet (narcotics), countertop work area, storage cabinet/ drawers, X-ray view box.

3)

- 3.3 Besides the main areas in the intensive care units, the ancillary areas shall include space for communication (house telephones, intercommunication system and emergency code alarm system), clerical space (filing cabinets and drawers) and public space adjacent to unit and prayer area.
- 3.4 A nursing home which intends to provide facilities for a newborn nursing or neonatal care unit shall have 4.65 square meter (50 square feet) per neonatal bed with provision of separate area for hand wash and gowning, formula preparation, stores and duty room for doctors. The floor area and walls upto 1.22 metre (4 feet) shall be washable.
- 4. Operation theatre and labour room. The operation theatre shall be provided with a minimum floor space of not less than 13.94 square metre (150 square feet), and the labour room with an area of not less than 9.29 square metre (100 square feet) per table. The labour room shall have the facilities and equipments for neonatal resuscitation unit.
- 5. Provision of duty room. A duty room shall be provided for the nursing staff on duty.
- 6. Storage space. Adequate space for storage of medicines, food articles, equipments, etc. shall be provided.
- 7. Water supply. The water used in the nursing home shall be pure and of drinkable quality.
- 8 Health clothing and sanitary requirements of staff. -
  - 8.1 The staff employed shall be free from contagious disease, and shall be provided with clear uniforms suitable to the nature of their duties.

- 8.2 The workers shall be medically examined at the time of employment and periodically so examined thereafter. The worker shall be vaccinated against all contagious diseases to which they are exposed or have a high risk of being exposed.
- 9. The equipments and Linens, etc. . The nursing home shall -
- 9.1 provide and maintain adequate number of commodes, bedpans and slop sinks, with flushing arrangements;
- 9.2 have high pressure sterilizer and instrument sterilizer;
- 9.3 have an uninterrupted supply of oxygen through adequate number of oxygen cylinders fitted with all necessary attachments and flow meter, for safe and hygienic delivery of oxygen to the patients;
- 9.4 have apparatus for transfusions, necessary equipments, instruments, apparatus and medicines of such quality and numbers, as are required in accordance with to the services offered by the nursing home;
- 9.5 have the equipments and drugs required in the neonatal resuscitation unit in the labour room and in the neonatal care unit as per guidelines framed by the supervising authority from time to time;
- 9.6 in case providing facilities for intensive care, have monitoring, diagnostic, radiological, therapeutic/supportive and bedside facilities and availability of drugs as per the guidelines framed by the supervising authority from time to time;
- 9.7 have adequate quantity of bed sheets, mattresses, pillows, blankets, draw sheets and other linens;
- 9.8 have a separate almirah under lock and key for poisons.

10. Food. – If the nursing home provides diet to the patients, it shall be prepared and served in hygienic conditions.

#### 11 Nursing Staff. -

- 11.1 There shall be one qualified nurse on duty at all times having minimum qualification as general nursing and midwifery course, registered with the Delhi Nursing Council, for every ten beds or a fraction thereof in the nursing home: Provided that a part of nursing staff may be substituted with the prior approval of the supervising authority by other trained staff like midwife, pharmacist, dressers, etc. according to the specific needs of the nursing home.
- 11.2 The nursing home providing facilities of intensive care shall have the qualified staff nurses with experience of working in a 10 bedded ICU/CCU for one year. At one point of time there shall not be more than 40% inexperienced staff nurses, who have not had experience of working in intensive care unit for one year, thus ensuring that there would be availability of minimum 60% experienced staff nurses in one shift. The staff nurses shall be available in the ratio of 1:1 round the clock and for every 10 nurses there shall be one qualified supervisor in the intensive care unit round the clock. The paramedical staff posted in the intensive care unit shall have the previous experience of working in the intensive care unit.
- 11.3 The nursing home providing newborn nursing or neonatal care unit, hall also have 1:1 nurses patient ratio.
- 12. Records. Separate stock registers shall be maintained by the nursing home for
  - (a) equipment,
  - (b) instruments, and
  - (c) linens.

#### 13. Doctor. -

- 13.1 There shall be one qualified doctor of modern scientific system of medicine having registration with the Delhi Medical Council, round the clock for every 20 beds or fraction thereof, and the consultant of the concerned speciality shall be on call, in the nursing home.
- 13.2 In the nursing homes providing intensive care, there—shall be a postgraduate doctor (MD) in the relevant speciality ICU. In case of nursing home providing facilities of super speciality, the consultant of relevant specialty shall be available on call. The consultant concerned shall possess requisite post-doctoral qualification:

Provided that in case of non availability of a postgraduate doctor, a doctor after graduation, having experience of working for one year in a 10 bedded general ICU/CCU under the supervision of a consultant, may be considered for working as resident doctor in the ICU/CCU. The ratio of the doctors shall be in the ratio of 1:4 beds round the clock and the consultants shall be on call.

#### 14 Co-operation at the time of natural calamity or disaster. -

- 14.1 In the event of any natural calamity or disaster, the owner or the keeper of every nursing home shall, on being requested by the supervising authority in writing co-operate and provide such reasonable assistance and medical aid as may be considered essential by the supervising authority at the time of natural calamity or disastrous situation.
- 14.2 The nursing home shall not refuse treatment to the injured/serious persons brought to them due to any reason, whatsoever.
- 15. Display of charges. The keeper of the nursing home shall ensure that the charges levied by the nursing home for the various services available in the nursing home are prominently displayed.

- 16. Provision of stand by generator. The keeper of the nursing home shall ensure the provision of stand by generator in case of the power failure in the nursing home.
- 17. Handling of biomedical waste. The nursing home shall abide by the Biomedical Waste (Management and Handling) Rules, 1998, as amended from time to time and shall also get authorization from Delhi Pollution Control Committee under these rules.
- 18. Disruption of services at a nursing home. Where the services of a nursing home are likely to be disrupted due to any reasons, the keeper shall give information about the same to the supervising authority, at least, four weeks in advance:

Provided that in the event of any exigency leading to disruption of services, the information shall be given to the supervising authority within twenty four hours of such disruption."

By order and in the name of the Lt. Governor of the National Capital Territory of Delhi,

(VIVEK RAE)

PRINCIPAL SECRETARY (HEALTH & FAMILY WELFARE)

# GUIDELINES REGARDING BASIC REQUIREMENTS, ESSENTIAL EQUIPMENTS AND DRUGS ETC. FOR ICU/ ICCU OPERATING IN THE PRIVATE HOSPITALS/ NURSING HOMES

Critical Care Units or Intensive care units are, such patients' units, which are responsible for a specifically defined and limited number of acutely ill, unstable, or potentially unstable patients who require constant instrument monitoring and a core of full time nurses and staff with specialized training. The critical care units would broadly include cardiac care units and intensive care units. The most common intensive care units are Medical Intensive Care Units (MICU), Surgical Intensive Care Units (SICU), Pediatric Intensive Care Units (PICU), Neurological Intensive Care Units (Neuro ICU), Neonatal Intensive Care Units (NICU), and Burn Units.

The intensive care units should have the following facilities

#### GENERAL ICUs

#### (A). Space Requirement

(1) Main

There should be a space of 200 square feet /bed for maintaining ICU bed. There should be sufficient storage space for medicine and equipment (for ventilators, special beds, suction machine, transport equipment, wheel chair carts, monitors etc.). It should have sturdy, large shelves, wide room access with touch less door openers and outlets for battery charging. The space for doctors, Nurses and staff on duty should be in addition to ICU bed space.

The supportive service rooms e.g. changing rooms, Duty rooms, attendant room should be near the ICU. Stand by electric supply system in case of failure of electricity must be available

Bedside (Readily accessible Storage) (one for 2/4 bedded pod; 3-4 for 10 bedded ICU) Crash cart alcoves (with electrical outlets)

Medication station

Refrigerator

Lockable cabinet (narcotics)

h



Countertop work area
Storage cabinet/ Drawers
X-ray view box

#### (ii) Ancilliary areas

#### a) Communication

House telephones

Intercommunication system

Emergency code alarm system

## b) Clerical space (preferably separate)

Filing Cabinets, Drawers etc.

#### c) Public space (Adjacent to unit)

Telephone (House and public)

Prayer area

#### B. Equipments (Essential)

# (i) Monitoring equipments with recording data storing and analyzing facilities

ECG machine /monitor

SpO2 '

Defibrillator facility

Temperature- Multiparameter

ETCo2 .

·NIBP

Infusion Pumps Syringe

Difficult intubation/ extubation carts

Nebulisers (Ultrasonics)

Optional

Cardiac output

## (ii) Diagnostic

h

Facilities of ABG machine, Electrolyte machine,

Haematocrit, K.F.T, Glucose Measurement facilities should be available round the clock within the ICU/Hospital

#### (iii) Radiological

Imaging X-rays, bedside ultrasonography facilities.

All basic imaging facilities and all investigative radiological procedure should be available. There should be assured arrangement for CT Scan and bedside Echocardiography facility.

#### (iv) Therapeutic/ Supportive

Ventilator/s

#### (v) Bedside Facilities

Central pipeline system for oxygen supply, vaccum suction, Blood Pressure monitoring System, Nitrous oxide, Air for ventilators. Sufficient electrical sockets to avoid electrical wires to crisscross, Air mattresses, Wheel Chairs, Shifting Trolleys. Adjustable bed with overhead trolly, Detachable bed.

#### SPECIALISED ICUs

All other ICUs such as Neurological ICU, Neonatal ICU, Medical ICU, Surgical ICU, should have equipments as per their requirements besides the requirements in a general ICU.

The Neurology/ Neurosurgery ICU must have CT Scan Facility.

The Coronary Care Units (CCU) must have cardiac monitor and temporary pacing and facilities for fluoroscopy and invasive arterial/venous pressure monitoring and Intra-aortic balloon counter pulsation facilities.

The facilities of Coronary Angiographies as optional,

h



#### (C) Essential Drugs and Consumbales

I Drugs: - There should be availability of required drugs / fluids in the ICU at all times and at no point of time there should be any shortage of drugs in the ICU.
A list of essential drugs is given below:

### (i) Induction/ Sedation agents

Thiopentone

Ketamine

Propofol '

Midazolam

Diazepam

Morphine

Pethidine

Pentazocine

Promethazine

Chlorpromazine

## (ii) Relaxants

Suxamethonium

Vecuronium

Pancuronium

Rocuronium

Atracurium

## (iii) Inotrops

Adrenaline

Noradrenaline

Dopamine

Dobutamine

#### (iv) Antibiotics

## (v) Bronchodilators

Deriphyllin

Aminophyline

h

(16)

Terbutaline

Nebulisation solution (Asthaline, Ipravent, Budicort, Mucolytic)

(vi) Infusions.

Esmolol

Nitroglycerine

Sodium Nitroprusside

Insulin

TPN Solution

Manitol

(vii) Other drugs

Metoprolol

Frusemide

Ranitidine

Metoclopramide

Onadamsetrone

Local anaesthetics (Lidocaine, Bupivacaine)

Antiarrythymic (Adenosine, Xylocard, Cordarone, Bretyllium)

Vitamine K

Low Molecular Weight Heparin

Dilitiazem

Diclofenac

Tramadol

Atropine

PAM

Inj. Avil

Inj. Decadron

Inj. Hydrocortisone

Inj.Stemetil

Inj. Emeset

Inj. Digoxin

Glycopyrrolate

Neostigmine

5

n

Calcium Gluconate

Sodabicarb

Inj Potassium Chloride and Syrup Potassium Chloride

Magnesium

Multivitamins

Local anaesthetic jelly

Eye ointment

Antiseptic solutions and ointments

Cleaning / disinfecting solutions

Antisnake venome

Colloids (Polygeline, Starches, Dextrans, Albumin)

Mexiletine

#### II. Consumbales

Endotracheal tubes (all sizes)

Tracheostomy tubes all sizes)

LMAs (including ILMA) (all sizes)

Face masks (all sizes)

Oropharyngeal airtways (all sizes)

Nasopharyngeal airways (all sizes)

Non touch suction apparatus

Suction catheters (all sizes)

Heat and Moisture exchangers (For use with ETT, Tracheostomy tube)

Incentive spirometers

I/V Cannulae

Three ways

CVP lines (all sizes)

Intra-arterial Cannulae

Foley's Catheters

Nasogastric tubes

CPAP Masks

Venturi Mask

Binasal Cannulae

Nasal Spectacle
Percutaneous dilatation tracheostomy set
Sterile dressings
Disposable Gloves, Masks, Syringes and needles, Shoe Covers.
Temporary pacing leads 6F.7F
Temporary pulse generator
Check Flow (5-7F) and Swan Ganz Catheter
Arterial Puncture Needle.
Sterile drape Sheets

#### (D). Staff requirement

#### (i) Doctors

There should be a post graduate doctor (MD) in the relevant specialty ICU and the consultant of relevant specialty should be available on call, in case of superspecialty. The consultant concerned must possess requisite post-doctoral qualification. In case of non availability of a post graduate doctor, a doctor after graduation, having experience of working for one year in a 10 bedded general ICU/CCU under the supervision of a consultant may be considered for working as Resident doctor in ICU/CCU. The doctors should be registered with Delhi Medical Council and the ratio of the doctors should be in the ratio 1:4 beds round the clock and the consultants should be on call.

#### (ii) Nursing Staff

There should be staff nurses with minimum qualification as General Nursing and Midwifery Course; having registration with Delhi Nursing council with an experience of working in al0 bedded ICU/CCU for one year. At one point of time there should not be more than 40 % inexperienced staff nurses, who have not had experience of working in ICU for a period of one year, thus ensuring that there would be availability of minimum 60% experienced staff nurses in one shift. The staff nurses should be available in the ratio of 1:1 round the clock and for every 10 nurses there should be one Qualified Supervisor in the ICU round the clock.

#### Paramedical Staff (iii)

The paramedical staff posted in the ICU should have the previous experience of working in the ICU.

#### General services (E)

Fire safety features Air conditioning / Heating Grounded electric points Emergency Power source Circuit Breaker access Proper Lighting

The facilities for transport of the patients to other Hospitals or High Centres should be available with each of the ICU/ICCU.

These recommendations have been made to be the guidelines for an ICU/ICCU and are not exhaustive, and they may need revision from time to time.

## BASIC REQUIREMENT OF ESSENTIAL EQUIPMENTS AND DRUGS IN THE NEWBORN CARE UNIT/NEONATAL CARE UNIT AND NEONATAL RESUSCITATION UNIT IN NURSING HOMES

#### Newborn care unit:

- 1. A nursing home intending to provide a newborn care unit shall have the following essential equipments and facilities:
  - a) A stethoscope with neonatal chest-piece for each Neo-natal bed
  - b) Baby weighing machine
  - c). Oxygen hood box and other oxygen delivery apparatus like humidifier and regulator
  - d) Phototherapy unit
  - e) Uninterrupted availability of oxygen and compressed air
  - f) Oxygen analyzer (oximeter)
  - g) Non-invasive blood pressure monitor
  - h) Heart rate and/or apnea monitor
  - i) Newborn resuscitation kit.
  - j) Transport incubator
  - k) Suction machine
  - i) Air thermometer
  - m) Radiant heat source

There shall be facilities to get requisite biochemical and hematological test done round the clock, as may be required for management of a sick baby, facilities for infection control such as uninterrupted water supply and isolation of infected babies, safe and adequate method for handling of soiled and dirty linen or other infected waste.

#### Neonatal resuscitation unit in labour room:

- a) A functioning wall clock with seconds arm or a stop clock.
- b) Radiant heat source.
- c) Pressure controlled suction machine and requisite number of mucus extractors.
- d) Two working infant laryngoscopes with neonatal sized blades.
- e) Requisite facilities for IPPR with self-inflating bag, well fitting neonatal facemask, endotracheal tubes and appropriate adapters.
- f) Umbilical vein cannulations set.
- g) Baby weighing machine.
- h) Essential drugs needed during resuscitation.

## GUIDELINES FOR MAINTAINING RECORDS OF THE PATIENTS IN THE NURSING HOMES

The nursing homes shall maintain the records as per the format given below in the Forms

FORM "D" Register of patients admitted

FORM "E" Records of every maternity cases admitted in the nursing home.

FORM "F" Records of miscarriages, MTP cases and still births occurring in the fixefy nursinghomes 4 PNDT AM

FORM "G" Records of deaths occurring in the nursing homes

Amount of the state of the stat	Whether MLC (Y/N)	Register of p Admn. Name, S/o, D/o No. W/o & address	
	Outcome or/ and remarks	Age x x x x x x x x x x x x x x x x x x x	
	07 /	admitted to  Bate & time of Admn.	
		FORM"D": (See rule 1 Admitting Diagnosis	
		12)  Final C  diagnosis	
		Doctor I/c	
		Cate/of Discharge/ Death/LAMA	
		arge.	
		1 1 1	

FORM "D"

			٠											
				_	-\					Z 0.	<b>₽</b>	Adm		
				•	2	1	SS	Addre	W/o &	D/o,	, S/o,	Name		Register
	,	•			ω							Age/Sex		Register of patients admitted to
	<u> </u>				4	_			Admin	of	ime			admitted
 					5			,			diagnosis	Admitting		0
 	<u> </u>				ග						Ciagnosio	Hinal		
						4	-		_	9	Case	1/C of	Doctor	
	*****			 	C	0		•			Death/	of discharge/	Date & time	Č
 :					(	Q.	•			****		MLC (Y/N) or / and	Whether	
						10			,		remarks	or / and	Outcome	
 				 		-								

(See rule 12)
----Nursing Home/ Hospital

14

FORM I

(Name and qualification of the Registered Medical practitioner in block letters)

(Full address of the Registered Medical practitioner)

(Name and qualification of the Registered Medical practitioner in block letters)

..... (Full address of the Registered Medical practitioner)

hereby certify that \*I/ We am/are of opinion, formed in good faith, that it is necessary to terminate the pregnancy of......(Full name of pregnant women in block letters)

for the reasons given below\*\*

\*I/we hereby give infilmation that \*I/We terminated the pregnancy of the woman referred to above who bears the serial no...............................in the Admission Register of the hospital/approved place.

Signature of the registered Medical Practitioner/Practitioners

Place: Date:

• Strike out whichever is not applicable,

• Of the reasons specified items (1) to (v) write the one which is appropriate.

(i) in order to save the life of the pregnant women,

(ii) in order to prevent grave injury to the physical and mental health of the pregnant women,

(III) In view of the substantial risk that if the child was born it would suffer from such physical or mental abnormalities as to be seriously handicapped,

(iv) as the pregnancy is alleged by pregnant women to have been caused by rape.

(v) as the pregnancy has occurred as result of failure of any contraceptive device or methods used by married woman or her husband for the purpose of limiting the number of children.

Note—Account may be taken of the pregnant women's actual or reasonably foreseeable environment in determining whether the continuance of her pregnancy would involve a grave injury to her physical or mental health.

Place: Date:

Signature of the registered Medical Practitioner/Practitioners

-	No. of Institution reporting		Andrews (Address)		East District Dollar
1010	no. of M.T.P case done_				
prec	IK UD of the total as a			<b></b>	
Durc	ation of pregnancy (give total	ises Il No only			
		ito. omy			
(a	The state of the s		٠	•	
(b	) Up to 12-20 weeks.		-		•
Age	group		]		,
	·			٠	
(a)			1		
(b)				•	
(d)	2024			•	
(e)	2529 3034				•
	25 00				
(g)	4044			•	
(h)	45 & above				
(i)	not available				
		[			
	W. I	<u></u>			•
	Tota	11 = .			•
₹elig	ion of women	•			
(a)	Hindu		•		•
(p)	Muslim		•		•
(c)	Christian		•		•
(C)					
<u> </u>	<u>-L</u> _				
<u> </u>	Others				
(d)	<u>-L</u> _				
(d)	Others Total	·		· . ·	
(d)	Others Total		*		
(d)	Others Total	head)			
(d) Rea	Others  Total  sons for termination: tal number under each sub-	· · · · · · · · · · · · · · · · · · ·			
(d) Rea	Others  Total  sons for termination: tal number under each sub-	ant woman.			
(d) Rea	Others  Total  sons for termination: tal number under each sub-	ant woman.			
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn	ant woman. If health of the preana	nt woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica	ant woman. If health of the pregna health of the pregnant	nt woman.		
(d)	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica	ant woman. If health of the pregna health of the pregnant	nt woman. I woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape.	ant woman. Il health of the pregna health of the pregnant	nt woman. t woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the et	ant woman.  I health of the pregnanthealth of the pregnanthe	nt woman. t woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the critical would suffer from such physical abnormalities as to be sorie	nant woman.  If health of the pregnant health of the pregnant health of the pregnant hild was born, ysical or mental	nt woman. t woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the critical would suffer from such physical abnormalities as to be sorie	nant woman.  If health of the pregnant health of the pregnant health of the pregnant hild was born, ysical or mental	nt woman. I woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the cr it would suffer from such ph abnormalities as to be serio Failure of any contraceptive	nant woman.  If health of the pregnant health of the pregnant health of the pregnant hild was born, ysical or mental	nt woman. I woman.		
(d) Rea	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the critical would suffer from such physical abnormalities as to be sorie	nant woman.  If health of the pregnant health of the pregnant health of the pregnant hild was born, ysical or mental	nt woman. t woman.		
Rea to	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the ch it would suffer from such ph abnormalities as to be serio Failure of any contraceptive	nant woman.  If health of the pregnant health of the pregnant  If health of	nt woman. t woman.		
(d) Readye to	Others  Total  sons for termination: tal number under each sub- Danger to life of the pregn Grave injury to the physica Grave injury to the mental Pregnancy cause by rape. Substantial risk that if the cr it would suffer from such ph abnormalities as to be serio Failure of any contraceptive	nant woman.  If health of the pregnant health of the pregnant  If health of	nt woman. t woman.		

Signature of the Officer in charge with Date

(36)

16 F 1

## FORM III (See Regulation 5)

## Admission Register

S. No.	Date of Admission	Name of the patient	Wife / Daughter of	Age	Religion	Address	
1	2	3	4	5	6	7	1

Duration Of Pregnancy	Reasons on Which Pregnancy Is Terminated	Date of termination Of Pregnancy	Date of Discharge Of patient	Result and Remarks	Name of Registered Medical Practitioner (s) by who the opinion is formed	Registered medical practitioner (s) by whom pregnancy is terminated
8	9	10	11	12	13	14

h

#### "FORM A

[See rules 4(1) and 8(1)] (To be submitted in Duplicate with supporting documents as enclosures)

SEPLICATION FOR REGISTRATION OR RENEWAL OF REGISTRATION OF A GENETIC COUNSELEERS CENTRE/GENETIC LABORATORY/GENETIC CLINIC/ULTRASOUND CLINC/IMAGING CENTRE

क्ति के the applicant ്രീം. hame of the organisation sought to be registered)

Additions of the applicant

Please specify whether the application is for registration of a Genetic Counselling Centre/Genetic Laboratory/Genetic Clinic/Ultrasound Clinic/Imaging Centre or any combination of these)

- 4. Full name and address/addresses of Genetic Counselling Centre/Genetic Laboratory/Genetic Clinic/ Ultrasound Clinic/Imaging Centre with Telephone/Fax number(s)/Telegraphic/Telex/E-mail address (s).
- 5. Type of ownership of Organisation (individual ownership/partnership/company/cooperative/any other to be specified). In case type of organization is other than individual ownership, furnish copy of articles of association and names and Saddresses of other persons responsible for management, as enclosure.
- 6 Type of Institution (Govt. Hospital/Municipal Hospital/Public Hospital/Private Hospital/Private Nursing Home/Private Clinic/Private Laboratory/any other to be stated.)
- 7. Specific pre-natal diagnostic procedures/tests for which approval is sought
- (a) Invasive (i) amniocentesis/ chorionic villi aspiration
- /chromosomal/biochemical/molecular studies
- (b) Non-Invasive Ultrasonography
- Leave blank if registration is sought for Genetic Counselling Centre only.
- & Equipment available with the make and model of each equipment (List to be ettached on a separate sheet).
- (a) Facilities available in the Counselling Centre.
- (b)Whether facilities are or would be available in the Laboratory/Clinic for the following tests:
  - Ultrasound
  - (ii) Amniocentesis
  - Chorionic villi aspiration (iii) Foetoscopy (iv)

  - (v) Foetal biopsy
  - (vi) Cordocentesis
  - able in the Laboratory/ Clinic for the following
    - Chromosomal studies (i)
    - Biochemical studies (ii)
    - (iii) Molecular studies
    - Preimplantation genetic diagnosis , (iv)
- 10 Names, qualifications, experience and registration number of employees (may be furnished as an enclosure).
- 11 State whether the Genetic Counselling Centre/Genetic Laboratory/Genetic Clinic/ultrasound clinic/imaging centre [11] qualifies for registration in terms of requirements laid down in Rule 3 ]

\CL Sh./Smt./Kum./Dr....son/daughter/wife of ......aged ......years record in (indicate name of the organisation to be indicate. hereby declare that I have read and understood the Pre-natal Discourse Techniques (Regulation and Prevention of Misuse) Act, 1994 (57 of 1994) and the Pre-natal Diagnostic Techniques (Regulation and Prevention of Misuse) Rules, 1996, I also undertake to explain the said Act and Rules to all employees of the Genetic Counselling Centre/Co-Laboratory/Genetic Clinic/ultrasound clinic/imaging centre in respect of which registration is sought and to ensure items of the contraction of th Place authorized to Name, designation and signature of the pension sign on behalf of the organisation to be registered [SEAL OF THE ORGANISATION SOUGHT TO BE REGISTERED. ACKNOWLEDGEMENT [See Rules 4(2) and 8(1)] The application in Form A-in duplicate for grant\*/renewal\* of registration of Genetic Counselling Centre\*/Genetic of applicant) has been received by the Appropriate Authority ...... On (date). \*The list of enclosures attached to the application in Form A has been verified with the enclosures submitted and cund to be correct. OR \*Ón verification it is found that the following documents mentioned in the list of enclosures are not actually enclosed This acknowledgement does not confer any rights on the applicant for grant or renewal of registration. Signature and Designation of Appropriate Authority, or authorized Date: Office of the Appropriate Authority. Place: SEAL

ORIGINAL/DUPLICATE FOR DISPLAY FORM B

[See Rules 6(2), 6(5) and 8(2)]

#### CERTIFICATE OF REGISTRATION (To be issued in duplicate)

Centre\* named below for purposes of carrying out Genetic Counselling/Pre-natal Diagnostic Procedures\*/Pre-natal Diagnostic Tests/ultrasonography under the aforesaid Act for a period of five years ending on ......

- This registration is granted subject to the aforesaid Act and Rules thereunder and any contravention there. shall result in suspension or cancellation of this Certificate of Registration before the expiry of the said period of Ex years apart from prosecution.
  - Name and address of the Genetic Counselling Centre\*/Genetic Laboratory\*/Genetic Clinic\*/Ultrasound Clinic\*/Imaging Centre\*.
  - Pre-natal diagnostic procedures\* approved for (Genetic Clinic). B.

Non-Invasive

(i) Ultrasound

Invasive

(ii) Amniocentesis

(iii) Chorionic villi biopsy

(iv) Foetoscopy

- (v) Foetal skin or organ biopsy
- (vi) Cordocentesis

(vii) Any other (specify)

- Pre-natal diagnostic tests\* approved (for Genetic Laboratory)
  - Chromosomal studies
  - Biochemical studies (ii)
  - Molecular studies (iii)
- Any other purpose (please specify)
- 3. Model and make of equipments being used (any change is to be intimated to the Appropriate Authority under rule 13).
- 4. Registration No. allotted
- 5. ..Period of validity of earlier Certificate of Registration. (For renewed Certificate of Registration only)

From ...... To ......

Signature, name and designation of The Appropriate Authority

Date:

C.

SEAL

DISPLAY ONE COPY OF THIS CERTIFICATE AT A CONSPICUOUS PLACE AT THE PLACE OF BUSINESS



#### FORM C [See Rules 6(3), 6(5) and 8(3)]

# FORM FOR REJECTION OF APPLICATION FOR GRANT/RENEWAL OF REGISTRATION

- Name and address of the Genetic Counselling Centre\*/Genetic Laboratory\*/Genetic Clinic\*/Ultrasound Clinic\*/Imaging Centre\*
- Reasons for rejection of application for grant/renewal of registration: (2)

Signature, name and designation of the Appropriate Authority with SEAL of Office

Date: Place:

\*Strike out whichever is not applicable or necessary.

F-2-1

#### FORM D [See rule 9(2)]

### FORM FOR MAINTENANCE OF RECORDS BY THE GENETIC COUNSELLING CHAIR.

- Name and address of Genetic Counselling centre.

   Registration No.
- 3. Patient's name
- 4 ^~~
- 4. Age
- 5. Husband's/Father's name
- 6. Full address with Tel. No., if any
- 7. Referred by (Full name and address of Doctor(s) with registration No.(s) (Referral note to be preserved carefully with case papers)
- 8. Last menstrual period/weeks of pregnancy
- 9. History of genetic/medical disease in the family (specify) Basis of diagnosis:
  - (a) Clinical
  - (b) Bio-chemical
  - (c) Cytogenetic
  - (d)Other (e.g.radiological, ulrasonography)
- 10. Indication for pre-natal diagnosis
  - A. Previous child/children with: -
    - (i) Chromosomal disorders
    - (ii) Metabolic disorders (iii) Congenital anomaly
    - (iv) Mental retardation
    - (v) Haemoglobinopathy
    - (vi) Sex linked disorders
    - (vii) Single gene disorder(viii) Any other (specify)
  - B. Advanced maternal age (35 years or above)
  - C. Mother/father/sibling having genetic disease (specify)
  - D. Others (specify)
- 11. Procedure advised<sup>2[2]</sup>
  - (i) Ultrasound
  - (ii) Amniocentesis
  - (iii) Chorionic vilii biopsy
  - (iv) Foetoscopy
  - (v) Foetal skin or-organ biopsy
  - (vi) Cordocentesis
  - (vii) Any other (specify)
- 12. Laboratory tests to be carried out
  - (i) Chromosomal studies
  - (ii) Biochemical studies
  - (iii) . Molecular studies (iv) Preimplantation genetic diagnosis
- 13. Result of diagnosis
  If abnormal give details.

Normal/Abnormal

- 14. Was MTP advised?
- 15. Name and address of Genetic Clinic\* to which patient is referred.
- 16. Dates of commencement and completion of genetic counseling.

(AV)

[See Rule 9(3)]
FORM FOR MAINTENANCE OF RECORDS BY GENETIC LABORATORY

Name and address of Genetic Laboratory

Registration No

Patient's name

Husband's/Father's name

Full address with Tel. No., if any

Referred by/sample sent by (full name and address of Genetic Clinic) (Referral note to be preserved carefully with case papers)

Type of sample: Maternal blood/Chorionic villus sample/amniotic fluid/Foetal blood or other foetal tissue (specify) 8

Specify indication for pre-natal diagnosis A. Previous child/children with

- Chromosomal disorders Metabolic disorders
- Malformation(s)
- Mental retardation
- Hereditary haemolytic anaemia Sex linked disorder (vi)
- Single gene disorder
- (viii) Any other (specify)
- B. Advanced maternal age (35 years or above)
  C. Mother/father/sibling having genetic disease (specify)
  D. Other (specify)
- Laboratory tests carried out (give details)

  (i) Chromosomal studies 10.

  - Biochemical studies (iii)
    - Molecular studies
  - (iv) preimplantation gentic diagnosis
- Result of diagnosis If abnormal give details.

Normal/Abnormal

Date(s) on which tests carried out.

The results of the Pre-natal diagnostic tests were conveyed to ...... on ......

Name, Signature and Registration No. of the Medical Geneticist/Director of the Institute

Place: Date:

9.

#### FORM F

[See Proviso to Section 4(3); Rule 9(4) and Rule 10(1A)]
OR MAINTENANCE OF RECORD IN RESPECT OF PREGNANT WOMAN BY GENETIC CLINIC/ULTRAMMENT
CLINIC/IMAGING CENTRE

Name and address of the Genetic Clinic/Ultrasound Clinic/Imaging Centre.

Registration No.

Patient's name and her age

Number of children with sex of each child

Husband's/Father's name

Full address with Tel. No., if any

Referred by (full name and address of Doctor(s)/Genetic Counselling Centre (Referral note to be preserved carefully with case papers)/self referral

Last menstrual period/weeks of pregnancy

History of genetic/medical disease in the family (specify) Basis of diagnosis:

- (a) Clinical
- (b) Bio-chemical
- (c) Cytogenetic
- (d) Other (e.g.radiological, ultrasonography etc. specify)
- Indication for pre-natal diagnosis
  - A. Previous child/children with:
    - Chromosomal disorders
    - Metabolic disorders
    - Congenital anomaly
    - Mental retardation (iv)
    - Haemoglobinopathy (v)
    - Sex linked disorders (vi)
    - Single gene disorder (vii)
    - (viii) Any other (specify)
  - B. Advanced maternal age (35 years)
  - C. Mother/father/sibling has genetic disease (specify)
  - D. Other (specify)
- Procedures carried out (with name and registration No. of · Gynaecologist/Radiologist/Registered Medical Practitioner) who performed it.

Non-Invasive

pregnancy) [List of indications for ultrasonography of pregnant women are given in the note below]

Invasive

- Amniocentesis (ii)
- Chorionic Villi aspiration (iii).
- Foetal biopsy (iv)
- Cordocentesis (v)
- Any other (specify) (vi)

Any complication of procedure - please specify

pre-natal diagnostic procedure we details)

(b) Ultrasonography specify abnormality detected, if any).

Normal/Abnormal

Date(s) on which procedures carried out.

Date on which consent obtained. (In case of invasive)

The result of pre-natal diagnostic procedure were conveyed to ......on .....

18. Was MTP advised/conducted?

19. Date on which MTP carried out.

Date: Place

Name, Signature and Registration number of the Gynaecologist/Radiologist/Director of the Clinic

DECLARATION OF PREGNANT WOMAN (name of the pregnant woman) declare that by undergoing ultrasonography /image scanning exdo not want to know the sex of my foetus.

Signature/Thump impression of pregnant women.

3 Strike out whichever is not applicable or not necessary

## DECLARATON OF DOCTOR/PERSON CONDUCTING ULTRASONOGRAPHY/IMAGE SCANNING

\_ (name of the person conducting ultrasonography/image scanning) declare that while conduction: ultrasonography/image scanning on Ms. \_\_\_\_\_ (name of the pregnant woman), I have neither detected nor disclose:

> Name and signature of the person conducting ultrasonography/image scanning Director or owner of genetic clinic/ultrasound clinic/imaging centre

#### important Note:

(i) Ultrasound is not indicated/advised/performed to determine the sex of foetus except for diagnosis of sex-linked diseases such as Duchenne Muscular Dystrophy, Haemophilia A & B etc. (ii)

During pregnancy Ultrasonography should only be performed when indicated. The following is the representative list of indications for ultrasound during pregnancy.

To diagnose intra-uterine and/or ectopic pregnancy and confirm viability.

Estimation of gestational age (dating).

(2) (3) (4) Detection of number of foetuses and their chorionicity.

Suspected pregnancy with IUCD in-situ or suspected pregnancy following contraceptive failure/MTP failure (5) (6)

Follow-up of cases of abortion.

Assessment of cervical canal and diameter of internal os. (7)

Discrepancy between uterine size and period of amenorrhoea. (8) (9)

Any suspected adenexal or uterine pathology / abnormality.

Detection of chromosomal abnormalities, foetal structural defects and other abnormalities and their follow-(10)(11)

To evaluate foetal presentation and position.

(12)Assessment of liquor amnii.

Preterm labour / preterm premature rupture of membranes. (.13)

Evaluation of placental position, thickness, grading and abnormalities (placenta praevia, retroplacental (14)haemorrhage, abnormal adherence etc.). (15)

Evaluation of umbilical cord – presentation, insertion, nuchal encirclement, number of vessels and presence of true knot. (16)

Evaluation of previous Caesarean Section scars. (17)

Evaluation of foetal growth parameters, foetal weight and foetal well being. (18)

Colour flow mapping and duplex Doppler studies. (19)

Ultrasound guided procedures such as medical termination of pregnancy, external cephalic version etc. and their follow-up. (20)

Adjunct to diagnostic and therapeutic invasive interventions such as chorionic villus sampling (CVS).



FORM G [See Rule 10] FORM OF CONSENT (For invasive techniques)

<i>*</i>	·		. ,		
	wife/daught	ter of	explained fully the prob	Age able side effe	
the pre-natal	diagnostic procedures.				
	n to undergo the preimplantation/pre-nat of any abnormality (i.e. disease/deformit				wn interest to are:
	ertake not to terminate the pregnancy if tmity/disorder.	the pre-nata	al procedure/technique/	est conducte	d show the above or
l und	erstand that the sex of the foetus will not	be disclose	ed to me.		
	erstand that breach of this undertaking v Regulation and Prevention of Misuse) Ac				
Date Place			Signature of the pregna	nt woman.	
-	•			•	
	e explained the contents of the above toRelationship				
			NT.	<b>3</b>	residents beautions and the
		•	Gynaecologist/Medical	Geneticist/Ra	/Registration number or adiologist/Paediatrician Clinic/Centre/Laboratory
			•		
Date					
		Name,	Address and Registratio	n number of	Genetic Clinic/Institute
					SEAL

4

#### FORM H [See Rule 9(5)]

PRIM FOR MAINTENANCE OF PERMANENT RECORD OF APPLICATIONS FOR GRANT/REJECTION UNDER THE PRE-NATAL DIAGNOSTIC TECHNIQUES (REGULATION AND PREVENTION MISUSE) ACT, 1994.

- 1.Sl. No.
- 2. File number of Appropriate Authority.
- 3. Date of receipt of application for grant of registration.
- 4.Name, Address, Phone/Fax etc. of Applicant:
- 5.Name and address(es) of Genetic Counselling Centre\*/Genetic Laboratory\*/Genetic Clinic\* / Ultrasound Clinic\*/Imaging Centre\*.
- 6.Date of consideration by Advisory Committee and recommendation of Advisory Committee, in summary.
- 7.Outcome of application (state granted/rejected and date of issue of orders record date of issue of order in Form B or Form C).
- 8. Registration number allotted and date of expiry of registration.
- 9. Renewals (date of renewal and renewed upto).
- 10. File number in which renewals dealt.
- 11. Additional information, if any.

Name, Designation and Signature of Appropriate Authority

## Guidance for Appropriate Authority

- (a) Form H is a permanent record to be maintained as a register, in the custody of the Appropriate Authority.
- (b) \* Means strike out whichever is not applicable.
- (c) On renewal, the Registration Number of the Genetic Counselling Centre/Genetic Laboratory/C Clinic/Ultrasound Clinic/Imaging Centre will not change. A fresh registration Number will be allotted in the exchange of ownership or management.
- (e) Registration number shall not be allotted twice.
- (f) Each Genetic Counselling Centre/Genetic Laboratory/Genetic Clinic/ Ultrasound Clinic/Imaging Centre in allotted a folio consisting of two pages of the Register for recording Form H.
- (g) The space provided for 'additional information' may be used for recording suspension, cancellations, rejec application for renewal, change of ownership/management, outcome of any legal proceedings, etc.
- (h) Every folio (i.e. 2 pages) of the Register shall be authenticated by signature of the Appropriate Authority with and every subsequent entry shall also be similarly authenticated.".

(Ms. K. Sujath: Joint Secretary to the Government of

[No.N.24026/14/2002-PND

Footnote:- The Principal Notification was published in the Gazette of India vide No.G.S.R. 1(E) dated 1<sup>st</sup> January
This is the first amendments to the Pre-Natal Diagnostic Techniques (Regulation and Prevention of Misuse) Rules 1996

FORM "G"

(See rule 13)

FORMAT FOR DEATH REGISTER

_						,					 				
Remarks			-		10						-		•	•	
Whether MLC	(Y/N) If yes	P.S. where	registered		6				-					,	•
Date	8 time	of	Death		8										
Cause of	Death		,		7		•	٠							
Doctor	I/C of	the	case .		9			,.							
Final	Diagno	Sis			5										
Age/	Sex				4					 			•		
Name	No. S/o, Sex Dia	D/o,	W/o &	address	3										
Admn.	So.				2							-			-
S.No.								,			 				

(दिल्ली राजपत्र भाग-4 असाधारण में प्रकाशनार्थ) राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार (स्वास्थ्य एवं परिवार कल्याण विभाग) 9वां तल, ए-विंग, दिल्ली सचिवालय, इन्द्रप्रस्थ एस्टेट, नई दिल्ली-02

सं.फा. 24 /विविध / डीएचएस / 94 /पीएफ / ए-2 / 2518 6 - 202 विनांक: - 16 - 5 : 0 8

## अधिसूचना

सं.फा. 24 / विविध / एन एच / डीएचएस / 94 / पीएफ / ए-2 / — दिल्ली निर्संग होम पंजीकरण नियमावली, 1953 का फिर से संशोधन करने के लिये नियमावली का निम्नलिखित प्रारूप, जो दिल्ली राष्ट्रीय राजधानी के उपराज्यपाल दिल्ली निर्संग होम पंजीकरण अधिनियम, 1953 (1953 का दिल्ली अधिनियम 6) की धारा, 16 द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुये बनाना प्रस्तावित करते हैं, वह इससे प्रभावित होने वाले व्यक्तियों की जानकारी के लिये प्रकाशित किया जाता है और हैं, वह इससे प्रभावित होने वाले व्यक्तियों की जानकारी के लिये प्रकाशित किया जाता है और इसके द्वारा सूचना दी जाती है कि उक्त प्रारूप पर इस अधिसूचना वाले दिल्ली राजपत्र की प्रतियां, जिस तिथि से जनता को उपलब्ध होती हैं, उस तिथि से तीस दिन के अवधि बीतने के प्रतियां, जिस तिथि से जनता को उपलब्ध होती हैं, उस तिथि से जीस दिन के अवधि बीतने के प्रश्चात् इस संबंध में निर्धारित अवधि तक प्राप्त होने वाले किन्हीं आपित्तयों या सुझावों के साथ पश्चात् इस संबंध में निर्धारित अवधि तक प्राप्त होने वाले किन्हीं आपित्तयों या सुझावों के साथ विचार किया जायेगा ।

ावचार १कथा जायगा । इस संबंध में आपितायां तथा सुझाव निदेशक खाख्य सेवायें, दिल्ली सरकार, एफ-17, कड़कड़डूमा, शाहदरा, दिल्ली-110032 को भिजवाए जाने चाहिये ।

## प्रारूप नियमावली

- संक्षिप्त शीर्षक एवं प्रारम्भ :- (1) इन नियमों को दिल्ली नर्सिंग होम पंजीकरण (संशोधन) नियमावली, 2008 कहा जा सकता है ।
- (2) ये तत्काल प्रभावी होंगे ।

  शर्त यह है कि जिस तिथि से ये नियम प्रवृत्त होते हैं, उस तिथि को पहले ही

  शर्त यह है कि जिस तिथि से चंद्रे दिन के अविध के भीतर इन नियमों का पालन

  पंजीकृत निर्मिंग होम उक्त तिथि से चंद्रे दिन के अविध के भीतर इन नियमों का पालन
- करग ।
  नियम 6 का संशोधन : दिल्ली नर्सिंग होग पंजीकरण नियमावली, 1953 (इसके पश्चात् "मूल नियमावली" के रूप में संदर्भित) के नियम 6 के उप नियम (1) के स्थान पर "मूल नियमावली" के रूप में संदर्भित) के नियम 6 के उप नियम (1) "पंजीकरण के नियमलिखित उप नियम प्रति स्थापित किया जायेगा अर्थात् (1) "पंजीकरण के नियमलिखित उप नियम प्रति स्थापित किया जायेगा अर्थात् (1) "पंजीकरण के जिया नियम प्रति प्रत्येक तीसरे वर्ष जनवरी माह में फार्म ख अग्रिम में किया जायेगा और इसके साथ नियम 7 में निर्धारित शुल्क लगा होगा" ।
- जायेगा ओर इसक साथ ।नयम / न ।नवारित सुल्प राजा रहा । 3. नियम ७ के स्थान पर नये नियम का प्रतिस्थापन :- मूल नियमावली के नियम ७ के स्थान पर निम्नलिखित नियम प्रतिस्थापित किया जायेगा, अर्थात् :
- "तीन वर्ष की अविध के लिये पंजीकरण तथा पंजीकरण का नवीनीकरण का शुल्क
   पंजीकरण और पंजीकरण के नवीनीकरण के लिये भुगतान किये जाने वाला शुल्क निम्न प्रकार से वसूल किया जायेगा :

•••	
	पंजीकरण / नवीनीकरण शुल्क
बिस्तरों की संख्या	दो हजार रूपये
दस बिस्तरों तक	तीन हजार रूपये
ग्यारह से तीस बिस्तर	Tar our

इक्कतीस से एक सौ बिस्तर एक सौ से अधिक बिस्तर	`.	आठ हजार रूपये आठ सौ रूपये तथा एक सौ से अधिक बिस्तरों की संख्या के लिये एक सौ पच्चीस रूपये प्रति बिस्तर
--	----	---

- (2) जहां नियम 6 के अनुसार नवीनीकरण का शुल्क यथासमय जमा नहीं कराया जाता है, वहां नवीनीकरण शुल्क की दस प्रतिशत राशि के बराबर राशि विलम्ब शुल्क के रूप में प्रतिमाह या इसके भाग के लिये जमा करानी होगी ।
- (3) नियम 6 के उप नियम (1) के अन्तर्गत निर्धारित अन्तिम तिथि से छः माह के भीतर पंजीकरण के नवीनीकरण का शुल्क जमा कराने में विफलता के परिणामस्वरूप नवीनीकरण के आवेदन—पत्र का अस्वीकरण होगा ।"
- 4. नियम 11 के स्थान पर नये नियम का प्रतिस्थापन— मूल नियमावली के नियम 11 के स्थान पर निम्नलिखित नियम प्रतिस्थापित किया जायेगा अर्थात् :—
  - 11 "बुप्लीकेट प्रमाण पत्र जारी करना यदि पंजीकरण प्रमाण पत्र खो जाता है, विकृत या नष्ट हो जाता है तो वह नये प्रमाण पत्र के लिये पर्यवेक्षक प्राधिकारी को आवेदन कर सकता है और पर्यवेक्षक प्राधिकारी यदि उचित समझते हैं तो पांच सौ रूपये के शुल्क के भुगतान करने पर ऐसा प्रमाण पत्र जारी कर सकते हैं । इस नियम के अन्तर्गत जारी प्रमाण पत्र पर "बुप्लीकेट" उल्लिखित होगा ।"
- 5. नियम 12 का संशोधन— मूल नियमावली के नियम 12 में —— (1) मुख्य शीर्षक के स्थान पर निम्नलिखित प्रतिस्थापित किया जायेगा अर्थात् : "12 नर्सिंग होम में दाखिल रोगी या जन्म शिशु का अभिलेख <sup>\*</sup>
  - (11) उप नियम (1) के स्थान पर निम्नलिखित शामिल किया जायेगा । अर्थात् "(1) किसी नर्सिम होग का रखने वाला निम्नलिखित रखेगा —
  - (क) समय-समय पर पयर्वेक्षण अधिकारी द्वारा जारी मार्ग निर्देशों के अनुसार नर्सिंग होम में दाखिल रोगियों का रजिस्टर इन नियमों के साथ संलग्न फार्म 'डी' में,
  - (ख) फार्म **"डी"** में प्रवेश रजिस्टर के अनुसार नर्सिंग होम में दाखिल रोगियों के नाम, सही वर्णक्रम के अनुसार,
  - (ग) किसी अन्य जानकारी के अतिरिक्त नर्सिंग होम में दाखिल प्रत्येक रोगी के स्वास्थ्य का अभिलेखं निम्नलिखित जानकारी सहित जो पर्यवेक्षक अधिकारी को समय—समय पर पर्यवेक्षण अधिकारी द्वारा बनाये गये मार्ग निर्देशों के अनुसार चाहियः—
  - 1. प्रवेश संख्या
  - 2. नाम

पुत्र/पुत्री/पत्नी श्री

- 3. आयु
- 4. लिंग
- 5. व्यवसाय
- 6. धर्म

- केल का प्रभारीडाक्टर 7,
- 8, प्रवेश का समय व तिथि .....
- छुट्टी देने की तिथि: 9.
- .प्रवेश के समय रोग निदान 10
- अन्तिम निदान 11.
- मामले का परिणाम/नतीजा 12.
- नामले का सारांश 13.
- जांच का अभिलेख 14.
- 15. परामर्श
- शल्यचिकित्सा प्रक्रिया का विवरण तथा संवेदनाहरण यदि किया गया हो । 16.
- 17.
- नर्सिंग देखभाल का अभिलेख - 18.
- आईसीयू/आईसीसीयू में दाखिल रोगियों के लिये विशेष अभिलेख तथा प्रगति 19. 20.
- यदि चिकित्सीय टीप कानूनी मानला है तो पुलिस को सूचना देने की तिथि और 22.
- पुलिस को सौंपे चिकित्सीय कानूनी मामले का साराश
- इस नियमों के साथ संलग्न फार्म "ड़" में नर्सिंग होम में दाखिल प्रत्येक प्रसूति मामले और वहां पैदा हुये प्रत्येक शिशु का अभिलेख
- इन नियमों के साथ संलग्न फार्म "च 1 तथा च 2" में नर्सिंग होम में हुये गर्भपात, चिकित्सीय गर्भ समापन तथा मृत जन्में शिशुओं का सारा अभिलेख होगा तथा वे एमटीपी अधिनियम (एफ-1) तथा पी एन डी टी अधिनियम (एफ-2) के प्रावधानों का अनुसरण

- 79 - 73

- नियम 13 के स्थान पर नये नियम का प्रतिस्थापन : मूल नियमावली के नियम 13 के स्थान पर निम्नलिखित प्रतिस्थापित किया जायेगा, अर्थात् :--
- 13. नर्सिंग होम में हुई मृत्यु की सूचना :-यदि कोई मृत्यु निर्सिंग होम में होती है तो निर्सिंग होम का संचालक (कीपर) मृत्यु होने के दांबीस घंटों के भीतर ऐसी मृत्यु के संबंध में पर्यवेक्षण प्राधिकारी को फार्म "जी" में, जिस स्वास्थ्य चिकित्सा अधिकारी एमसीडी / एनडीएमसी/केन्टोमैन्ट बोर्ड के क्षेत्राधिकार में नर्सिंग होन स्थित है, उस स्वास्थ्य चिकित्सा अधिकारी को पर्यवेक्षण अधिकारी द्वारा अपेक्षित किसी अन्य जानकारी के साथ प्रस्तुत करेगा।"
- अनुसूची के स्थान पर नई अनुसूची का प्रतिस्थापन :-- मूल नियमावली की अनुसूची के स्थान पर निम्नलिखित अनुसूची प्रतिस्थापित की जायेगी अर्थात् :--

## अनुसूची (नियम 14 देखिए)

## किसी नर्सिंग होम द्वारा पालन की जाने वाली अपेक्षाएं

- 1. स्थान और आसपास :- नर्सिंग होम का स्थान और उसके आसपास का क्षेत्र साफ सुथरा होगा और किसी खुली सीवर लाइन, नाले या जनता शौचालय के निकट नहीं होगा या धुंआ छोड़ने वाले या गंदी/विषैली दुर्गंध छोड़ने वाले कारखाने के निकट नहीं होगा । नर्सिंग होम के पास समय—समय पर प्रचलित नगर निगम उपविधियों एम पी डी 2021 के अनुसार आगुन्तकों के लिये पार्किंग क्षेत्र की पर्याप्त सुविधायें होगी ।
- 2. भवन :2,1 नर्सिंग होम के लिये प्रयुक्त भवन प्रचलित नगर निगम उप विधियों का और समय-समय
  पर सरकार द्वारा बनाए गये ऐसे दिशा निर्देशों का अनुपालन करेंगे और परिसर का प्रयोग
  सम्बद्ध कानून/कानूनों में निर्धारित भूमि प्रयोग के अनुरूप करेगा ।
- 2,2 नर्सिंग होम के कमरे सुवातित (हवादार) प्रकाश वाले होंगे और उन्हें साफ सुथरा स्वास्थ्य कर परिस्थितियों में रखा जायेगा । गर्मियों में कमरे ठण्डे रखने और सर्दियों में गर्म रखने की व्यवस्था होगी ।
- 2,3 प्रसव कक्ष और शल्य चिकित्सा मंच की दीवार तल से 1.22 मीटर (4फुट) की ऊंचाई तक इस तरह निर्मित होगी ताकि यह जलरोधक हो ! फर्श ऐसे होंगे कि उन पर धूल नहीं जमी होगी । दीवारों या तलों में किसी प्रकार की छेद या सुराख/तेराड़ नहीं होंगे ।
- 2,4 प्रसव कक्ष और आपरेशन कक्ष एसेप्टिक होंगे ।
- 2,5 सेप्टिक तथा संक्रामक मामलों को अलग रखने के लिये पर्याप्त व्यवस्था की जायेंगी ।
- 3. रोगियों के लिये आवास, स्थान आदि :—
  3.1 किसी एक विशेषज्ञता या अतिरिक्त विशेषज्ञता के लिये सुविधा प्रदान करने वाले नर्सिंग होम में रोगियों तथा उनके परिचरों के लिये पर्याप्त बैठने की व्यवस्था तथा अन्य सुविधा वाला पर्याप्त प्रतीक्षा क्षेत्र स्वागत / पंजीकरण काऊंटर के समीप होना चाहिये और विशेषज्ञता के अनुसार पर्याप्त व्यवस्था होनी चाहिए । सामान्य नर्सिंग होम में तल क्षेत्र 7.43 वर्ग मीटर (80 वर्ग फुट) एक विस्तर के लिये तथा कमरे में प्रत्येक अतिरिक्त विस्तर के लिये 5.57 वर्ग मीटर (60 वर्ग फुट) से कम नहीं होना चाहिये तथा इसमें रोगियों के लिये शौचालय का क्षेत्र शामिल नहीं होगा ।
- 3.2 सघन चिकित्सा कक्ष की सुविधा वाले नर्सिंग होन में मुख्य क्षेत्र में 18.50वर्ग मीटर (200 वर्ग फुट) प्रति बिस्तर का स्थान होना चाहिये । इसमें दवाईयां तथा उपकरणों (वेंटिलेटर, विशेष बिस्तर, सक्शन मशीन, परिवहन उपकरण, व्हील चेयर कार्ट, मोनिटर आदि) को रखने के लिये पर्याप्त स्थान होना चाहिये । सधन चिकित्सा युनिटों में बड़े—बड़े सेल्फ, चौड़े दरवाजे जो बिना छुए खुले तथा बैटरी चार्जिंग के स्थान होने चाहिये । डॉक्टरों/


डयूटी पर स्टाफ के लिये स्थान सघन चिकित्सा कक्ष के अतिरिक्त होना चाहिये । सहायक सेवाओं के कक्ष (चेंजिंग रूम, ड्यूटी रूम, अटैंडेंट रूम) सघन चिकित्सा कक्ष के नजदीक होने चाहिये । इसमें मंडारण (एक 2/4 बैडिड पोड के लिये ; 3-4, 10 बैडिड आईसीयू के लिये) क्रेश कार्ट एल्कोब्स (इलैक्ट्रिक आउटलैंट वाले) मेडिकेशन स्टेशन, रेफिजरेटर, लोकेवल केबिनेट (नेरकोटिक्स) काउंटरटाप वर्क एरिया, स्टोरेज केबिनेट / द्राज, एक्सरे व्यू बॉक्स के लिये सुगमता से पहुंचा जा सकने वाला स्थान होना चाहिये ।

- 3.3 मुख्य सघन चिकित्सा कक्षों के क्षेत्र के अलावा आनुषंगिक क्षेत्रों में संप्रेषण (टेलिफोनों के लिये, इंटरकम्यूनिकेशन सिस्टम तथा एमरजेंसी कोड अलार्म सिस्टम), लिपिकीय स्थान (फाइलिंग केबिनेट तथा द्राज) तथा युनिट के साथ सार्वजनिक स्थान तथा प्रार्थना क्षेत्र आदि होगें।
- 3.4 नवजात शिशुओं या नवप्रसूति सुश्रुत युनिट की सुविधा प्रदान करने वाले नर्सिंग होम में 4.65वर्ग मीटर (50वर्ग फीट) का क्षेत्र प्रत्येक नवप्रसूति बिस्तर के लिये होना चाहिये जिसमें हाथ धोने तथा गाउनिंग, फार्मुला तैयार करने, भंडार तथा डाक्टरों के लिये ड्यूटी रूम के लिये अलग क्षेत्र होना चाहिये । फर्श क्षेत्र तथा 1.22मीटर (4फुट) तक दीवार धोई जा सकें ।
- 4. आपरेशन थियेंटर तथा लेबर रूम :- आपरेशन थियेटर का फर्श क्षेत्र 13.94 वर्ग मीटर (150 वर्ग फुट) तथा लेबर रूम 9.29 वर्ग मीटर (100 वर्ग फुट) प्रति टेबल से कम नहीं होना चाहिये । लेबर रूम में नवप्रसूति रिसस्सीटेशन युनिट की सुविधा तथा उपकरण होने चाहियें ।
- 5. ड्यूटी रूम की व्यवस्था :- ड्यूटी पर नर्सिंग स्टाफ के लिये ड्यूटी रूम होगा ।
- भंडारण स्थान :- दवाईयों, खाने का सामान, उपकरणों आदि के लिये पर्याप्त स्थान उपलब्ध कराया जायेगा ।
- जलापूर्ति :- नर्सिंग होम में प्रयोग किया जाने वाला पानी स्वच्छ तथा पीने योग्य गुणवत्ता का होना चाहिये ।
- स्वास्थ्य, कपड़े तथा स्टाफ की सफाई संबंधी आवश्यकतायें :--
- 8.1 नियुक्त किया गया स्टाफ संक्रामक रोगों से मुक्त होना चाहिये तथा उन्हें अपनी ड्यूटी की प्रकृति के अनुरूप स्वच्छ वर्दी प्रदान की जायेगी ।
- 8.2 कर्मचारियों को रोजगार दिये जाते समय चिकित्सा जाँच होगी तथा उसके पश्चात समय-समय पर जाँच की जाती रहेगी । कर्मचारियों को सभी संक्रामक बीमारियों से बचाने या संभावित खतरे वाली संक्रामक बीमारियों के लिये टीके लगाये जायेंगे ।

- 9. उपकरण तथा लिनन आदि :- नर्सिंग होम में -
- 9.1 पर्याप्त संख्या में कोमोड, बैडपैन तथा फलसिंग व्यवस्था वाले स्लोप सिंक होंगे तथा अनुरक्षित किये जायेंगे !
- 9.2 हाईप्रेशर स्टेरलाइजर और औजार स्टेरलाइजर होंगे ।
- 9.3 रोगियों को सुरक्षित तथा स्वच्छ आक्सीजन देने के लिये सभी प्रकार के आवश्यक उपकरणों तथा फ्लोमीटरों से लैस प्राप्त संख्या में आक्सीजन सिलेंडरों से अबाध आक्सीजन की आपूर्ति की व्यवस्था होगी ।
- 9.4 ट्रांस्पयूजन के उपकरण, आवश्यक उपकरण, औजार, यंत्र तथा दवाईयाँ उस स्तर तथा संख्या में होने चाहिये जो नर्सिंग होम द्वारा प्रदान की जाने वाली सेवाओं के अनुरूप हों ।
- 9.5 प्रसूति कक्ष तथा नवप्रसूति देखभाल कक्ष की नवप्रसूति रिसरसीटेशन युनिट में उपकरण तथा दवाईयाँ पर्यवेक्षण अधिकारी द्वारा समय—समय पर तैयार किए गये मार्ग दर्शक नियमों के अनुसार होने चाहिये ।
- 9.6 सघन देखभाल के लिये सुविधायें प्रदान करने के विषय में इसके लिये पर्यवेक्षण. निदानात्मक, रेडियोलॉजिकल, थेरेप्यूटिक/सहायक तथा बिस्तरों के समीप सुविधायें तथा समय—समय पर पर्यवेक्षण अधिकारी द्वारा तैयार किये गये मार्ग दर्शक नियमों के अनुसार होने चाहिये।
- 9.7 पर्याप्त मात्रा में चादरें, गददे तिकए, कंबल, बिछाने वाली चादरें तथा अन्य लिनन होने चाहिये ।
- 9.8 विशेष ओषधियों के लिये ताला लगी हुई अलग अलमारी होनी चाहिये ।
- 10. भोजन यदि नर्सिंग होम रोगियों को खुराक प्रदान करता है तो इसे स्वास्थ्यपरक स्थितियों में पकाया और परोसा जाये ।
- 11. नर्सिंग स्टाफ :--
- 11.1 ड्यूटी पर पूरे समय, दिल्ली निर्संग पिषद् के पंजीकृत कम से कम सामान्य निर्संग तथा मिडवाईफरी परीक्षा उत्तीर्ण, नर्स होनी चाहिये जो निर्संग होम के प्रत्येक दस बिस्तरों या उसके किसी भाग के लिये एक होनी चाहिये ।

बशर्ते कि पर्यवेक्षण अधिकारी पूर्वानुमोदन से नर्तिंग स्टाफ के एक भाग के स्थान पर अन्य प्रशिक्षित स्टाफ जैसे मिडवाईफ, फार्मासिस्ट, ड्रेसर आदि नर्सिंग होम की विशेष जरूरतों के अनुसार हो सकते हैं ।

11.2 सघन देखभाल की सुविधा प्रदान करने वाले निर्संग होम में किसी 10बिस्तरों वाले आईसीयू/सीसीयू में एक वर्ष के कार्य का अनुभव रखने वाली प्रशिक्षित स्टाफ नर्स होनी चाहिये । किसी विशेष समय पर 40प्रतिशत से अधिक अनुभवहीन स्टाफ नर्स नहीं होने



- नवजात की देखभाल या नवप्रसूति देखभाल युनिट सेवा प्रदान करने वाले नर्सिंग होम में भी 1:1 नर्स रोगी का अनुपात रहेगा ।
- 12 रिकार्ड :- निम्नलिखित के लिये नर्सिंग होन द्वारा अलग स्टॉक रजिस्टर रखे जायेंगे;
- (ब) ओजार और
- (स) लिनन

## 13 डाक्टर :--

- निसंग होम में दिल्ली चिकित्सा परिषद् द्वारा पंजीकृत आधुनिक वैज्ञानिक चिकित्सा पद्धति का एक योग्य डाक्टर चौबीस घंटे प्रत्येक 20बिस्तर या उसके किसी भाग की संख्या के लिये उपलब्ध रहेगा तथा संबंधित विशेषज्ञता की सेवा बुलाने पर उपलब्ध होनी चाहिये
- सघन देखभाल सेवा प्रदान करने वाले नर्सिंग होम में संबंधित विशेषज्ञता आईसीयू में स्नातकोत्तर डाक्टर (एमडी) होनी चाहिये । सुपर स्पेशलिटी की सुविधा प्रदान करने वाले नर्सिंग होम के मामले में संबंधित विशेषज्ञता का परामर्श बुलाने पर उपलब्ध रहेगा । संबंधित परामर्शदाता अपेक्षित स्नातकोत्तर योग्यता वाला होगा ।

बशर्तें कि किसी रनातकोत्तर डाक्टर के उपलब्ध न होने की स्थिति में, रनातक उपाधि के पश्चात् किसी परामर्शदाता के पर्यवेक्षक में 10 बिस्तर वाले सामान्य आईसीयू/सीसीयू में एक वर्ष के कार्य अनुभव वाले डाक्टर पर भी आईसीयू/सीसीयू में रेजिडेंट डाक्टर के रूप में कार्य पर भी विचार किया जा सकता है । डाक्टरों बिस्तर का अनुपात चौबीस घंटे 1:4 का रहेगा तथा परामर्शदाता बुलाने पर आयेंगे ।

## 14 प्राकृतिक आपदा या विनाश के समय सहयोग :--

- किसी प्राकृतिक आपदा या विनाश की स्थिति में प्रत्येक नर्सिंग होम के स्वामी या संचालक को पर्यवक्षक अधिकारी द्वारा लिखित अनुरोध किये जाने पर सहयोग देना होगा तथा प्राकृतिक आपदा या विनाश के उत्तय पर्यवेक्षक अधिकारी द्वारा आवश्यक समझी जाने वाली उपयुक्त सहायता तथा चिकित्सा सहायता उपलब्ध करानी होगी।
- नर्सिंग् होम किसी भी कारण से इलाज के लिये लाए गए घायल / गंभीर व्यक्ति को इंकार नहीं करेगा ।
- 15 प्रभारों का प्रदर्शन :- नर्सिंग होम का संचालक सुनिश्चित करेगा कि नर्सिंग होनं द्वारा नर्सिंग होम में उपलब्ध सभी सेवाओं के लिये जाने वाले प्रभार स्थायी रूप से प्रदर्शित किये जाते रहें।

16 अतिरिक्त जेनरेटर की व्यवस्था :- नर्सिंग होम का रखवाल नर्सिंग होम में बिजली जाने की स्थिति में अतिरिक्त जेनरेटर की व्यवस्था करेगा ।

- 17 जैव चिकित्सा कूड़े को संमालना :- नर्सिंग होम समय-समय पर यथासंशोधित जैव चिकित्सा कूड़ा (प्रबंधन एवं संमालना) नियमावली, 1998 का पालन करेगा तथा इन नियमों के अन्तर्गत दिल्ली प्रदूषण नियंत्रण समिति से अधिकार पत्र प्राप्त करेगा ।
- 18 निर्सिंग होम की सेवा में व्यवधान :- जहाँ किसी निर्सिंग होम में किसी भी कारण से सेवाओं में व्यवधान उत्पन्न होने की संभावना है तो रखवाल इसके विषय में कम से कम चार सप्ताह पूर्व पर्यवेक्षक अधिकारी को इसकी सूचना देगा ।

बशर्ते कि किसी आपातकालिक स्थिति में सेवाओं में व्यवधान की स्थिति में सूचना पर्यवेक्षक अधिकारी को इस प्रकार के व्यवधान के चौबीस घंटे के भीतर देनी होगी ।

राष्ट्रीय राजधानी क्षेत्र दिल्ली के उपराज्यपाल के आदेश से तथा उनके नाम सर

(विवेक रे)

प्रधान सचिव (स्वा. एवं परि. कल्याण)

नर्सिंग होम में इनटैनसिव कंयर यूनिट (सघन चिकित्सा कक्ष) मे अनिवार्य उपकरणों /औषधियों की आवश्यकताओं के लिये दिशा निर्देश

गंभीर देखभाल यूनिट या गहन चिकित्सा यूनिट ऐसे रोगियों के यूनिट हैं जो अत्यधिक बीमार, अस्थिर स्थिति वाले या अत्यधिक अस्थिर स्थिति वाले रोगियों के लिये है जिनके लिये निरन्तर उपकरण संचालन तथा पूर्णकालिक नर्सों और विशेष प्रशिक्षित स्टॉफ की आवश्यकता है। गंभीर देखभाल यूनिटों में विस्तृत रूप से ह्दय रोग संबंधी यूनिट तथा गहन चिकित्सा यूनिट सम्मिलित होंगे। अत्यधिक सामान्य गहन चिकित्सा यूनिटों में मेडिकल केयर यूनिट (एम आई सी यू), सर्जिकल इनटैनसिव केयर यूनिट (एस आई सी यू) बाल चिकित्सा यूनिट देखभाल यूनिट (पीआईसीयू) न्यूरोलोजीकल गहन चिकित्सा यूनिट (न्यूरो आईसीयू), न्यूओनैटल गहन देखभाल यूनिट (एन आई सी यू) तथा बर्न यूनिट सम्मिलित है।

गहन चिकित्सा यूनिटों में निम्नलिखित सुविधायें होनी चाहिये :--

सामान्य आई० सी० यू०

(1) मुख्य आई० सी० यू० बैड के लिए 200 वर्ग फीट / बैड का स्थान होना चाहिए। औषधियों तथा अपकरण (वेंटिलेटर, विशेष बैड, सक्शन मशीन, वहन उपकरण, व्हीलचेयर कार्ट, मोनिटर्स आदि) के भंडारण हेतु पर्याप्त स्थान होना चाहिए। यह विस्तृत, बड़े—बड़े सैल्फ, खुला दरवाजा जिसमें टच लैस डोर ओपनर हो तथा बैटरी चार्जिंग के लिए स्थान होना चाहिए। डाक्टरों, नर्सों तथा ड्यूटी पर स्टाफ के लिए स्थान आई०सी०यू बैड स्थान से अतिरिक्त होना चाहिए।

सहायक सेवा कक्ष अर्थात् चेंजिंग रूम, ड्यूटी रूम, अटेंडेट रूम आईसीयू के नजदीक होना

चाहिए। बिजली जाने पर वैकल्पिक बिजली आपूर्ति उपकरण उपलब्ध होने चाहिए।

बैड साइड (तत्काल उपलब्ध सामान) (2-4 बिस्तर वाले पोड के लिए एक, 10 बिस्तर वाले आईसीयू के लिए 3-4) क्रेश कार्ट एल्कोव्स (इलैक्ट्रिकल आउट लैट सहित)

मेडिकेशन स्टेशन रेफ्रिजेरेटर ताले वाली केबिनेट (नार्कोटिक्स) काउंटर टाप वर्क एरिया भंडारण केबिनेट / दराजे एक्स-रे- व्यू बाक्स

(ii) आनुषंगिक क्षेत्र

- (क) सम्प्रेषण हाउस टेलिफोन इंटर कम्यूनिकेशन सिस्टम इमरजेंसी कोड अलार्म सिस्टम
- (ख) लिपिकीय स्थान (वरीयता अलग) फाइलिंग केबिनेट्स दराजे आदि
- (ग) सार्वजनिक स्थान (युनिट के साथ) टेलिफोन (हाउस तथा सार्वजनिक) प्रार्थना क्षेत्र

-4

## (ख) उपकरण (अनिवार्य)

(i) रिकार्डिंग डॉटा स्टोरिंग तथा विश्लेषण सुविधाओं सहित उपकरण संचालन ई सी जी मशीन/संचालन एस पी ओ 2 डेफीब्रिलेटर सुविधा तापमान—मल्टीपैरामीटर ईटीसीओ एन आई वी पी 2 इन्पयूजन पम्प सिरिंज डिफिकल्ट इनट्यूवेशन/एक्सट्यूबेशन कार्ट नेबुलाइजर (अल्ट्रासोनिक्स)

वैकल्पिक कार्डिअक, ऑउटपुट

(ii) डाइगनोस्टिक ए बी जी मशीन, इलैक्ट्रोलयर मशीन की सुविधा हेमाटोक्रिट, के एफ टी, ग्लुकोस मापन सुविधाएं आई सी यू/अस्पताल में चौबीस घंटो उपलब्ध होनी चाहिये ।

## (iii) रेडियोलॉजिकल

इमैजिना एक्स-रे, बेडसाइट अल्ट्रासोनोग्राफी सुविधाएं समस्त मूलभूत इमैजिंग सुविधाएं तथा समस्त इनवैस्टिगेटिव रेडियोलॉजिकल पद्धति उपलब्ध रहनी चाहिये । सी टी स्कैन तथा वेडसाइड इकोकार्डियोग्राफी सुविधा के लिये प्रबंध सुनिश्चित किया जाना चाहिये ।

(iv) थैराप्यूटिक / सपोरटिव

वैनटिलेटर्स

## (v) बैडसाइड सुविधाएं

आक्सीजन आपूर्ति के लिये केन्द्रीय पाइपलाईन प्रणाली, वैक्यूम एक्शन, बल्डप्रैशर संचालन प्रणाली, निटशैस आक्साइड, वैनटिलेशन के लिये हवा, विद्युतीय तारों के आड़े – तिरछे बिखरे रूप से बचने के लिये पर्याप्त इलैक्ट्रिकल सौकेट्स, एयर मैटरस, व्हीलचेयर, शिफ्टिंग ट्रॉली, ओवरहैड ट्रोली सहित एडजस्टेबल बिस्तर, डीटैचेब्ल बिस्तर –

विशेष आई.सी.यू

समस्त अन्य आई.सी.यू.जैसे :-न्यूरोलॉजिकल आई.सी.यू. न्यूरोलॉजिकल आई.सी.यू. न्यूओनैटल आई.सी.यू., मेडिकल आई.सी.यू., सर्जिकल आई.सी.यू. में सामान्य आई.सी.यू. के अतिरिक्त उनकी आवश्यकताओं के अनुसार उपकरण होने चाहिये ।

न्यूरोलॉजी / न्यूरोसर्जरी आई.सी.यू. में सी.टी.स्कैन सुविधा होनी चाहिये । कोरोनरी केयर यूनिट (सी सी यू) में कार्डिअग मौनीटर तथा अस्थाई पेसिंग तथा पल्ओरोसकॉपी तथा इनवेसिव आरटिऊल / वीनिऊस दाब संचालन तथा इनढाओरटिक बैलून काउंटर पलसेशन सुविधा के लिये सुविधा होनी चाहिये । कोरोनटी एंजोग्राफी की सुविधा वैकल्पिक है ।

ग अनिवार्य औषधियाँ तथा उपयोग हेतु आवश्यक वस्तु :1. औषधियाँ :- आई.सी.यू. में चौबीस घंटे अपेक्षित औषधियाँ / फ्लूड उपलब्ध रहने चाहिये तथा आई.सी.यू. में किसी भी समय किसी भी दवाई की कमी नहीं होनी चाहिये । अनिवार्य औषधियों की सूची नीचे दी गई है :-

## (i) इन्डेक्शन/सीडेशन एजेंट

थिओपैनटोन

केटामिन.

प्रोपोफोल

मिडाजोलम

डिकाउपैम.

मोरफिन

पैथीडाइन

पुन्टाजोसिने

प्रोमीथाजिन

चोरप्रोमैजिन

(ii) रिलैक्सेंट्स
सुएक्समैथोनिऊम
वैक्यूरोनिऊम
पैनक्यूरोनिऊम
रोक्यूरोनिअम
एटराक्यूरिऊम

## (iii) इनोट्रोप्स एडरिनेलिन नोराड्रेनालिन डोपामाइन डोबूटामाइन

- (iv) एन्टीबॉयोटिक्स
- (v) ब्रोनकोडिर्लेटस डैरिफिलिन एमीनोफिलिन टरब्यूटेलिन नेबूलिसेशन सोलूशन (आस्थालाइन, आईपरावेंट, बडीकोर्ट, म्यूकोलाइटिक)
  - (vi) इनप्यूशन
    एस्मोलोल
    नाईटोगिलिश्रीन
    सोडियम निट्रोप्रैसाइड
    इन्सुलिन

टी पी एन सोल्यूशन मेनीटोल

## (vii) अन्य औषधियाँ

मैरोपरोलोल

फू्समाइड

रैनिटाइडिन

मैटोक्लोपरामाइड

ओनाडामसीट्रोन

स्थानीय एनैसथैटिक्स (लिडोकेन, बुपीवैकेन)

एन्टीरयूमैटिक (एडनोसाइन, एक्लीलोकार्ड, कारडरोन, ब्रीटैलिअयम)

विटामिन के

लोमोलीक्यूलर वेटहीपैरिन

डिलीटिआजम

डिक्लोफिनैक

ट्रेमाडोल

एटरोपाइन

पी ए एम

इन्जैक्शन एविल

इन्जैक्शन डिकाङ्रोन

इन्जैक्शन हाइड्रोकोर्टिसोन

इन्जैक्शन एटीमैटिल

इन्जैक्शन इमैसैट

#### इन्जिस्थान् डाइलीमिश्चन् ग्लाइकोफीरोलेट

न्यूओस्टिगमाइन
कैल्शियम ग्लुकोनेट
सोडाबाईकार्ब
इन्जैक्शन पोटाशियम क्लोराइड
तथा सिरप पोटासियम क्लोराइड
मैगनेशियम
मल्टीविटामिन्स
लोकल एनसकैटिक जैली
आई आइनटमेंट
एन्टीसौटिक सोल्यूशन तथा आइनटमेंट
क्लीनिंग / डिसइनफैंक्टिंग सोलूशन
एन्टीरनेक वीनोम
कोलोइड्स (पोलीजैलिन, स्टार्य, डीम्ट्रॉस एलवूमिन)
मैक्सिलेटिन

# II कन्ज्यूनेबल

इन्डोट्रैकल ट्यूब (समस्त आकारों में)
ट्रैचोसटोमी ट्यूब (समस्त आकारों में)
एल एन ए (आई एल एम ए सहित) (समस्त आकारों में)
फेस भास्कः (समस्त आकार)
ओरोपैरीनजील एयरवेज (समस्त आकार)

नेसोफेरिजियल एयरवेज समस्त आकार नौन टच सक्शन उपकरण सक्शन केथेटर्स (समस्त आकार) गर्नी और नमी एक्सचेंजर (इटीटी, ट्रोचैक्टोमी ट्यूब के साथ प्रयोगार्थ) इनसैनटिव स्पाईरोमीर्टस आई/वी कैन्यूलै थ्री वेज़ सी पी पी लाइन (समस्त आकार) इनट्रा आरटीरियल कैनूलेक फोलीस कैथटर्स नैसोगैस्ट्रिक ट्यूट सी पी ए पी मास्क वैन्ट्यूटी मास्क बिनैसल कैनूलैक नैसल संपैक्टेकल परक्यूटैनिकस डिलेशन ट्रकैओस्टोमी केट स्टराइल ड्रेसिंग डिस्पोजेबल ग्लोब, मास्क, सीरिंज तथा नीडल, शू कवर अस्थाई पैसिंग लीड्स ६ एफ / ७एफ अस्थाई पत्स जनरेटर चैक फ्लो (5-7एफ) तथा स्वान गंज कैथेटर आरटीरियल पंक्यर नीडल स्टराइल ड्रेप शीट्स

(घ) अपेक्षित कर्मचारी

(1) SHER

संबंधित विशेषज्ञता आईसीयू में स्नातकोत्तर डाक्टर (एमडी) तथा सुपर स्पेसिलिटी के मामले में संबंधित विशेषज्ञता का परामर्शदाता उपलब्ध होना चाहिए संबंधित परामर्शदाता को अपेक्षित स्नातकोत्तर योग्यता संपन्न होना चाहिए। स्नातकोत्तर डाक्टर के उपलब्ध न होने पर किसी 10 बिस्तर वाले सामान्य आइसीयू/सीसीयू में किसी परामर्शदाता के पर्यवेक्षण में एक वर्ष तक कार्य का अनुभव रखने वाले किसी रनातक डाक्टर को रेजिडेंज डाक्टर रखा जा सकता है डाक्टर का दिल्ली चिकित्सा परिषद में पंजीकरण हो तथा डाक्टरों का अनुपात 24 घंटे बिस्तरों का 1:4 का होना चाहिए तथा विशेषज्ञ बुलाए जाने पर उपलब्ध हो।


#### (ii) नर्सिंग कर्मचारी

ऐसी स्टाफ नर्स हों जिनकी न्यूनतम योग्यता सामान्य नर्सिंग तथा मिडवाइफरी कोर्स होना चाहिए। दिल्ली नर्सिंग परिषद के पास पंजीकृत तथा 10 बिस्तर वाले आईसीयू/सीसीयू में एक वर्ष कार्य का अनुभव हो। किसी एक समय 40प्रतिशत से अधिक ऐसी अनुभवहीन स्टाफ नर्से नहीं होनी चाहिए जिन्हें एक वर्ष आईसीयू में कार्य का अनुभव न हो। अतः सुनिश्चित होना चाहिए कि एक पारी में न्यूनतम 60प्रतिशत अनुभवशील स्टाफ नर्से उपलब्ध होनी चाहिए। स्टाफ नर्स 24 घंटे 1:1 के अनुपात में होगी तथा प्रत्येक 10 नर्सों पर शिक्षित पर्यवेक्षक चौबीस घंटे आई०सी०यू० में उपलब्ध होना चाहिए।

#### (iii) अर्ध-चिकित्सा स्टाफ

आई०सी०यू० में तैनात अर्ध—चिकित्सा स्टाफ को आई०सी०यू० में कार्य का पिछला अनुभव होना चाहिए।

(ङ) सामान्य सेवाएं
अग्नि सुरक्षा उपाय
वातानुकूलन / हीटिंग



भूमिगत विद्युत प्वाइंट आपातकालीन पॉवर स्रोत सर्किट ब्रेकर उपकरण उचित प्रकाश व्यवस्था

मरीजों को अन्य अस्पताल ले जाने या बड़े—बड़े केन्द्रों में लाने—ले जाने की सुविधा आई. सी.यू. / सी.सी.यू. सहित होनी चाहिये ।

ये सिफारिशें आई.सी.यू. /सी.सी.यू. के लिये दिशा निदेश बनाई गई है तथा संपूर्ण नहीं है तथा इनमें समय-समय पर संशोधन की आवश्यकता हो सकता है ।

नर्सिंग होम में नवजात शिशु (न्यूबोर्न) देखणाल यूनिट नवप्रसूति (नियोनेटल) देखमाल यूनिट तथा नियोनेटल पुनर्जीवन यूनिट में अनिवार्य उपकणों और औषधियों की मूलभूत आवश्यकता

# नवजात शिशु (न्यूबोर्न) देखभाल यूनिट

- वे नर्सिंग होम जो नवजात शिशु देखभाल की सुविधा उपलब्ध कराते हैं उनमें निम्नलिखित अनिवार्य उपकरण और सुविधायें होनी चाहिये :-
- प्रत्येक नवप्रसूति बिस्तर के लिये नियोनेप्ल चेस्टपीस सहित एक स्टैथोस्कोप
- आक्सीजन हूड बॉक्स तथा अन्य आक्सीजन वितरण उपकरण जैसे हम्यूडिकायर तथा बच्चे का वजन मापक मशीन
- रेगुलेटर
- आक्सीजन तथा कम्प्रैस्ड एयर की निरन्तर उपलब्धता फोटोथेरेपी यूनिट
- आक्सीजन एनॉलाइजर (आक्सीमीटर)
- नॉन्इन्वेसिव बल्ड प्रेशर मानीटर
- हार्ट रेट तथा / या अपनीया मानीटर
- नवजात शिशु बचाव किट
- ट्रांसपोट इंक्यूबेटर
- सक्सन मशीन
- एयर थर्मामीटर
- (থ) रेडीएन्ट हीट सोर्स

ऐसी नर्सिंग होम में चौबीसों घंटे बायोकैमीकल तथा हीमेटोलोजिकल जाँच के लिये अपेक्षित स्विधायं होगी जो बीमार शिशु के उपचार प्रबंधन के लिये आवश्यक हो सकती हैं । संक्रमण नियंत्रण की सुविधा होनी चाहिये जैसे अबाधित जलापूर्ति तथा संक्रमित शिशुओं को अलग रखने की व्यवस्था । गन्दे और मैले लीलन या अन्य सीमित अवशिष्ट के निपटान की सुरक्षित और पर्याप्त पद्धति ।

# लेबर रूम में नवप्रसूति पुनजीवत (नियोनोल)

- एक चालू दीवार घड़ी जिसमें सैकेंड की सुई हो या स्टाप क्लॉक ।
- दाब नियंत्रण यूपण मशीन तथा म्यूकस एक्सट्रैक्र की पर्याप्त संख्या । (ख)
- $(\Pi)$
- सैल्फ इनफ्लैटिंग बैग सहित आई पी पी आर के लिये अपेक्षित सुविधाएं, भलीभांति फिट नवप्रसूति आधार के ब्लेज सहित दो कार्यरत स्वर यंत्रदर्शी किये गये नियोजनटल फेस मास्क, एन्डोट्रेक्ल ट्यूब तथा समुचित एडॉटरस् (ঘ)
- अनबिलिंकल वेन केन्यूलेशनस् सेट
- शिशु भार मापक मशीन
- प्रसव के दौरान आवश्यक दवाईयों की उपलब्धता ।

नर्सिंग होन में रोगियों के अभिलेखों के रखरखाव के लिये दिशा-निर्देश

नर्सिंग होम को निम्नलिखित प्रपन्नों के दिए गए प्रारूप के अनुसार अभिलेखों का रखरखाव करना होगा ।

फार्म प्रपत्र "डी" भर्ती रोगियों का रिजस्टर । फार्म प्रपत्र "ई" नर्सिंग होम में भर्ती प्रत्येक प्रसूति मामलों का अभिलेख । फार्म प्रपत्र "एफ 1—2" गर्भपातों का अभिलेख एम० टी० पी० मामले, तथा नर्सिंग होम में होने वाले मृत प्रसव का अभिलेख फार्म "जी" नर्सिंग होम में हुई मृत्यु का रिकार्ड ।

# फार्म घ (संशोधित) (नियम 12 देखें)

नर्सिंग होम/अस्पताल के रोगियों का रजिस्टर

	4	•				•			
भर्ती संख्या	नाम पुत्र/पुत्री/पत्नी तथा पता	आयु / लिंग	भर्ती की तिथि तथा . समय	भर्ती का रोंग निदान	अंतिम रोग निदान	केस की प्रभारी डाक्टर	छुद्टी/मृत्यु/ लामा की तिथि तथा समय	एमएलसी या नहीं (हाँ / नहीं)	परिणाम या / तथा टिप्पणी
1	2	3	4	5	6	7	8	9	10
									,

4

) (j)

फार्म डिस्वार्ज (छुट्टी) की तारीख व समय नार्सिंग होम में फिडिंग की डिलीवरी करवाने वाले चिकत्सा कार्मिक का नाम च पता केस की प्रभारी डॉक्टर बच्चे का नाम वजन डिलीवरी का तरीका वया बच्चा जीवितः अथवा मृत हुआ डिलीवरी की तारीख तथा समय पिता का नाम एवं पता माता का नाम, आयु एवं दाखिला क्र0 सं0 सलाह एवं लिंग 12 11 10 6

Ť ————	(आर0 एम0 पी0 का नाम एवं योग्यता स्पष्ट अक्षरों में) (आर0 एम0 पी0 का पूरा नाम)
•	(आर0 एम0 पी0 का नाम एवं योग्यता स्पष्ट अक्षरा म) (आर0 एम0 पी0 का पूरा नाम)
(गर्भवती महिला का पूरा नाम र जिसका निम्नलिखित व	ाता है* मेरा / हमारा सद्भाव पूर्वक विचार है कि ————— खंपता स्पष्ट अक्षरों में) का गर्भपात कराना आवश्यक है।
आर०एम०पी० के हस्ताक्षर	
स्थान : दिनांकः	
* जो लागू न हो उसे काट रि * मद संख्या (1) से (5) तक (i) गर्भवती महिला का ज	देया जाए विनिर्दिष्ट कारण में से जो सही हो उसे लिखे :- नीवन बचाने के उद्देश्य से।

गर्भवती महिला क़े शारीरिक एवं मानसिक स्वास्थ्य को क्षति पहुँचने से बचाने के उद्देश्य से। (ii) ·

महत्वपूर्ण जोखिम को ध्यान में रखते हुए जैसे यदि बच्चा पैदा होता तो वह ऐसी शारीरिक अथवा मानसिकता असामान्यता के रूप में होता है जो कि गंभीर रूप से विकलांग हो सकता था। ,

गर्भवती महिला का गर्भधारण बलात्कार के कारण हुआ है।

गर्भावस्था बच्चों की संख्या को सीमित रखने के उद्देश्य से विवाहित महिला अथवा उसके पति द्वारा प्रयोग किए गर्भनिरोधक उपायों अथवा साधनों की असफलता के परिणामस्वरूप हुआ हो।

नोट : गर्भवती महिला के वास्तविक स्थिति तथा ऐसे वातावरण को निर्धारित करने का ध्यान रखा जाए कि गर्भपात करने के लिए उसके शारीरिक अथवा मानसिक स्वास्थ्य को क्षति पहुँचाने से बचाया जा सकेगा।

आर०एम०पी० के हस्ताक्षर

स्थान : दिनांक:

# फार्म—II (विनियम 4 (5) देखें)

माह	की 🚅 जिला, दिल्ली की गर्भपात अधिनियम सूचना
1.(i) (ii)	अनुमोदित संस्थानों की संख्या ————— सूचना देने वाले संस्थानों की संख्या ————— महीने का नाम —————
2.	कुल एन०टी०पी० मामले
	कुल मामलों का विभाजन
4. (i)	गर्भधारण की अवधि (केवल कुल संख्या दें)

# (ii) आयु समूह

12 सप्ताह तक 12—20 सप्ताह तक

а	15 से कम
Ъ	15-19
С	20-24
d	2529
е	30-34
f	35-39
g	4044
h	45 से अधिक
i	उपलब्ध नहीं

# (iii) महिला का धर्म

а	हिन्दु	
b	मुस्लिम	
С	ईसाई	
d	अन्य	
е	कुल	

गुफ-1

फार्म-III (विनियम 5 देखें) प्रवेश रजिस्टर

	40 30	दाखिले   की तारीख	रोगी का नाम	की पत्नी / पुत्री	आयु	धर्म	पता	गर्भावस्था की अवधि	गर्भपात करने के कारण	गर्भपात की तारीख	रोगी को डिस्चार्ज करने की तारीख	परिणान तथा अभ्युक्ति	पंजीकृत चिकित्सा प्रैक्टिसनर का नाम जिसके द्वारा विचार किया गया	पंजीकृत चिकित्सा प्रैक्टिफर्नर का नाम जिसके द्वारा गर्भपात किया	
.· <b>·</b>		1			1		ļ		<u> </u>	<u> </u>	11	12	13	14	7
		<u> </u>	1_	4	- 5	6	7	. 8	9	10		<del></del>			
		2	3	4										·	

h

 $\int_{\mathbb{R}^d} \int_{\mathbb{R}^{d+1}}$ 

# फार्म क (नियम 4 (1) तथा 8 (1) देखें) (समर्थित दस्तावेजों सहित अनुलिपि में जमा कराए)

जैनेटिक परामर्श केन्द्र/जैनेटिक प्रयोगशाला/जैनेटिक क्लिनिक/अल्ट्रासाउंड क्लिनिक/इमेजिंग केन्द्र के पंजीकरण अथवा पंजीकरण के नवीकरण के लिए आवेदन

- विश्वास्त्र के लिए आ	वदन
1. आवदेक का नाम	
उस संगठन का नाम जिसका गंजीकर है	
3. पंजीकृत किए जाने का के न	
प्रयोगशाला / जैनेटिक क्लिनिक / अल्ट्रासाउंड क्लिनिक / इमेजि केन्द्र अथवा इनमें से किसी के स्वीपना ने किसी	क
केन्द्र अथवा इनमें से किसी के सम्मिलन के पंजीकरण है	नंग ∤
आवेदन किया जाना है)	हेतु
4. जनिर्देक प्राथमर्च 🛶 🐧	
किलनिक / अल्ट्रासाउंड किलनिक / इमेजिंग केन्द्र का दूरभा संख्या / फैक्स संख्या / टेलीगफिक / केने पर्वा	क
संख्या / फैक्स संख्या / टेलीग्राफिक / टैलेक्स / ई-मेल पते सहि	ष   -
उनका पूरा नाम एवं पता	त
5. संगठन के स्वामित्व का प्रकार (व्यक्तिगत स्वामित्व/साझेदार /कंपनी/सहकारी/अन्य कोर्ड विभिन्न	
/कंपनी/सहकारी/अन्य कोई, विनिर्दिष्ट किया जाए, या	$\eta$
संगठन की किस्म व्यक्तिगत स्वामित्व के अतिरिक्त है तो उर	<u>द</u>
रिथित में संस्था मदों की प्रति तथा संलग्न व्यक्तियों जो वि	H
प्रबंधन हेतु उत्तरदायी है, ऐसे व्यक्तियों का नाम एवं पता प्रस्तुत	2
6 Tiron -2 O	. (,
6. संस्था की किस्म (सरकारी अस्पताल/नगर अस्पताल/ सार्वजनिक अस्पताल/निजी अस्पताल/	
सार्वजनिक अस्पताल/निजी अस्पताल/निजी नर्सिंग होम/प्राईवेट क्लिनिक (पार्टी)	
होम / प्राईवेट क्लिनिक / प्राईवेट प्रयोगशाला / अन्य कोई) 7. विशेष पर्व प्रस्त विदान गर्नी (अन्य कोई)	
7. विशेष पूर्व प्रसव निदान पद्धति/जांच जिसके लिए अनुमोदन प्राप्त किया जाना है	
(क) दस्तेमच्या (१)	
(क) इनवेसहव (i) एमनीओ सेटेसिस/जरायु अकुर एसपाइरेशन	
/ कैरोमोशोमल / जीव रसायन / मोलीक्यूलर अध्ययन (ख) नॉन इन्तेयन्य : अस्मायन / अस्मायन	
इसे खाली छोड दे यदि पंजीकरण केवल जैनेटिक परामर्श केन्द्र	
8. प्रत्येक उपकरण के मेक एवं मॉडल सहित उपलब्ध उपकरण (अलग पेपर पर सुची)	
(अलग पेपर पर सूची)	
9. (क) परामर्श केन्द्र भे जा क	
(ख) क्या निम्नलिखित जाँचों के लिए प्रयोगशाला/क्लिनिक में	
सुविधाएं उपलब्ध है या होगी :-	
(i) अल्ट्रासाउंड	
(ii) एमनीओ सेरेसिस	
(iii) जरायु अंकुर एसपाइरेशन	
रच्या चार्यं अन्युर एसपाइरशन	

ĺ
1
١
ł
ļ
_

ļ

में शपथ लेता हूँ कि उक्त अधिनियम तथा नियमावली के विषय में जैनेटिक काउंसलिंग केन्द्र / जैनेटिक प्रयोगशाला / जैनेटिक क्लिनिक / अल्ट्रासाउंड क्लिनिक / इमेजिंग केन्द्र के सभी कर्मचारियों को बता दूंगा जिनके अंतर्गत पंजीकरण करवाया गया है तथा सुनिश्चित करता हूँ कि अधिनियम तथा नियमावली का पूर्णतया पालन किया जायेगा।

तिथि : स्थानः

> व्यक्ति का नाम, पदनाम तथा हस्ताक्षर जिसे संस्थान की तरफ से पंजीकृत किया गया है जिसका पंजीकरण किया जाना है

पजाकरण किया जाना ह पावती (नियम 4 (2) तथा 8(1) देखें) काउंसलिंग केन्द्र / जैनेटिक प्रयोगाला / जैनेटिक क्लिनिक / अल्ट्रासाउंड

\*फार्म 'क' में आवेदन के साथ अनुलग्नकों की सूची को प्रस्तुत किए गए अनुलग्नकों से जाँच करके सही पाया गया है।

या

\*जाँच करने पर पाया गया कि सूची में उल्लिखित निम्नलिखित दस्तावेज संलग्न नहीं है। इस पावती से आवेदक को पंजीकरण प्रदान करने/नवीकरण का कोई अधिकारी प्राप्त नहीं होता।

> समुचित अधिकारी के कार्यालय में समुचित अधिकारी या अधिकृत व्यक्ति के हस्ताक्षर तथा पदनाम

तिथि : स्थानः

मुहर

h.



1.

#### प्रदर्शन हेतु मूल / डुप्लीकेट फार्म ख (नियम 6 (2), 6 (5) तथा 8 (2) देखें) पंजीकरण प्रमाण पत्र (दो प्रतियों में जारी किया जाए)

- 2. यह पंजीकरण उपरोक्त अधिनियम तथा उसके अधीन नियमों के अनुसार किया जाता है तथा इसका किसी भी प्रकार से उल्लंघन करने पर अभियोजन के अतिरिक्त पाँच वर्ष की अवधि समाप्त होने से पूर्व पंजीकरण प्रमाण-पत्र को निलंबित किया जाएगा या रद्द किया जाएगा।
  - क फार्म ग का (1) लें ख. पूर्व प्रसव निदान पद्दति (जैनेटिक क्लिनिक) के लिए अनुमोदित नॉन इनवेसइव
    - (i) अल्ट्रासाउँड इनवेसइव
    - (ii) एमनीयोसेंटसिस
    - (iii) जरायु अंकुर बायोप्सी
    - (iv) फोइटो स्कॉपी
    - (v) भ्रूण त्वचा या अंग बायोप्सी
    - (vi) कॉरडोसेटेसिस
    - (vii) अन्य कोई (उल्लेख करें)
  - ग. जैनेटिक प्रयोगशाला के लिए अनुमोदित प्रसव पूर्व निदान जाँच
    - (i) गुणसूत्र अध्ययन
    - (ii) जीव रसायन अध्ययन
    - (iii) आणविक अध्ययन
  - घ. अन्य कोई उद्देश्य (कृपया उल्लेख करें)
  - 3. प्रयोग किए गए उपकरणों मॉडल तथा मेक (किसी भी प्रकार के परिवर्तन से नियम 13 के अधीन समुचित प्राधिकारी को सूचित किया जाए)
  - 4. आबंटित पंजीकरण संख्या

## फार्म ग (नियम 6 (3), 6(5) तथा 8(3) देंखे) पंजीकरण करने / नवीकरण के लिये आवेदन पत्र को रद्द करने के लिये फार्म

पूर्व प्रसव निदान तकनीक (विनियम तथा दुरूपयोग रोकथाम) अधिनियम, 1994 की धारा 19(2) के अधीन प्रदत्त शक्तियों का प्रयोग करते हुये समुचित प्राधिकारी एतद् द्वारा निम्नलिखित जैनेटिक परामर्श केन्द्र/\* जैनेटिक प्रयोगशाला/जैनेटिक क्लीनिक/अल्ट्रासांउड क्लीनिक/इमेजिंग केन्द्र के पंजीकरण/नवीकरण के आवेदन को रद्द करता हूँ ।


(1) जैनेटिक परामर्श केन्द्र/जैनेटिक प्रयोगशाला/जैनेटिक क्लीनिक/अल्ट्रासाउंड क्लीनिक/इमेजिंग केन्द्र का नाम एवं पता

(2) पंजीकरण करने / नवीकरण के लिये आवेदन

दिनांक : स्थान :

समुचित प्राधिकारी के हस्ताक्षर नाम तथा पदनाम कार्यालय मुहर सहित

\* जो लागू न हो, काट दिया जाए ।



	जनाटक परामरा कर्प्य क्षारा रहार		<del></del> 7
	ि — च्या परं पत्		
1.	जैनेटिक परामर्श केन्द्र का नाम एवं पता		
2.	पंजीकरण संख्या		
3.	रोगी का नाम		
4.	आयु		
5.	पति/पिता का नाम		
6.	पूरा पता, दूरभाष सहित, यदि कोई हो		
7.	द्वारा भेजा गया (डाक्टर/जनाटक परागरा राज्य		
	नाम व पता)		
\	नाम व पता) (रैफरल नोट को केस पेपरों के साथ सुरक्षित रखा जाए)		
	A was Albertal		
8.	अंतिम महावारी तारीख/गर्भावस्था के सप्ताह		
9.	अतिम महावारा ताराख/ गंनापरपा में का पूर्ववृत्त (उल्लेख परिवार में जैनेटिक/मेडिकल रोगों का पूर्ववृत्त (उल्लेख		
}	करें)	, -	Ì
Ì	निदान का आधार	•	
1	(क) क्लिनिकल		
	(ख) जीव रसायन		
	1: 1: 1: 1: 1: 1: 1: 1: 1: 1: 1: 1: 1: 1		
}	(ग) साइटाजानाटक (घ) अन्य (रेडियोलॉजिकल, अल्ट्रासोनोग्राफी इत्यादि का	·	
1			
1	0. पूर्व प्रसंव निदान के लिए विशेष अनुदेश	·	
	क पहले हए बच्चा / बच्च		}
}	(i) गणसत्र संबंधी खराबा		
Ì	(ii) चयापचयी खराबी	-	
	(iii) विकृति		
\	(iv) मानसिक खराबी		
1	(17) मानासक खरावा		
İ	(v) वंशानुगत एनीमिया		
}	(vi) लिंग खराबी		}
	(vii) सिंगल जैनी खराबी		
	ं र १११ नोर्च (जल्लेख करें)		
	(VIII) अन्य कोई (उरलेख पर) ख. एडवांस मातृत्व आयु (35 वर्ष या अधिक)		
	ख. एडवांस मातृत्व आयु (३५ वर्ष या जावप) ग. माता / पिता / सहोदर जिन्हे जैनेटिक रोग हो (उल्लेख		
	करें)		
	घ. अन्य (उल्लेख करें)		
•	11. प्रक्रिया सलाह		
	(i) अल्ट्रासाउंड		
	(ii) एमनीओसेंटेसिस	rins	
	(11) तिस्तावादाराज	·	
	(iii) जरायु अकुर बायोस्पी		
	(iv) फोटोस्कॉपी		
		•	1

	· · · · · · · · · · · · · · · · · · ·	
	(v) भ्रूण त्वचा या अंग बायोप्सी	
	(vi) गुणसूत्र	
	(vii) अन्य कोई (उल्लेख करे)	
12.	किए गए प्रयोगशाला जाँच	
1	(i) गुणसूत्रीय अध्ययन	
	(ii) जीव रसायन अध्ययन	
	(iii) आणविक	
	(iv) प्रीम प्लांटेशन जैनेटिक निदान	
13.	निदान का परिणाम	
	यदि असामान्य हैं तो विवरण दें सामान्य/असामान्य	
14.	एमटीपी सलाहकार	
15.		
	[ 141 ]	,
16.	जैनेटिक परामर्श का प्रारंभ तथा अंत का विवरण	

## फार्म ड़ (ई) (नियम ९ (३) देंखे)

	(14.15 (6) 14.15
	जैनेटिक प्रयोगशाला द्वारा अभिलेखों के रखरखाव के लिये फार्म
1.	जैनेट्क प्रयोगशाला का नाम एवं पता
2.	पंजीकरण संख्या
3 <i>.</i> 4.	रोगी का नाम
4. 5.	आय
5. 6.	पति / पिता का नाम
7.	पूरा पता, दूरभाष सहित, यदि कोई हो
۰. 8.	द्वारा भेजा गया / द्वारा नमूना भेजा गया (जैनेटिक क्लिनिक का पूरा नाम एवं पता)
٥.	क्षानुबन को केस प्रेपरों के साथ सावधानीपर्वक सरक्षित रखा जाय)
9.	नमूने का प्रकार : मातृ रक्त / जरायु अंकुर नमूना / एमनीओटिक फ्लूड /भ्रूण का रक्त
	या अन्य भ्रूण टिशु (उल्लेख करें)
(क)	पहले हुये बच्चा / बच्चे
(i)	
(3)	i) चयापचयी खराबी
	v) वंशानुगत एनीमिया
. (1	vi) लिंग खराबी
	vii) सिंगल जैनी खराबी
7)	viii) अन्य कोई (उल्लेख करें)
(ख)	एडवांस मातृत्व आयु (३५वर्ष या अधिक)
(ग)	माता/पिता/सहोदर जिन्हें जननिक रोग हो (उल्लंख कर)
(ঘ)	अन्य (उल्लेख करें)
10.	किए गये प्रयोगशाला जाँच (विवरण दें)
(	i) गूणसूत्र अध्ययन
(	ii) जीव रसायन अध्ययन
(	iii) आणविक अध्ययन
. (	iv) प्रिइम प्लाटेशन जैनेटिक निदान
11.	निदान का परिणाम
	यदि असामान्य हो तो विवरण दें सामान्य/असामान्य
12.	तद तारीख जिसमें जांच की गर्ड
	पूर्व प्रसव निदान जांचों का परिणामको दिनांकको भेजा
	भागा ।
	नाम हस्ताक्षर एवं चिकित्सा जैनेटिक पंजीकरण
	सं. / संस्था के निदेशव
स्था	न :
दिन	f
	· · · · · · · · · · · · · · · · · · ·

### फार्म ड़ (ई) (नियम ९ (3) देंखे)

जैनेटिक प्रयोगशाला द्वारा अभिलेखों के रखरखाव के लिये फार्म 1. जैनेटिक प्रयोगशाला का नाम एवं पता पंजीकरण संख्या 3. रोगी का नाम 5. आयु पति / पिता का नाम पूरा पता, दूरभाष सहित, यदि कोई हो द्वारा भेजा गया / द्वारा नमूना भेजा गया (जैनेटिक क्लिनिक का पूरा नाम एवं पता) (रैफरल नोट को केस पेपरों के साथ सावधानीपूर्वक सुरक्षित रखा जाये) नमूने का प्रकार : मातृ रक्त / जरायु अंकुर नमूना / एमनीओटिक फ्लूंड / भ्रूण का रक्त या अन्य भ्रूण टिशु (उल्लेख करें) पहले हुये बच्चा / बच्चे (क) गुणसूत्र खराबी (i)चयापचयी खराबी (ii)विकृति (iii) (iv) मानसिक खराबी वंशानुगत एनीमिया (v)लिंग खराबी (vi) (vii) सिंगल जैनी खराबी अन्य कोई (उल्लेख करें) एडवांस मातृत्व आयु (35वर्ष या अधिक) (ख) माता / पिता / सहोदर जिन्हें जननिक रोग हो (उल्लेख करें) अन्य (उल्लेख करें) (ঘ) किए गये प्रयोगशाला जाँच (विवरण दें) गूणसूत्र अध्ययन (i) जीव रसायन अध्ययन (ii) आणविक अध्ययन (iii) प्रिइम प्लांटेशन जैनेटिक निदान निदान का परिणाम 11. यदि असामान्य हो तो विवरण दें सामान्य/असामान्य वह तारीख जिसमें जांच की गई पूर्व प्रसव निदान जांचों का परिणाम......को दिनांक .......को भेजा गया । नाम, हस्ताक्षर एवं चिकित्सा जैनेटिक पंजीकरण सं. / संस्था के निदेशक स्थान : दिनाक :

(vi) अन्य कोई उल्लेख करें 12. प्रक्रिया की कोई जटिलता (कृपया उल्लेख करें)

प्रसव पूर्व निदान प्रक्रि (विवरण दें)	य
(सामान्य / असामान्य)	
राटि कोर्ट है स्पाप्त करें।	

(ख) अल्ट्रासोनोग्राफी (सामान्य / असामान्य) (पता लगाई गई असामान्यता, यदि कोई है, स्पष्ट करें)

15. वे तिथियाँ जब प्रक्रिया पूरी की गई।

16. सहमति प्राप्त करने की तिथि (आक्रामक के मामले में)

17. प्रसव—पूर्व निदान प्रक्रिया के परिणाम ...... को ......(तिथि) को बताए गए ।

18. क्या एमटीपी की सलाह दी गई/की गई?

19. एमटीपी करने की तारीख ।

दिनांकः स्थान :

स्त्री रोग विज्ञानी/रेडियोलॉजिस्ट/ क्लीनिक के निदेशक का नाम, हस्ताक्षर तथा पंजीकरण संख्या

गर्भवती की घोषणा

मैं सुश्री.......(गर्भवती का नाम) घोषणा करती हूँ कि अल्ट्रासोनीग्राफी / इमेज स्केनिंग आदि करवाकर मैं भ्रूण का लिंग नहीं जानना चाहती हूँ ।

गर्भवती के हस्ताक्षर/अंगूठा निशान

> अल्ट्रासोनोग्राफी करने वाले व्यक्ति जनेटिक क्लीनिक/ अल्ट्रासाउंड क्लीनिक/इमेजिंग क्लीनिक के निदेशक/ स्वामी का नाम तथा हस्ताक्षर

#### महत्वपूर्ण नोट :

- (i) अल्ट्रासाउंड भ्रूण का लिंग पता लगाने के लिये नहीं किया गया/सलाह दी गई है यह डकेन मस्कुलर डिस्ट्राफी, हिमोफीलिया ए एवं बी आदि लिंग—सापेक्ष रोगों के निदान के लिये किया गया है ।
- (ii) गर्भावस्था में अल्ट्रासोनोग्राफी जब बताई गई हो तभी की जानी चाहिये । गर्भावस्था के दौरान अल्ट्रासाउंड के लिये निम्नलिखित संकेतक सूची है ।

1. इंट्रा-यूट्राइन एवं / या एक्टोपिक गर्भाधान एवं स्वस्थ होने की पुष्टि

2. गेस्टेशनल आयु का पूर्वाकलन (तिथि)

3. भ्रूणों की संख्या एवं उनकी कोरियोनिसिटी का पता लगाना

4. आइ यू सी डी होने पर गर्भावस्था या गर्भनिरोधक असफल / एम टीपी असफल होने पर संभावित गर्भावस्था

5. योनि रक्त स्नाव/स्नाव

6. गर्भपात मामलों की अनुवर्ती परीक्षा

7. आन्तरिक ओ एस की सर्वाइकल कनाल तथा व्यास का निर्धारण करने के लिये

8. योनि आकार एवं अनार्तव की अवधि के बीच विसंगति

9. कोई संभावित एडिने क्सल या यूटीराइन पेथोलोजी/असामान्यता

10. क्रामोसोम संबंधी असामान्यता का पता लगाना, गर्भ का स्वरूप संबंधी दोष तथा अन्य असामान्यताएँ एवं अनुवर्ती

11. भूण उपस्थिति एवं स्थिति का निर्धारण

12. लिंकर एमनी का निर्धारण

13. अवधि पूर्व प्रसव/अवधि पूर्व प्रीमेच्योर रपचर ऑफ नेमब्रेन्स

- 14. प्लेसेंटाल स्थिति, मोटाई, ग्रेंडिंग तथा असामान्यताओं का मूल्यांकन (प्लेसेंटा प्रीवीया, रेट्रोप्लेसेंटाल, हेमरेज, असामान्य एडेरेंस आदि)
- 15. गर्भनाल का मूल्यांकन—उपस्थिति, डालना, नकेल घेरा, वाहिनियों की संख्या तथा ट्रूनाट की उपस्थिति
- 16. पिछले सिजेरियन कटाई के निशानों का मूल्यांकन
- 17. भ्रूण विकास मानदण्डों का निर्धारण भ्रूण भार तथा भ्रूण स्वास्थ्य

18. रंग स्नाव जाँच तथा डूप्लेक्स डापलर अध्ययन

- 19. अल्ट्रासाउंड आधारित प्रक्रियाएँ जैसे चिकित्सीय गर्भपात, बाह्य सिफालिक वर्जन आदि एवं
- 20. निदान संबंधी एडजंक्ट एवं थेरेप्यूटिक इनवेसिव इंटरवेंशन जैसे जीर्ण विलस सेम्पलिंग (सी वी एस)

प्रपत्र — छ (नियम 10 देंखे) सहमति का प्रपत्र (अपवंचन तरीको के लिये)

मैं	
मैं बच्चे में, जो मेरी देखरेख में है । किसी भी प्रकार की असामान्यता (जैसे :- बीमारी/विकृति/खराबी की संभावना का पता लगाने के लिये अपनी इच्छा से प्रिइम प्लांटेशन/पूर्व-प्रसव निदान तकनीक/जांच पद्धतियाँ अपनाना चाहता हूँ।)	
मैं समझता हूँ कि भ्रूण के लिंग के बारे में मेरे पास जानकारी नहीं होगी । मैं समझता हूँ कि इस शपथ का उल्लंघन करने पर मैं दण्ड का उत्तरदायी हूँ जैसा कि पूर्व—प्रसद निदान तकनीक (विनियम तथा दुरूपयोग रोकथाम) अधिनियम, 1994 (1994 का 57) में तथा उसवे अधीन निर्मित नियमावली में निर्धारित है ।	٠ ١
दिनांक : गर्भवती महिला के हस्ताक्षर : स्थान :	
मैंने उपरोक्त तथ्यों के बारे में मरीज को तथा उसके सहयोगी की उसकी / उनकी भाषा में स्पष्ट रूप से समझा दिया है / स्पष्ट कर दिया है(नाम(नामपतापतापतापतापतापतापतापता	
स्त्री रोग विशेषज्ञ / चिकित्सा जैनिटिसिस्ट / रेडियोलोजिस	

दिनांक:

जैनेटिक विलनिक / संस्था का नाम, पता तथा पंजीकरण संख्या

नुहर

फार्म - ज (नियम 9 (5) देखें)

पूर्व-प्रसव नैदानिक तकनीक (विनियम तथा दुरूपयोग रोकथाम) अधिनियम, 1994 के अधीन पंजीकरण करने / रद्द करने के लिए आवेदनों के स्थायी अभिलेख के रखरखाव के लिए प्रपत्र

- 1. क्रम संख्या
- 2. सनुचित प्राधिकारी की फाइल संख्या
- 3. पंजीकरण प्रदान करने के लिए आवेदन प्राप्ति की तारीख
- 4. आवेदक का नाम, पता, फोन / फैक्स इत्यादि
- 5. जैनेटिक परामर्श केन्द्र / जैनेटिक प्रयोगशाला / जैनेटिक विलनिक / अल्ट्रासाउंड विलनिक / इमेजिंग केन्द्र का नाम एवं पता
- 6. सलाहकार समिति द्वारा विचार किए जाने एवं सिफारिश (संक्षेप्त
- में) की तारीख

- 7. आवेदन की स्थिति (दिया गया प्रपत्र ख तथा ग में) रद्द किया गया तथा आदेश अभिलेख जारी करने की तारीख
- 8. आबंटित पंजीकरण संख्या तथा समाप्ति की तारीख
- 9. नवीकरण (नवीकरण की तारीख तथा जब तक नवीकरण किया गया)
- 10. फाईल संख्या जिसमें नवीकरण किया गंया
- 11. अतिरिक्त सूचना, यदि कोई हो

समुचित प्राधिकारी का नाम, पदनाम तथा हस्ताक्षर

प्रपत्र 'क' एक स्थायी अभिलेख है जो समुचित प्राधिकारी की अभिरक्षा में रजिस्टर के रूप (ক) में रखा जाए।

\*साधन काट दिए जाएं, जो लागू न हो ।

नवीकरण पर जैनेटिक परामर्श केन्द्र/जैनेटिक प्रयोगशाला/जैनेटिक विलनिक/ अल्ट्रासाउंड क्लिनिक / इमेजिंग केन्द्र की पंजीकरण संख्या परिवर्तित नहीं होगी। एक नया पंजीकरण संख्या स्वामित्व अथवा प्रबंधन में परिवर्तन के कारण आबंटित किया जाएगा।

पंजीकरण संख्या दो बार आबंटित नहीं की जाएगी।

प्रत्येक जैनेटिक परामर्श केन्द्र/जैनेटिक प्रयोगशाला/जैनेटिक क्लिनिक/ अल्ट्रासाउंड विलिनिक / इमेजिंग केन्द्र को एक फोलियो दिया जाएगा जिसमें प्रपृत्र 'ज़' के अभिलेख के लिए रजिस्टर के दो पृष्ठ होंगे।

अतिरिक्त सूचना के लिए निर्धारित स्थल निलंबन अभिलेख, निरसन, नवीकरण के लिए आवेदन को रद्द करना स्वामित्व/प्रबंधन में परिवर्तन, किसी प्रकार की अन्य कानूनी कार्यवाही इत्यादि के लिए प्रयुक्त किया जाए। रिजस्टर के प्रत्येक फोलियों (2 पृष्ठ) समुचित प्राधिकारी के हस्ताक्षर द्वारा तारीख सहित प्रमाणित होगी तथा प्रत्येक प्रविष्टि भी उसी तरह प्रमाणित होगी। (ঘ)

(छ)

( सुश्री कें0 सुजाता राव ) संयुक्त सचिव, भारत सरकार संख्या 24026/14/2008 पीएनडीटी सैल

पाद : मूल अधिसूचना 01 जनवरी, 1996 के हीएसआर 1(ई) के अनुसार भारत के राजपत्र में प्रकशित की गई।

