

OFFICE OF THE EXECUTIVE ENGINEER
SOUTH EASTERN DIVISION NO.11
D.D.A., VIKAS SADAN, NEW DELHI-23

SPEED POST

No. F5(59)SED-11/DDA/08-09/ 1400

Date: 24/10/08

To,

Sh. P.J. Bhatia,
1-19, Lajpt Nagar-I,
New Delhi.110024.

Sub :- D/ Millennium park along Ring Road between ISBT sarai Kale Khan & Bhairon Road.
SH: C/O S.W.Drain, sewerage and sump well near Vihwa Shati Stupa at Millennium Park.

D/Sir,

Your quoted item rate tender for the above noted work has been accepted on behalf of DDA subject to the terms and conditions given below :

- | | |
|---|--|
| 1. Estimated Cost | Rs. 11,11,688/- (Rs. Eleven lacs eleven thousand six hundred-Eighty eight only). |
| 2. Quoted/Accepted amount. | Rs. 9,96,089/- (Rs. Nine lacs ninety six thousand eighty - Nine only). |
| 3. Contractor %age for the Purpose of Clause 12 | 10.40% below on DSR-2007 |

You are requested to attend this office along with Non judicial Stamp Paper worth Rs.50/- and sign the agreement within seven days from the date of issue of this letter failing which acceptance of your tender is likely to be withdrawn and the earnest money shall be forfeited

You are also directed to contact the Asstt.Engineer-II/SED-11/DDA and start the work at once. Please note that the time allowed for carrying out the work as entered in the tender form shall be reckoned from 10th day after the date of issue of this letter to commence the work.

The time allowed for execution of the work will be 2(Two) month. only

Copy to:

4. CE,SEZ,DDA, 2. SE,CC-16,DDA. 3.F.O. to CE,SEZ,DDA 4.P.A.O.(E.W)DDA.5. A.O(W)-I
6. Income Tax Officer, Contractor Circle,ITO,N.Delhi. 7 All EEs DDA, 8.All AEs ,SED-11,DDA. 9 AE(P),SED-11 10. The Labour Commissioner, Rajpur Road,N.Delhi. 11. A.O,CAU,SEZ,DDA. 12. The Deputy Commissioner (Work contract)Bikri Kar Bhawan, I P Estate,New Delhi. 13. For Agreement. 14. AE-II,SED-11 along with copy of schedule, with the direction to report to this office within 10 days whether contractor has taken over the site for execution. 15. Cashier,SED-11 16. EE(QC), 17. Security officer, DDA, Vikas Sadan. 18. dda tender @dda.org.in.& dirysystem dda.org.in.

Executive Engineer
SED - 11 : DDA
22/10/08

Executive Engineer
22/10/08

ESSH. Cost Rs 11,11,688-

SCHEDULE OF QUANTITIES

NAME OF WORK : D/O MILLENNIUM PARK ALONG RING ROAD BETWEEN ISBT SARAI KALE KHAN & BHAIROON ROAD.

SH: C/o S.W drain, sewerage and sumpwell near Vishwa Shanti Stupa at Millennium Park.

S.No.	Description of Item	Qty	Unit	Rate(Rs.)	Amount(Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead 50 m. (a) All kinds of soil.	525.60	Cum <i>As per survey only</i>	Rs 70000	Rs 36,792000
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (a) 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregate 40 mm nominal size)	44.79 <i>As per survey</i>	Cum <i>As per survey</i>	Rs 160000 <i>As per survey</i>	Rs 71,664000 <i>As per survey</i>
3.	Brick work with F.P.S. Bricks of class designation 75 in foundation and plinth in: (a) Cement Mortar 1:4 (1 cement: 4 coarse sand)	165.83	Cum <i>As per survey</i>	Rs 200000 <i>As per survey</i>	Rs 33,166000 <i>As per survey</i>
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (a) 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	9.00	Cum <i>As per survey</i>	Rs 300000 <i>As per survey</i>	Rs 2700000 <i>As per survey</i>

Cont P-2

Rs 4,67,1162

5.	12 mm cement plaster 1:3 of mix (1 cement: 3 coarse sand) finished with a floating coat of neat cement	553.50	Sqm As Ninety only	Rs 90=0	Rs 49,815~
6.	P/F in position of drain Covers (SERC) Medium Duty as per required size complete as direction of Engineer- in-charge	306.00	Sqm. Above thousand only	Rs 1000=0	Rs 3,06,000=0
7.	Providing and laying in position Specified grade of reinforced cement concrete excluding the cost of centering. Shuttering, finishing and reinforcement- All work up to plinth level: a) 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size	16.51	Cum As Three thousand three hundred only	Rs 3300=0	Rs 54,483=0
8.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. a) Thermo-mechanically treated bars.	1651.00	Kg As Forty five hundred only	Rs 45=0	Rs 74,295~
9.	Centering and shuttering including strutting, propping etc. and removal of form for: a) Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc. b) Suspended floors, roofs landings, balconies and access platform.	94.00 6.00	Sqm As One hundred twenty only Sqm	Rs 120=0	Rs 11,280~ Rs 9,63,709~

Contd 0-3.

SPEED POST

OFFICE OF THE EXECUTIVE ENGINEER
SOUTH EASTERN DIVISION NO.11
D.D.A., VIKAS SADAN, NEW DELHI-23

No. F5(54)SED-11/DDA/08-09/ 1399

Date: 24/10/08

To,

M/s Arch Constn.,
G-8, Abdul fazal Encl-II,
Okhla, New Delhi-110025

Sub :- D/O Millennium park along Ring Road between ISBT Sarai Kale Khan & Bhairon Road.
SH : P/L water Supply line at Shanti Stupa.

D/Sir,

Your quoted item rate tender for the above noted work has been accepted on behalf of DDA subject to the terms and conditions given below :

- | | |
|---|---|
| 1. Estimated Cost | Rs. 2,98,427/- (Rs. Two lacs ninety eight thousand - Four hundred twenty seven only). |
| 2. Quoted/Accepted amount. | Rs. 3,40,004/- (Rs. Three lacs forty thousand four only). |
| 3. Contractor %age for the Purpose of Clause 12 | 13.93 % above on DSR-2007 |

You are requested to attend this office along with Non judicial Stamp Paper worth Rs.50/- and sign the agreement within seven days from the date of issue of this letter failing which acceptance of your tender is likely to be withdrawn and the earnest money shall be forfeited

You are also directed to contact the Asstt.Engineer-II/SED-11/DDA and start the work at once. Please note that the time allowed for carrying out the work as entered in the tender form shall be reckoned from 10th day after the date of issue of this letter to commence the work.

The time allowed for execution of the work will be 2(Two) months only

Copy to:

5. CE,SEZ,DDA, 2. SE,CC-16,DDA . 3.F.O. to CE,SEZ,DDA 4.P.A.O.(E.W)DDA.5. A.O(W)I,DDA.
6. Income Tax Officer, Contractor Circle,ITO,N.Delhi. 7 All EEs DDA, 8.All AEs ,SED-11,DDA. 9 AE(P),SED-11 10. The Labour Commissioner, Rajpur Road,N.Delhi. 11. A.O,CAU,SEZ,DDA. 12. The Deputy Commissioner (Work contract)Bikri Kar Bhawan, I P Estate,New Delhi. 13. For Agreement. 14. AE-II,SED-11 along with copy of schedule, with the direction to report to this office within 10 days whether contractor has taken over the site for execution. 15. Cashier,SED-11 16. EE(QC), 17. Security officer, DDA, Vikas Sadan. 18. dda tender @dda.org.in.& dirysystem dda.org.in.

Executive Engineer.

SED-11/DDA

Executive Engineer

SCHEDULE OF QUANTITIES

NAME OF WORK : D/O MILLENNIUM PARK ALONG RING ROAD BETWEEN ISBT SARAI KALE KHAN & BHAIRON ROAD.

SH : Providing and laying Water Supply line at Shanti Stupa.

S.No.	Description of Item	Qty	Unit	Rate(Rs.)	Amount(Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead 50 m. (a) All kinds of soil.	22.29	Cum	Rs 140 - 1 footy only	Rs 3121 -
2.	Providing and Laying in position mixer of good earth and cement in the proportion of 1:5 (1 cement: 5 good earth) up to Plinth level complete as per direction of Engineer-in-charge.	16.16	Cum	Rs 2200 - two hundred and twenty	Rs 35552 -
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (a) 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregated 40 mm nominal size)	2.31	Cum	Rs 2400 - two thousand four hundred only	Rs 5544 -
4.	Brick work with F.P.S. Bricks of class designation 75 in foundation and plinth in: a) Cement Mortar 1:4 (1 cement: 4 coarse sand)	4.80	Cum	Rs 2500 - two thousand five hundred only	Rs 12,000 -
5.	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5mm nominal size).	3.43	Sqm	Rs 160 - Sixty only	Rs 549 -
6.	Brick work with F.P.S. Bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in: a) Cement mortar 1:4 (1 cement : 4 coarse sand)	11.00	Cum	Rs 2700 - two thousand seven hundred only	Rs 29,700 -

Cont P.2 -

Rs 56,466 -

7.	Centering and shuttering including strutting, propping etc. and removal of form for: a) Suspended floors, roofs landings, balconies and access platform.	13.58	Sqm Two hundred only	Rs 80000	Rs 2716-
8.	Reinforced cement concrete work in beam, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stones aggregated 20 mm nominal size).	1.54	Cum Four hundred five hundred only	Rs 4500-	Rs 6930-
9.	12 mm cement plaster of mix: (a) 1:4 (1 cement: 4 fine sand)	67.00	12 Sqm one hundred only	Rs 100-	Rs 6700-
10.	15 mm cement plaster on the rough side of single or half brick wall of mix: a) 1:6 (1 cement : 6 fine sand)	41.00	Sqm one hundred only	Rs 100-	Rs 4100-
11.	12 mm cement plaster of mix: (a) 1:4 (1 cement: 4 coarse sand)	7.92	18 Sqm hundred only	Rs 350-	Rs 6300-
12.	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	1.20	16 Sqm hundred fifty only	Rs 250-	Rs 3000-
13.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. (a) 40 mm thick with 20 mm nominal stone aggregate.	12.00	Sqm. Two hundred fifty only	Rs 250-	Rs 41250-

Cont 0-3

<p>14. Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. a) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.</p>	<p>50.00</p>	<p>Kg (As severity order)</p>	<p>Rs 70000</p>	<p>Rs 350000</p>
<p>15. Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators side/top/centre hung with beading and all members such as K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted with 15x3mm lugs, 10 cm long, embedded in cement concrete blocks 15x10x10cm of 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregated 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of hinges, pivots, float glass panes with glazing clips and special metal sash putty of approved make and a priming coat of approved steel primer excluding the cost of metal beading and other fittings except necessary hinges or pivots complete as per approved design.</p>	<p>27.00</p>	<p>Kg (As two hundred quantity for order)</p>	<p>Rs 225000</p>	<p>Rs 6,02500</p>
<p>16. Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part-I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or crows bands and face veneers on both faces of shutters: a) 35 mm thick including ISI marked stainless Steel butt hinges with necessary screws.</p>	<p>3.15</p>	<p>Sqm (As one hundred size for order)</p>	<p>Rs 1100000</p>	<p>Rs 3,465000 Rs 124164000</p>

Cont P-4-

17.	Finishing walls with waterproofing cement paint cement paint of required shade: (a) New Work (Two or more coats applied @3.84 kg/10 sqm).	75.00	1/4 Sqm Rs 4000	Rs 300000
18.	White washing with lime to give an even shade a) New Work (three or more coats)	12.00	1/4 Sqm Rs 10000	Rs 12000
19.	Distemping with dry distemper of approved brand and manufacture (two or more coats) and of required shade on new work, over and including priming coat of whitening to give an even shade.	41.00	1/4 Thirty Sqm Rs 3000	Rs 123000
20.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: b) Two or more coats on new work	8.50	1/4 Sqm Rs 4000	Rs 34000
21.	Excavating trenches of require width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m including getting out the excavated soil, and then returning the soil as required, in lyers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering, etc. and disposing or surplus excavated soil as directed, within a lead of 50 m: [Add kind of soil] (a) Pipes, cables etc. exceeding 80 mm dia but not exceeding 300 mm dia.	100.00	Mtr Rs 15000	Rs 1500000
22.	Providing & Laying S&S Centrifugally cast (spun) iron pipes (class LA) conforming to IS - 1536 a) 100 mm dia. pipe	100.00	Mtr Rs 800000	Rs 80000000
23.	Providing & Laying S&S C.I. standard specials such as tees, bends, collars, tapers, caps etc. (Heavy class) a) Up to 300 mm dia	1.00	Quintal Rs 310000	Rs 22695000

Cont P-5

24.	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): a) 100 mm diameter	1 No.	Each	Rs 260000	Rs 260000
25.	Supplying pig lead at site of work	0.50	Quintal <i>Rs 7000 per quintal</i>	Rs 350000	Rs 350000
26.	Constructing masonry Chamber 60x60x75 cm, inside with 75 class designation brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm. top diameter, 160 bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement complete as per standard design: a) With F.P.S. Bricks	1 No	Each <i>Rs 400000</i>	Rs 400000	Rs 400000
27.	Providing & Fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work (a) 40 mm dia nominal bore	355.00	Metre <i>Rs 25000</i>	Rs 8925000	Rs 8925000
28.	Painting G.I. pipes and fittings with two coats of anticorrosive bitumetic paint of approved quality (a) 40 mm diameter pipe	355.00	Metre <i>Rs 10000</i>	Rs 3550000	Rs 3550000
29.	Providing and filling sand of grading zone V or coarser grade all round G.I. Pipes in external work. a) 40mm diameter pipe	355.00	Metre <i>Rs 30000</i>	Rs 10650000	Rs 10650000

NOTE :-

CEMENT :- 8.30 M.T CR. 517500 Per M.T shall be *Rs three lacs forty thousand four only*
issued from any D.D. A Store Delhi | N. Delhi

Total Rs 3,40,00,000

Executive Engineer
South Eastern Division-XI
D.D. Vikas Sadan, N. Delhi
22/10/18

OFFICE OF THE EXECUTIVE ENGINEER
SED-11/DDA/VIKAS SADAN I.N.A/NEW DELHI

No. F.5 (58) SED-11/A/DDA/08-09 / 1407

Dated: 29/10/08

To,

Sh. Harinder Singh
G, Extension I, Kirti Nagar,
New Delhi - 110015.

**Sub: D/o Millennium Park along Ring Road between ISBT Sari Kale Khan & Bhairon Road.
SH: Const. of Pedestrian Paths at Shanti Stipua.**

D/Sir,

Your quoted item rate tender for the above noted work has been accepted on behalf of DDA subject to the terms and condition given below:-

- | | | |
|---|---|--|
| 1. Estimated cost | : | Rs. 9,42,678/- (Rs. nine lacs forty two thousand six hundred seventy eight only) |
| 2. Quoted/Accepted amount. | | Rs. 9,77,449/- (Rs. nine lacs seventy seven thousand four hundred forty nine only) |
| 3. Contractor's %age for the purpose of clause-12 | | 3.69% above on DSR-2007. |

You are requested to attend this office alongwith non judicial stamp paper worth Rs. 50/- and sign the agreement within seven days from the date of issue of this letter failing which acceptance of your tender is likely to be withdrawn and the earnest money shall be forfeited.

You are also directed to contact the Asstt. Engineer.II/SED-11 and start the work at once. Please note that the time allowed for carrying out the work, as entered in the tender form shall be reckoned for 10th day after the date of issue of this letter to commence the work.

The time allowed for execution of the work will be 2 months.

Saravjit Singh
Executive Engineer
SED-11/DDA
29/10/08

Copy to:-

1. CE (SEZ) DDA.
2. SE/CC-16/DDA.
3. FO to CE/SEZ.
4. PAO(EW).
5. A.O(W)I.
6. Income tax Officer, Contr. Circle ITO, N. Delhi.
7. All EEs/DDA/
8. All AEs/SED-XI
9. AE (P)/SED-XI.
10. The Labour Commissioner(Work contract) Bikri Kar Bhawan I.P. Estate, New Delhi.
13. For agreement, SED-XI.
14. AE.II/SED-XI, DDA alongwith schedule with the direction to report to this office with ten days whether the contractor has taken over the site for executing the work..
15. Cashier, SED-XI.
16. EE (QC) DDA.
17. Security Officer, Viikas Sadan.
18. DDA tender @ dda.org.in & dairystem dda.org.in..

Saravjit Singh
Executive Engineer
SED-11/DDA
29/10/08

SCHEDULE OF QUANTITIES

NAME OF WORK : D/O MILLENNIUM PARK ALONG RING ROAD BETWEEN ISBT SARAI KALE KHAN & BHAIRON ROAD.

SH : Construction of Pedestrian paths at Shanti Stupa.

S.No.	Description of Item	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1.	Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. a) In grating, frams, guard bar, ladder, railing, brackets gates & similar work.	1470.00	Kg.	Rs 70/- <i>(As Seventy only)</i>	Rs 1,02,900/-
2.	Proving and laying 60 mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50 mm thick compacted bed of course sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge.	1141.50	Sqm	Rs 390/- <i>(As three hundred ninety only)</i>	Rs 4,45,185/-
3.	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement: 3 coarse sand) including making joints with or without groves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	45.50	Cum	Rs 4500/- <i>(As four thousand five hundred only)</i>	Rs 2,04,750/-

Rs 7,52,835/-

ESSA. 657- K 942 678/2

<p>4. Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (a) 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregated 40 mm nominal size)</p>	<p>114.00</p>	<p>Cum (One hundred eight hundred only)</p>	<p>Rs 1800-00</p>	<p>Rs 205200-</p>
<p>5. Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be leveled and neatly dressed: (a) All kinds of soil</p>	<p>1142.00</p>	<p>100 Sqm</p>	<p>Rs 1700-00 (One hundred seven hundred only)</p>	<p>Rs 171400-</p>

Total Rs 977448-00

NOTE: Cement 15.00 M.T @ Rs. 5175=00 Per M.T
Should be issued from any D.D.A Store
Delhi (New Delhi)

(B Nil has seventy seven hundred-
four hundred forty nine only)

S. Anand
Executive Engineer
South Eastern Division-XI
O.D.A. Vikas Sadan, N Delhi
29/11/18